

Biological Services Program

FWS/OBS-80/37

December 1980

*Catalog of California
Seabird Colonies*



Bureau of Land Management
Fish and Wildlife Service

U.S. Department of the Interior

From the collection of



**International
Bird Rescue
Research Center**

Cordelia, California

in association with

z n m
o Preinger
v L Library
t p

San Francisco, California
2006

Program was established within the U.S. Fish and Wildlife
Information and methodologies on key environmental issues
resources and their supporting ecosystems. The mission of

and Wildlife Service in its role as a primary source of
national fish and wildlife resources, particularly in respect
to assessment.

to present information that will aid decisionmakers in the
solution of problems associated with major changes in

biological information and evaluation for Department of
at programs, such as those relating to energy develop-

The Biological Services Program is intended for use in the
process to prevent or minimize the impact of development
activities and technical assistance services are based on an
evaluation of the decisionmakers involved and their infor-
mation of the state of the art to identify information gaps
and is a strategy that will ensure that the products pro-
duced are useful.

in the following areas: coal extraction and conversion;
oil and oil shale development; water resource analysis,
Western water allocation; coastal ecosystems and Outer
Continental Shelf systems inventory, including National Wetland
analysis, and information transfer.

The program consists of the Office of Biological Services in
charge of overall planning and management; National
Coastal Ecosystems Team central scientific and technical expertise and arrange
studies with states, universities, consulting firms, and
industry as a link to problems at the operating level; and staff at
research facilities, who conduct inhouse research studies.

son and G.S. Lester. 1980. Catalog of California
of Interior, Fish and Wildlife Service, Biological
571 p.

Questions or requests for this publication should be directed to:

Information Transfer Specialist
National Coastal Ecosystems Team
U.S. Fish and Wildlife Service
NASA - Slidell Computer Complex
1010 Gause Boulevard
Slidell, Louisiana 70458

Catalog of California Seabird Colonies

by

Arthur L. Sowls, Anthony R. DeGange, Jay W. Nelson and Gary S. Lester

Project Officer

Editorial Assistants

Mary B. Evans
Cherry Keller

Jay F. Watson
U.S. Fish and Wildlife Service
Lloyd 500 Building, Suite 1692
500 N.E. Multnomah St.
Portland, Oregon 97232

Field Assistants

William E. Rodstrom
Margaret A. Stewart

CONTRIBUTORS

The following people were involved in surveys of seabird colonies covered by this report. Without their efforts, this catalog would not have been possible.

| | | | |
|-----------------------|---------------------|----------------------|---------------------|
| Steve Abbore | Anthony R. DeGange | Paul R. Kelly | Gordon Reetz |
| David G. Ainley | Craig Denson | Gary S. Lester | Jack G. Reynolds |
| Daniel W. Anderson | Richard A. Erickson | Ronald A. LeValley | William E. Rodstrom |
| Jonathan L. Atwood | Michael Evans | David B. Lewis | Fred C. Sibley |
| Douglas Ayers | Bill Everett | T. James Lewis | Fred Sorensen |
| Alan Baldrige | Alan K. Fukuyama | David A. Manuwal | Arthur L. Sowls |
| Linda Belluomini | Ron Garrett | Barbara Massey | Steven M. Speich |
| Carl Benz | Robert E. Gill | Stephen H. Morrell | Margaret A. Stewart |
| Lynn C. Berner | Sharon Goldwasser | Tim McKay | Gary Strachan |
| Lawrence C. Binford | Franklin Gress | Maria Joyce Nakagawa | Craig Strong |
| Robert J. Boekelheide | Stanley W. Harris | Maura Naughton | Laurie Stuart |
| Kenneth T. Briggs | Thomas E. Harvey | Jay W. Nelson | Philip Unitt |
| James R. Chambers | Valerie Hironaka | John S. Nelson | Daniel H. Varoujean |
| Howard L. Cogswell | Harriet R. Huber | Audrey Newman | Michael C. Vasey |
| Paul Collins | George L. Hunt, Jr. | Timothy O. Osborne | Jay F. Watson |
| Elizabeth Copper | Ron Jameson | Robert L. Pitman | Kathy Winnett |
| Mary Ann Danielson | Ronald M. Jurek | Mark Rauzon | |

This study was funded by the Bureau of Land Management, Pacific Outer Continental Shelf Office, under Memorandum of Understanding No. AA551-MU9-13.

Published by

Coastal Ecosystems Project
Office of Biological Services
Fish and Wildlife Service
U.S. Department of the Interior
Washington, DC 20240

ACKNOWLEDGMENTS

A project of this magnitude would not have been possible without the assistance of many individuals and organizations. Jay F. Watson, our Project Officer, was paramount in managing this study and provided us with encouragement and advice throughout the project. Bill Rodstrom's able field assistance during the 1979 field season played a principal role in the completion of this project. He was responsible for data collection for much of the north coast. Margaret Stewart's help during the 1980 field season and with the preparation of this report were invaluable.

Gary Rankel of the U.S. Fish and Wildlife Service in Arcata, California graciously provided us with office space, a congenial work atmosphere, and access to a copy machine. Paul Springer, also of the U.S. Fish and Wildlife Service in Arcata, kindly provided us with space to store our equipment. The following organizations loaned us equipment for which we are grateful: U.S. Fish and Wildlife Service, Anchorage, Alaska and Sacramento, California; San Francisco Bay National Wildlife Refuge; and Washington State Fisheries Cooperative Unit.

Data from many investigators were incorporated into this report. Without their cooperation this project would not have been possible. We thank all of those people listed on the title page who were involved in these recent collections of data. Special thanks in this regard go to Dave Ainley, Dan Anderson, Jonathan Atwood, Bob Boekelheide, Ken Briggs, Alan Craig, Elizabeth Copper, Frank Gress, Stan Harris, George Hunt, Jr., Ron Jurek, Paul Kelly, Tim Osborne, and Dan Varoujean.

We thank the many individuals of the California State Park System and the California Department of Fish and Game for assistance in many ways. John Warrick, of the Pacific Gas and Electric Company, arranged access to the Diablo Nuclear Power Plant and Jim Chambers assisted us with our surveys there and made his field notes available to us. Several aerial surveys were done with the cooperation of the U.S. Coast Guard. We would particularly like to acknowledge Lt. Sutter Fox of the Arcata Air Station for arranging logistic support.


Jim Bartonek, Ron LeValley, Paul Springer, and Mark Strong reviewed an early draft of this report and their suggestions were most helpful. Dave Ainley, Dan Anderson, George Hunt and Stan Harris reviewed the final draft and added many useful refinements.

We are much indebted to Linda Parkinson and Margaret Stewart who donated several of the drawings which adorn the pages of this catalog. Allen Brooks' drawing of the Marbled Murrelet was provided courtesy of The Murrelet, A Journal of Northwestern Ornithology and Mammalogy. Help with maps was provided by Richard Huxley and Lorraine Strong. Dave Van de Mark printed our photographs. Drafts of this report were typed by Marla Collins and Bernadene Logan, and typesetting was done by *Kathy Amyotte and Jeannie Jacobsen*.

Finally, we thank the Bureau of Land Management for sponsoring this project and in particular Gordon Reetz of the Pacific Outer Continental Shelf Office.

TABLE OF CONTENTS

| | |
|---|-----|
| INTRODUCTION | 1 |
| THE NATURE OF SEABIRDS | 1 |
| THREATS TO SEABIRDS | 2 |
| METHODS | 7 |
| DISCUSSION | 11 |
| SPECIES ACCOUNTS: | |
| Fork-tailed Storm-Petrel | 20 |
| Leach's Storm-Petrel | 22 |
| Ashy Storm-Petrel | 24 |
| Black Storm-Petrel | 26 |
| Brown Pelican | 28 |
| Double-crested Cormorant | 30 |
| Brandt's Cormorant | 32 |
| Pelagic Cormorant | 34 |
| Black Oystercatcher | 36 |
| Western Gull | 38 |
| Common Murre | 40 |
| Pigeon Guillemot | 42 |
| Marbled Murrelet | 44 |
| Xantus' Murrelet | 46 |
| Cassin's Auklet | 48 |
| Rhinoceros Auklet | 50 |
| Tufted Puffin | 52 |
| MAPS AND TABLES: | |
| How to Use Maps and Tables | 56 |
| Map Index | 57 |
| Section 325, Eureka | 58 |
| Section 379, Ukiah | 106 |
| Section 404, Santa Rosa | 142 |
| Section 429, San Francisco | 180 |
| Section 454, Monterey | 212 |
| Section 477, San Luis Obispo | 236 |
| Section 501, Santa Maria | 260 |
| Section 502, Los Angeles | 282 |
| Section 524, Long Beach | 298 |
| Section 525, Santa Ana | 318 |
| Section 545, San Diego | 326 |
| REFERENCES | 341 |
| APPENDIX A: Data Archives | 351 |
| APPENDIX B: Observation Points for Seabird Colonies | 355 |
| APPENDIX C: Index of California Seabird Colonies | 366 |



INTRODUCTION

This catalog is a summary of the location, size, and species composition of seabird colonies along the California coast. It documents more than 260 nesting areas with a total estimated population of nearly 700,000 birds.

Our study was sponsored by the Bureau of Land Management, Pacific Outer Continental Shelf Office, to fulfill requirements of the National Environmental Policy Act of 1970. The information will help resource planners evaluate possible effects on seabirds of proposed oil and gas leasing. Detailed information on seabird distribution and abundance will be useful to coastal planners, scientists, and amateur bird-watchers. For this reason, we have included a section on threats to seabirds and appendices on the archiving of our field data (Appendix A) and viewpoints from which several colonies can be observed without causing disturbance (Appendix B).

Seventeen species of seabirds from six families are discussed in this report. These include four species of storm-petrels (Fork-tailed, Leach's, Ashy, and Black), one species of pelican (Brown Pelican), three species of cormorants (Brandt's, Double-crested, and Pelagic), one species of shorebird (Black Oystercatcher), one species of gull (Western Gull), and seven species of alcids (Common Murre, Pigeon Guillemot, Marbled Murrelet, Xantus' Murrelet, Cassin's Auklet, Rhinoceros Auklet, and Tufted Puffin). In addition to population information in the maps and tables, species accounts discuss aspects of the natural history of each of the above species, emphasizing the California populations.

Population information for six additional species which could also be affected by coastal development and pollution has been included in the maps and tables. All the known locations of Least Tern (*Sterna albifrons*) colonies are identified in this catalog, although yearly surveys by the California Department of Fish and Game will soon render this data obsolete. The catalog also identifies coastal breeding sites of the Caspian Tern, (*Sterna caspia*), Forster's Tern (*Sterna forsteri*), and Black Skimmer (*Rynchops niger*), species which also breed inland. The single known California nesting location of the Elegant Tern (*Sterna elegans*) in San Diego Bay is also identified. Finally, locations of known Heermann's Gull (*Larus heermanni*) nest sites are

indicated, although this species was never recorded breeding in California until 1980, and cannot be considered part of the normal breeding avifauna. All six species, except Heermann's Gulls and some Least Terns, nest and feed primarily in enclosed bays and estuaries. Our inclusion of this information is intended only to supplement other sources of information on these species.

It must be recognized that this report only documents nesting sites. Large numbers of non-nesting birds migrate through coastal California in spring and fall and many additional birds winter along the coast. These include shearwaters from as far away as New Zealand and Tasmania, many kinds of shorebirds and waterfowl from arctic Alaska and Canada, pelicans and gulls from Mexico, and inland nesting birds such as grebes and small gulls. Oil spills and other disturbances could severely affect these populations. Seabirds are truly an international resource and must be managed as such.

THE NATURE OF SEABIRDS

Seabirds evolved in an environment free of most of the competition and predators faced by terrestrial birds. They have evolved into birds with long lifespans, low adult mortality rates, relatively late sexual maturity, and small clutch sizes. Lifespans of seabirds are not exactly known, but they are certainly long in comparison to most terrestrial birds. Records exist of individuals of several species of seabirds reaching more than 20 and even 30 years of age (Bergstrom 1952, Clapp and Sibley 1966, Clapp and Hackman 1968, Graham 1980). Long lifespans in a species imply a low annual rate of adult mortality, and annual mortality rates below 20 percent are common in seabirds (Ashmole 1971, Richdale and Warham 1973). Some albatrosses may have annual mortality rates as low as three percent (Lack 1954). Many passerines, at the other extreme, have annual mortality rates from 40 to 70 percent (Lack 1954). If mortality rate remains constant with increasing age, large seabirds with very low annual mortality rates may attain a breeding life of 50 years or more (Ashmole 1971). In addition, recruitment of birds into the breeding population is often slow and delayed. Before attaining maturity, many seabirds spend at least 2 years, and more commonly 3, 4, 5, and up to 9 years as non-breeders (Ashmole 1971). Long

breeding lives, low recruitment rates, and delayed maturity could delay the effects of successive breeding failures on breeding populations for several years.

The clutch size of seabirds is usually low. Storm-petrels and other procellariiformes lay one egg, alcids lay one or two eggs, and pelicans and gulls lay one to three eggs. Cormorants may lay up to seven eggs, though clutches of four or five are more common. By contrast, many land birds lay from 7 to 15 eggs and many produce two broods each year.

Because seabirds reproduce at a slow rate but over a long lifetime, the effects of an oil spill or other disaster and the potentially more dangerous effects of longterm chronic pollution, habitat loss, and other disturbances demand careful and frequent monitoring of seabird populations.

Seabirds tend to be of two types: those which spend most of their time near shore (including cormorants, pelicans, and most gulls), and those which come to land only during the breeding season or sometimes intermittently during other times of the year (including storm-petrels and alcids). Of the truly pelagic seabirds, several are nocturnal on the breeding grounds; they will enter or leave their colonies only at night. In California, the four storm-petrels, Marbled and Xantus' Murrelets, Cassin's Auklets, and, to a lesser degree, Rhinoceros Auklets are nocturnal on their breeding grounds.

The seabird colony is the most critical habitat for seabirds because reproduction and thus continuation of species depend on these sites. Here the population will reach its annual low, just before young are hatched, and its annual high, just after hatching. At other times of the year, seabirds may be able to avoid problems such as disruption of food supplies, and perhaps even large oil spills, simply by flying somewhere else, but for successful nesting they are limited to the area around the colony.

In the following section, we discuss some of the problems which face seabirds. We hope an awareness of these will alert coastal planners to the kinds of problems that may be encountered.

THREATS TO SEABIRDS

OIL

Oil exploration, production, and transport are important industries along the coast of California. A federal outer continental shelf

leasing program by the Bureau of Land Management offshore of California was initiated in 1963. Areas in the Santa Barbara Channel were leased in 1966 and 1968, and other sections of the Southern California Bight were leased in 1975. Five new oil lease zones were identified offshore of central and northern California in 1977. The southernmost of these tracts is scheduled for sale in 1981.

Resource planners must be aware of potential hazards to seabirds that may be caused by oil development. There is ample literature documenting the lethal effects of oil on marine birds, including papers by Bourne (1968, 1970), Clark (1969), Clark and Kennedy (1968), Croxall (1975), Manuwal (1978), and many others. Vermeer and Vermeer (1974) reviewed the literature appearing between 1922 and 1973 on the effects of oil on birds.

One effect of oil on seabirds is destruction of the insulating properties of feathers. An oiled bird compensates for the loss of insulation and subsequent loss of heat by increasing its metabolic rate, using stored energy (Hartung 1967). If the bird's energy balance is not restored, energy reserves are soon depleted and death from hypothermia results. Oiled birds are unable to maintain their energy reserves because they cannot or will not feed.

Marine birds may also ingest oil while drinking, feeding, and especially when oiled individuals attempt to preen their soiled plumage. Ingestion of oil may hinder the absorption of



A Common Murre fouled with oil on a Pacific Coast beach. Photo by Duncan McDonald

water across the intestinal wall (Crocker et al. 1974). Ingested oil may also affect reproductive success. Grau et al. (1977) showed that ingested oil altered the yolk structure of recently laid Japanese Quail eggs (*Coturnix coturnix*) and greatly reduced their hatchability. These authors are continuing their studies on the Farallon Islands with Western Gulls and Cassin's Auklets (Ainley et al. 1979). Hartung (1965) demonstrated that ingested lubricating oil reduces the egg laying rate of captive Mallards (*Anas platyrhynchos*). Oil applied to the exterior of eggs also reduces hatching success. This has been observed in experiments performed on the eggs of Mallards (Hartung 1965), Common Eiders (*Somateria mollissima*, Albers and Szaro 1978), Laughing Gulls (*Larus atricilla*, King and Lefever 1979), Glaucous-winged Gulls (*Larus glaucescens*, Patten and Patten 1977), and Great Black-backed Gulls (*Larus marinus*, Coon et al. 1979, McGill and Richmond 1979).

The species vulnerable to oil spills are those which are most restricted to an aquatic environment, particularly loons, grebes, seaducks, and alcids, although some variation will occur depending on the season. We have discussed these aspects of each species' life history in the species accounts.

In California, three well-documented oil spills which killed large numbers of birds have occurred: the Santa Barbara oil spill of 1969 (Straughan 1971) and the San Francisco oil spills of 1937 and 1971 (Aldrich 1938, Moffitt and Orr 1938, Smail et al. 1972). All three spills occurred in the winter which greatly influenced the species of birds killed. Wintering Western Grebes (*Aechmophorus occidentalis*) and loons suffered the greatest mortality in the Santa Barbara oil spill. Western Grebes were similarly affected in the 1971 San Francisco oil spill and to a lesser extent in the 1937 spill. Common Murres and wintering scoters (*Melanitta* spp.) also experienced heavy mortality from oil in the San Francisco oil spills. Common Murres breed in California and appear in the near-shore zone periodically in the winter.

CHRONIC POLLUTION AND TOXIC CHEMICALS

Large oil spills are well publicized, but low-level chronic oil pollution, small oil spills, and the build-up of other pollutants probably pose a more serious long-term threat to seabirds. Pollutants of particular concern, other than oil, include

pesticides and their residues, heavy metals, polychlorinated biphenyls and other by-products of industry, and plastic particles.

Most seabirds are long-lived and feed at or near the tops of their food chains. Certain pollutants such as DDT and its principal metabolite DDE are stored in the body and concentrate in increasing amounts at each higher level in the food chain. When concentrations of these chemicals reach sufficiently high levels, reproduction may be impaired or death may occur. Seabirds constitute one of the most conspicuous and easily studied components of the marine ecosystem, so their reproductive failure or death may be our first indication that the environment contains dangerous quantities of toxic chemicals. In Minamata, Japan, high levels of mercury in effluent from a vinyl chloride plant were first manifested in the deaths of fish-eating birds. This was followed by the tragic deaths of many humans (Kurland et al. 1960). The effects of pollutants on seabirds can be monitored by close study and may serve as a valuable indicator of the health of marine ecosystems. For this reason alone, continued study of certain seabird populations will be useful.

The effects of chlorinated hydrocarbon pesticides and their residues and polychlorinated biphenyls on birds are well documented (Peakall 1970, 1975). These contaminants reduce breeding success by decreasing fertility, reducing the viability of eggs and chicks, and interfering with calcium deposition, resulting in the production of thin eggshells which may later break. Physical abnormalities have also been associated with organochlorine residues (Hays and Riseborough 1972).

In California the Brown Pelican has become a symbol in the fight against pollution of the world's oceans. The reproductive success of Brown Pelicans was seriously reduced by the presence of DDT, DDE, and related chemicals in the ocean off southern California. Because of eggshell thinning, most eggs were broken before the young hatched and only 12 chicks fledged out of 2,368 nesting attempts in 1969, 1970, and 1971 (Gress et al. 1973). Double-crested Cormorants suffered a similar decrease in reproductive success in southern California and Mexico (Gress et al. 1973). These reproductive failures were traced to DDT dumped into the Los Angeles sewer system by a chemical manufacturing plant. Since April, 1970, these wastes have been deposited in a landfill and DDT input into the ocean has declined significantly (Anderson et al. 1975). Reproductive

success of both Brown Pelicans and Double-crested Cormorants has improved dramatically and the population of Brown Pelicans may be on its way to recovery (Anderson et al. 1975).

Chlorinated hydrocarbons and polychlorinated biphenyls have also been linked with shell thinning of Ashy Storm-Petrel and Common Murre eggs on the Farallon Islands (Coulter and Riseborough 1973, Gress et al. 1973). Many other populations of seabirds in North America have been similarly affected by these contaminants.



This Brown Pelican egg was broken under the weight of incubating adults as a result of thin eggshells from pesticide contamination. Photo by Frank Gress.

Plastic particles are commonly found in the stomachs and gizzards of seabirds collected for scientific study (Baltz and Morejohn 1976, Rothstein 1973). It is likely that seabirds mistake these for larval fish, eggs, or other foods floating on the ocean surface. These particles enter the environment by physical breakdown of the huge quantities of plastics which are dumped into the world's oceans each year.

The physical presence of plastic particles may affect the health of birds. Particles which accumulate in the gizzard probably are not as effective as the pebbles normally used to grind up food. Fortunately, plastics are nearly chemically inert and are unlikely to affect birds the way toxic chemicals do. More research on this topic and concern about the "garbage can" attitude we have toward our oceans are needed.

FISHERIES

Commercial fisheries can affect seabirds in three primary ways: 1) birds drown in gillnets, 2) offal from fishing boats provides an additional

food supply for certain seabird species, and 3) extensive fisheries deplete some seabird prey species. Depletion of prey fishes presently seems to be the major fisheries-related threat to seabirds in California. Gillnet drowning and offal discharge have dramatically affected seabirds in other parts of the world.

Seabirds drown in gillnets when they are caught while diving or plunging into the water for food. The alcids, which dive to feed, and shearwaters (*Puffinus* spp.), which plunge into the ocean to feed, are among the most vulnerable of seabirds. The salmon driftnet fisheries of the North Atlantic and North Pacific Oceans have caused high mortality of seabirds. The Danish salmon fishery off West Greenland killed an estimated 500,000 to 750,000 Thick-billed Murres (*Uria lomvia*) annually between 1968 and 1975 (Tull et al. 1972). In the North Pacific, the Japanese salmon mothership fishery kills over 200,000 seabirds in gillnets each summer (Ainley et al. in prep.), and large numbers of seabirds die in the Japanese land-based fishery as well (Sano 1978). Restriction of gillnet fishing near colonies and in regions of known high seabird concentrations at sea could reduce this kill. The large incidental kill of Thick-billed Murres in the Danish fishery was curtailed after an international agreement took effect in 1976, restricting the Danish fishery to only coastal waters (Salomonsen 1979). The Japanese fishery, although reduced in size in recent years, is still very active in the North Pacific.

The only salmon gillnet fishery in California is located in the Klamath River of northern California. Some birds drown in the nets of this fishery each summer (Chatto pers. comm.) but the total number of birds killed is small.

An unknown number of seabirds are killed annually in a small coastal gillnet fishery for bottomfish that operates from Tomales Bay south to Santa Barbara (Miller pers. comm.). Common Murres, cormorants, and Sooty Shearwaters (*Puffinus griseus*) are apparently the species most frequently caught. Although this fishery has existed for at least 50 years, it has only recently become large enough to cause concern. The California Department of Fish and Game and the U.S. Fish and Wildlife Service are currently investigating the mortality of marine birds and mammals in this fishery.

Offal from boats, particularly processing ships associated with large whaling and fishing fleets, provides large amounts of food for some seabird species, especially Northern Fulmars

(*Fulmarus glacialis*) and gulls. This new food supply may be in part responsible for increases in fulmar and gull numbers in some parts of the world (Brown 1970, Bourne 1972). Commerical fishing in California is primarily from small, privately-owned boats and offal discharge is probably insignificant at present. Coastal garbage dumps are likely a more important food source for gulls.

Commerical fisheries are increasingly harvesting species of fish used by seabirds for food. This is due largely to an increasing demand for fish products, depletion of more desirable species, and improved fishing technology. Fish stocks can become so depleted through overfishing that decreases in populations of seabirds can result. This is best illustrated by the crash of Peruvian seabird populations following overfishing of the anchoveta (*Engraulis ringens*). In the years between 1953 and 1965, Peruvian seabird populations declined from 28 million birds to 4 million birds (Schaefer 1970).

A similar conflict seems likely to occur between the Northern Anchovy (*Engraulis mordax*) and seabird populations along the west coast of Mexico and southern California. The diet of breeding Brown Pelicans in southern California has been found to contain 92 percent anchovies (Gress pers. comm.). Brown Pelicans reproduce best during periods when anchovies are abundant near breeding colonies (Anderson et al. 1980). Although pre-1979 harvest levels of anchovies probably did not affect Brown Pelican reproduction, potential increases in the harvest proposed under some options of the Anchovy Management Plan, Pacific Fisheries Management Council, could be serious (Anderson et al. 1980). Hunt and Butler (1980) have shown the importance of anchovies to the reproductive success of Xantus' Murrelets and Western Gulls on Santa Barbara Island (524 008, See page 56).

Protecting seabird feeding areas, particularly those near breeding colonies, may be necessary. Caution should be used before any decision to increase anchovy harvests is made (MacCall 1974, Radovich 1979, Anderson et al. 1980). Little information is available on the effects of fisheries-caused depletion of prey species on other California seabirds and continued research is needed (Anderson et al. 1980).

HUMAN DISTURBANCE

A serious danger to nesting seabirds is disturbance by people, including scientists, bird-

watchers, recreationalists, and others. Disturbance is usually unintentional and, more often than not, the culprits are unaware of the harm that they have caused. When people go into or near a seabird colony they can cause disturbance in many ways. An awareness of potential problems can do much to reduce disturbance.

Flushing birds from nests must be avoided since it can cause adults to abandon nests, exposes eggs and chicks to predators, and interferes with incubation and the feeding of chicks. During panic departures adults may even break eggs or kick eggs and chicks from nests. Larger chicks may run off and, unable to get back to the nest, may die or be killed. Airplanes, boats, and helicopters, as well as individuals on foot, can cause birds to flush by approaching a colony too closely. Helicopters are especially disruptive.

In California, predation on uncovered eggs and chicks is primarily by Western Gulls and Common Ravens (*Corvus corax*). Both gulls and ravens patrol colonies in search of unattended eggs and chicks or for a chance to steal food brought in by parent birds. Under natural circumstances their success rate is low, but a colony from which adults have been flushed is "easy pickings." Plundering gulls may walk ahead of human intruders, pecking holes into eggs, or they may fly off with eggs to eat elsewhere (Anderson and Keith 1980). Gulls calling overhead attract more gulls and add to the panic of the colony (Anderson and Keith 1980). Western Gulls are formidable predators. They will consume young chicks whole, including chicks of their own species, and will even attack large 3 to 4 week old pelican chicks to obtain regurgitations or will remove the eyes, uropygial glands, and entrails, causing death (Anderson and Keith 1980).

Incubation of eggs and chicks is a means of maintaining an optimum temperature for rapid development. Parents sit on and turn eggs to warm them and will shade eggs and chicks from the sun to keep them from overheating. If parent birds are kept off their nests for a long enough period of time, death of the young from hyperthermia (overheating) or hypothermia (overcooling) can occur. Shorter periods of neglect can extend the incubating time required for hatching.

The most damaging type of human disturbance is physical alteration of habitat, since its effects are longterm, and in most cases irreversible. Whaler Island (325 045) near the Oregon border is now part of the Crescent City breakwater and is no longer used by nesting seabirds. Osborne

(1972) estimates from historical records that 20,000 storm-petrels (Leach's and Fork-tailed Storm-Petrels), along with Western Gulls, Pigeon Guillemots, and Black Oystercatchers, nested on Whaler Island. Loss of this nesting island may have substantially reduced the number of nesting Leach's and Fork-tailed Storm-Petrels in California.

Several seabird species nest in burrows dug into the ground. No one should walk on these burrow areas since they can easily collapse under the weight of a person. Birds may then abandon the burrow. Burrow destruction can also accelerate the serious problem of soil erosion from offshore rocks. Most islands along the California coast were once part of the mainland and soil is primarily or entirely a remnant from before the islands broke away.

In California, burrow nesting species are: Black, Leach's, Fork-tailed, and Ashy Storm-Petrels, Xantus' Murrelets, Cassin's and Rhinoceros Auklets, Tufted Puffins, and, in some instances, Pigeon Guillemots. Of these, Rhinoceros Auklets, Tufted Puffins, and Black and Fork-tailed Storm-Petrels are present only in very low numbers. None of these species' California populations exceed 400 birds, and none of these species is present at more than 14 sites in the state. While Cassin's Auklets and Leach's and Ashy Storm-Petrels are present in greater numbers in California, they are also limited to very few nesting locations. Any disturbance to burrow-nesting species would be particularly unfortunate.



Whaler Island (325 045) was an important seabird colony until the island was quarried and a breakwater was constructed. Few seabirds nest there now. Photo by Art Sowls

SPACE SHUTTLE

The following account is drawn largely from Potential impact of space shuttle sonic booms on the biota of the California Channel Islands: literature review and problem analysis (Evans et al. 1979).

Channel Island seabird populations may be subjected to a new disturbance during the 1980's. The U.S. Government has selected Vandenberg Air Force Base (VAFB), just north of Point Conception, as launch site for the Space Shuttle. Most of these launches will be directed west over the open Pacific, but approximately six launches planned for polar orbit will pass directly over the Channel Islands. These launches will produce sonic boom pressure waves of up to 30 pounds per square foot (psf), considerably greater than the 2.0 to 2.5 psf produced by aircraft sonic booms. Depending on weather and other factors, sonic booms produced by the Space Shuttle will be at maximum intensity over San Miguel Island (Figure 1). Areas south and east of San Miguel Island will be subjected to intense, though less potentially devastating sound pressures. In addition, all of the estimated 129 Space Shuttle re-entries will pass directly over the Channel Islands. Sonic booms from these flights will be similar to those from military aircraft, and 18 per year are




Figure 1. Predicted lines of maximum sonic boom pressures in pounds per square foot (psf) at sea level resulting from Space Shuttle launches into polar orbit from Vandenberg Air Force Base (modified from U.S. Air Force, 1978. Final Environmental Impact Statement, Space Shuttle Program, Vandenberg Air Force Base, California).

scheduled.

These sonic booms may pose several potential dangers to seabirds:

- 1) High sonic boom pressures, particularly those from launches, could physically damage birds regardless of the time of year.
- 2) Both surface nesting and burrow or crevice nesting seabirds may desert eggs and young or fail to initiate nesting because of sonic booms.
- 3) Death of eggs and chicks will probably occur if sonic booms cause panic flights by adults. This result would be similar to that already discussed in the section "Human Disturbance."
- 4) The nests of both burrow-nesting and cliff-nesting seabirds could be damaged or destroyed. An underground nuclear blast in Colorado reduced local raptor reproduction by 20 percent when cliffs crumbled and crushed eggs in two of nine nests (Stahlecker and Allredge 1976). Sound pressures from the Space Shuttle sonic booms may produce a similar effect. Sonic booms in Arizona reportedly have caused geological damage (Graham 1969). Subterranean-nesting species would be particularly vulnerable to the shifting of rocks and soils.

METHODS

Information compiled in this catalog comes from four primary sources. The U.S. Fish and Wildlife Service (this study) conducted surveys of seabirds in 1979 and 1980 along the California coast from Point Conception to the Oregon border. An initial survey of this part of the coast was conducted in 1969 and 1970 by Osborne and Reynolds (1971), and their data still provide the best population estimates for some species at some sites. Data for the Channel Islands and the coast south of Point Conception come primarily from another BLM-sponsored oil lease study conducted from 1974 to 1977 by Hunt et al. (1979) and the California Department of Fish and Game. Information for the Farallon Islands has been collected over the past ten years by staff members of the Point Reyes Bird Observatory. Other sources are listed in the references section and in colony tables. All persons known to have

gathered recent data compiled in this catalog are listed on the title page under "Contributors".

Inherent in any collection of data from different sources is variability in methods. No attempt has been made to enumerate all techniques used to collect data presented in this catalog. Instead we refer readers to the appropriate references from which we obtained population estimates listed in this catalog (After each line of data in the Maps and Tables section, we reference the source from which we obtained the information). A detailed account of the techniques we used during our 1979 and 1980 surveys is presented below.

We conducted seabird surveys from Point Conception to the Oregon border from mid-May to mid-August, 1979, and from mid-May to late August, 1980. Adequate coverage of such a long stretch of coastline required two teams of two observers each with a vehicle, an inflatable boat, and two outboard engines. In 1980, a fifth observer was added to the team. Surveys were concentrated during the peak of the nesting season, from late May to late July. Surveys of surface-nesting seabirds completed earlier in May when seabirds began nesting were repeated later in the season to determine the maximum breeding population. We concentrated our 1979 surveys on conspicuous, diurnal, surface-nesting species such as Brandt's Cormorants, Pelagic Cormorants, Western Gulls, Common Murres, and Pigeon Guillemots. In 1980, we divided our time equally between censusing diurnal surface-nesting seabirds and censusing nocturnal burrowing species such as storm-petrels and Rhinoceros Auklets.

All sections of coastline with likely seabird nesting habitat were surveyed by boat one or more times. Least Terns nesting in bays and on beaches were not counted, since their populations are surveyed annually by the California Department of Fish and Game. We did not attempt to census Snowy Plovers (*Charadrius alexandrinus*), Clapper Rails (*Rallus longirostris*), American Avocets (*Recurvirostra americana*), Black-necked Stilts (*Himantopus mexicanus*), or some of the other species mentioned by Varoujean (1979) in his catalog of seabird colonies of the Pacific States, which was completed from available literature before our surveys were made.

Counts were made from inflatable boats using 7X binoculars or the unaided eye. We found that binoculars with a wide-angle field of view were far superior to normal binoculars when counting from boats. Whenever possible, direct

counts of nests and individual birds were made. Usually, the boat was slowed or stopped and both observers counted birds or nests at the same colony or section of cliff. Counts were often repeated to ensure accuracy.

Except for the Farallon Islands (429 012) and Redding Rock (325 013), all islands and offshore rocks north of Point Conception are within one kilometer of the mainland. Counts of seabirds on offshore rocks, islands, and mainland cliffs were often made from shore promontories. Generally, these counts underestimated populations since only the landward sides of colonies were visible. In many instances, our population figures for a particular colony are derived from a combination of different survey techniques, which may have included boat surveys, aerial photography, counts from the mainland, and observations made directly on an island after landing.

Landings were made on islands and rocks whenever possible, except at colonies of Brandt's Cormorants and Common Murres, which are especially sensitive to disturbance. When we landed on an island, we counted cormorant and gull nests and searched for burrows of storm-petrels, auklets, and puffins. Island visits were as brief as possible to minimize disturbance.

Counts made from boats, the mainland, and the islands themselves were the principal methods used to census Double-crested Cormorants, Pelagic Cormorants, Western Gulls, Black Oystercatchers, Pigeon Guillemots, Marbled Murrelets, Rhinoceros Auklets, Tufted Puffins, and, to a lesser extent, Brandt's Cormorants. Most of our surveys were conducted in 1979. In 1980 we attempted to refine estimates made at locations where surveys were hampered by poor weather conditions the previous year. Also, many sites which were accurately surveyed in 1979 were resurveyed in 1980 to determine whether any population changes had occurred.

Cormorants and gulls build conspicuous nests and are therefore the easiest species to census. Since their nests were directly counted, our population estimates for these species are the most reliable. Most surveys for Pelagic Cormorants and Western Gulls were made from a boat, often very close to shore. Our counts of Double-crested and Brandt's Cormorants and Western Gulls were sometimes hampered by our inability to see the tops of islands, the preferred nesting habitat for these species. We circumvented this problem by making counts from the mainland where possible, or by taking aerial photographs.

We counted and noted the locations of all Black Oystercatchers, Marbled Murrelets, Pigeon Guillemots, Rhinoceros Auklets, and Tufted Puffins seen during our surveys. Nests of these species are either difficult to find or, in the case of burrowing species, difficult to identify with certainty. Therefore counts of individual birds and extrapolation from these counts were our best survey method.

Black Oystercatchers were counted during nearshore surveys but in 1979 poor weather hampered our efforts in some locations. Better weather in 1980 allowed us to re-survey selected portions of the coastline and improve our census data. Because nests of this species are difficult to find, the breeding status of many Black Oystercatchers was impossible to determine. Estimates of populations were usually based on the presence and behavior of birds rather than counts of nests. Some non-breeding oystercatchers were probably included in our counts and may have inflated population estimates for some regions. Frequently, however, sections of coastline with poor habitat for other seabirds were by-passed, even if some habitat looked promising for Black Oystercatchers. For this reason, and because oystercatchers were sometimes hard to see among the confusion of reefs, rocks, and breakers, we believe our estimates of Black Oystercatcher populations in California are conservative.

Marbled Murrelets were counted opportunistically in a narrow strip offshore of the coast. The distances of these counts from shore varied, depending on the nature of the coast, but never exceeded one kilometer. The most critical factors influencing our counts of Marbled Murrelets were sea conditions and time of year. Our counts were made from small inflatable boats, so we probably overlooked some birds on the water in all but the flattest seas. The best censuses of Marbled Murrelets can probably be made in spring when both members of a breeding pair are on the water offshore of coastal forests. Our surveys, however, were usually conducted later in the year. In addition, our census strips were of necessity narrow and this probably resulted in many missed birds. Although our surveys of Marbled Murrelets have provided few data with which future comparisons can be made, we feel they reflect the species' breeding distribution in the state.

Rhinoceros Auklets and Tufted Puffins were frequently seen standing near and entering burrows in the early morning. Time of day is an important factor when censusing these birds, since they are seldom seen at their colonies in late

morning and afternoon. We tried to locate eggs and chicks of Rhinoceros Auklets and Tufted Puffins at several sites where we observed these birds, but only at Prince Island (325 003) were we successful. For the other sites in our study area, we based our population estimates on the number of birds in breeding plumage on or near the colonies in 1979 or 1980. For some colonies that had been previously intensively surveyed, we relied on estimates in the literature.

Pigeon Guillemots are some of the most difficult of California seabirds to census. Finding Pigeon Guillemot nests during brief surveys of the rugged habitat where they usually nest is nearly impossible. Also, numbers of birds around a colony fluctuate greatly depending on the stage of nesting and time of day. Distinguishing breeders from non-breeders is impossible in most cases, so our numbers reflect the total number of guillemots at a colony rather than the number of breeding birds. We found that Pigeon Guillemots are present in large numbers around colonies in the early morning but nearly disappear by mid to late afternoon. Once incubation begins one member of each pair is probably always absent from view. The best time to census this species is therefore in the early morning, before the egg laying season, when both members of a breeding pair are on the water near the colony. Nettleship (1976) concluded that this is the best time to census populations of the similar Black Guillemot (*Cepphus grylle*) in arctic and eastern Canada. Surveying Pigeon Guillemots later in the day will result in underestimation of numbers or even failure to detect entire colonies. Most of our surveys could not be conducted at this optimum time, so guillemot estimates which appear in this catalog are based not only on the numbers of birds seen, but have been modified to reflect the influences of time of day, stage of nesting, and quality of habitat. These adjusted numbers, we feel, provide the most realistic estimates of the populations at each site, but they may be higher or lower than actual guillemot numbers. Although our population estimates are almost always many times higher than those made during previous surveys (1,285 percent higher for the entire study area), we still feel they are conservative. Differences in survey techniques and more complete coverage of the coast are likely to account for our higher numbers.

Aerial surveys were our best means of censusing Brandt's Cormorants and Common Murres. In 1979, we conducted nine aerial surveys in order to cover the coast from Point Conception



Jay Nelson and Bill Rodstrom censusing cliff nesting seabirds from a small boat at False Cape Rocks (325 040).
Photo by Art Sowls

to the Oregon border. Three 1979 surveys were flown from a high-wing Cessna 182 or 210 and the remaining six were flown in U.S. Coast Guard helicopters. In 1980 we conducted five aerial surveys. Four of these were made in a high-wing Cessna 172, and one was flown from a U.S. Coast Guard helicopter. Photographs of seabird colonies were taken either through the open window of a plane or open door of a helicopter. Both color slides (ASA 64, 200, and 400) and black-and-white film (ASA 132 and 400) were exposed in a 35-millimeter camera equipped with either a 70- to 210-millimeter zoom lens or a 300-millimeter lens. Flight altitudes varied, but most photographs were taken from an altitude between 150 and 250 meters. We were careful not to flush nesting seabirds or marine mammals by flying too low, and we are satisfied that we caused no disturbances during our aerial surveys.

Seabirds flush readily from their nests when "buzzed" by low-flying aircraft, therefore it is imperative to fly high enough to avoid disturbing them. For the study area from Point Conception to the Oregon border, we recommend a flight altitude of 200 meters or higher. Common Murres in coastal California nest primarily on the flat tops of islands and, possibly, excluding murres nesting on the Farallon Islands, appear somewhat accustomed to low-flying aircraft. Murres in other regions also frequently nest on cliff faces where more care is needed to avoid flushing birds. Helicopters are more disturbing to birds than fixed-wing aircraft, and should maintain a higher altitude. Telephoto lenses, especially zoom lenses in the 70- to 300-millimeter range, are needed to photograph seabird colonies well enough to make accurate counts later from the photos. Rapid shutter speeds of 1/1,000 second or 1/500 second are important to dampen vibrations. We usually used high speed color slide film because it enabled us to shoot at rapid shutter speeds even on cloudy days.

Most counts of Brandt's Cormorants and Common Murres were made from projected slides. In the case of Brandt's Cormorants, we counted individual nests and determined the number of breeding birds by multiplying the number of nests by two. Brandt's Cormorant nests are conspicuous and easy to count from aerial photographs. Our estimates for this species are probably as accurate as any estimates included in this catalog. Numbers of Common Murres were estimated either by counting individual birds on slides or by blocking off groups of 10's, 50's, or 100's, depending on the sizes of colonies and

the quality of our photographs.

Time of day and of year influence the number of Common Murres at a colony. The greatest numbers of murres are seen in early morning, before the egg-laying season. Both members of each breeding pair, as well as non-breeding birds, are presumably present on the colony at this time. Later in the season, during the incubation and nestling stages of nesting, the number of murres on a colony at any one time decreases because one member of each pair is frequently at sea. Most of our surveys were flown during the incubation and nestling stages, near mid-day. A correction factor must be added to the murre count to account for this variability in colony attendance. Addition of a correction factor to our counts of murres from photographs should result in an adjusted estimate of the breeding population which is more representative than the straight count from the photographs. We used a factor of two-thirds, as proposed by Ainley (1976). A factor of two-thirds implies that fewer than half of the birds are away from the colony at the time of a survey, an assumption which we feel is reasonable. To obtain the adjusted total, we multiplied the count obtained from the photographs by 1.67. Our estimates of murre numbers included in this catalog are only the adjusted totals. The actual numbers of murres counted from slides, which may be the most useful numbers for later historical comparisons, can be obtained by dividing the number listed in this catalog by 1.67.



Brandt's Cormorants and Common Murres were censused primarily by counts made from aerial photographs. Here, Brandt's Cormorant nests are shown at Piedras Blancas (477 007). Photo by Jay Nelson

We were unable to distinguish between breeding and non-breeding Common Murres on the photographs. Our Common Murre estimates are actually the numbers of birds at a colony rather than the numbers of breeding birds.

Common Murres are extremely difficult to census and our estimates of their populations are probably the crudest of all estimates in the catalog. These birds pack densely on islands and it is often impossible to distinguish between individuals, even on high-quality photographs. Comparison of our numbers with those obtained in future surveys will be difficult, but direct visual comparisons of photographs could easily show whether the extent and density of a colony has markedly changed. To make comparisons simpler, we have archived data and photographs at several different sites (see Appendix A).

Storm-petrels and Cassin's Auklets are nocturnal and difficult to census. We made no attempts to census colonies of nocturnal seabirds which we knew existed on Castle Rock (325 006), Green Rock (325 020), and Little River Rock (325 035), but instead relied on population estimates in the literature. Other colonies of nocturnal birds in our study area which we censused were either small in magnitude or small in area and did not warrant intensive survey efforts such as establishing sample plots and determining the ratio of active to inactive burrows. To obtain more refined data on these sites would have caused more disturbance than we felt was justified.

Besides searching many islands for storm-petrel and Cassin's Auklet colonies during the day, we made overnight surveys one or more times on Prince Island (325 003), Flatiron Rock (325 023), Pewetole Island, Button Rock (325 054), Goat Rock (379 006), an island at Van Damme Cove (379 027), and Fish Rocks (404 003). We conducted searches at night for nesting storm-petrels and auklets, and on all but Pewetole Island, Flatiron Rock, and Goat Rock erected mistnets to catch nocturnal birds. We caught and banded 174 Leach's Storm-Petrels on Prince Island, Button Rock, and Fish Rocks combined. Our population estimates for several storm-petrel colonies were based on one or more of the following: 1) the number and density of burrows, 2) the number of birds seen and heard on the island at night, 3) the number of birds captured and banded, and 4) the number of birds recaptured. We discuss our population estimates for storm-petrels at each site more fully in the species accounts. We offer no new estimates of Cassin's

Auklet numbers in the catalog.

This catalog includes the best information available for all seabird colonies along the coast of California, but the information varies in quality from species to species and from site to site. We have devised a data quality code, described below, as an attempt to rate our data by its quality. A data quality code number follows each of our population estimates in the maps and tables section.

Data Quality Code

- I. Total count of all nests (number of nests x 2 = number of breeding birds). Few if any errors were made in these counts. Any changes in number of breeding birds from year to year can probably be detected.
- II. Count of nests. Because of omission or misidentification of nests, counts may be slightly higher or lower than actual bird numbers. Small or moderate changes in number of breeding birds from year to year can probably be detected.
- III. An estimate of the size of a breeding population based on counts of nests and birds and on estimation of the amount of available nesting habitat. Census techniques vary considerably among species. Only large changes in populations from year to year can probably be detected.

DISCUSSION

Populations containing nearly 700,000 seabirds, representing 23 species, are discussed in this catalog. All major and most minor seabird colonies along the California coast have probably been identified, and present data seem adequate to evaluate the importance of even small sections of coastline to breeding birds.

Unfortunately, sufficient historical data do not exist to evaluate population changes or trends that may have occurred or are occurring along much of the California coast. Only on the Farallon Islands (429 012), Santa Barbara Island (524 008), Anacapa Island (502 007), and at Least Tern colonies in southern California have long-term studies been initiated.

Although California's breeding marine avi-

fauna is diverse, only a few species make up the majority of this assemblage of seabirds. Common Murres, Brandt's Cormorants, Cassin's Auklets, and Western Gulls compose almost 90 percent of the California population (Figure 2). A disproportionately large percentage of this population breeds at only a few locations in the state. Two regions, the Farallon Islands and the north coast of California from Cape Mendocino to the Oregon border, contain the largest number of breeding seabirds (Figure 3). The Farallon Islands are extremely important. Large portions of the state's breeding populations of Ashy Storm-Petrels, Brandt's Cormorants, Western Gulls, Common Murres, Pigeon Guillemots, Cassin's Auklets, Rhinoceros Auklets, and Tufted Puffins breed

on these islands (Figure 4).

The coastline north of Cape Mendocino contains more breeding seabirds than the Farallon Islands although no single site there approaches the Farallones in number of birds. Large portions of the state's breeding population of Fork-tailed Storm-Petrels, Leach's Storm-Petrels, Double-crested Cormorants, Common Murres, Rhinoceros Auklets, and Tufted Puffins inhabit this coast. Castle Rock (325 006), the second-largest seabird colony in the state, is found in this stretch of coastline.

The Channel Islands are particularly noteworthy since the entire California breeding populations of Black Storm-Petrels, Brown Pelicans, and Xantus' Murrelets nest there. The




Figure 2. Populations of breeding seabirds and percentages of total aggregate population in California.

*coastal population only.

more sub-tropical seabird community of the Channel Islands, although containing fewer breeding seabirds than the Farallon Islands and northern California, is of no less importance.

Six of the 23 species discussed in this catalog are widespread along much of the California coast. Of the six, the Black Oystercatcher is the most widely distributed, despite an estimated breeding population of only 1,000 birds. This distribution reflects the abundance of this species' preferred nesting habitat in California. The Black Oystercatcher's small population size, however, is perhaps related to its tendency to nest as isolated pairs on offshore rocks and inaccessible stretches of the California coastline.

The distributions of Pelagic Cormorants and

Pigeon Guillemots are also relatively uniform, in part because their nesting habitat is abundant in this state (Figure 4). Pelagic Cormorants are most numerous between Cape Mendocino and San Francisco, an area possessing long stretches of vertical cliffs. Pigeon Guillemots attain their greatest abundance in central California, south of San Francisco, including the Farallon Islands, but large colonies are also found at many locations north of Point Conception. Both Brandt's Cormorants and Western Gulls are widely distributed throughout California but extremely large concentrations of each exist on the Farallon Islands (Figure 4). Common Murres are found throughout much of central and northern California although they are most abundant in




Figure 3. Percentage of breeding seabirds along the California coast. Circle size is directly proportional to numbers of birds.





Figure 4. Percentages of the California breeding population of seventeen species of seabirds for



ten sections of the coast and the Farallon Islands.

northern California.

Twelve of the 23 species discussed in this catalog reach either the northern or southern limits of their breeding ranges within California. Elegant Terns breed only as far north as San Diego Bay. Black Storm-Petrels, Brown Pelicans and Xantus' Murrelets breed as far north as the Channel Islands, although they are much more abundant farther south. The breeding range of Ashy Storm-Petrels is restricted to coasts between northern Baja California, Mexico, and Marin County in northern California. Fork-tailed Storm-Petrels, Pelagic Cormorants, Common Murres, Pigeon Guillemots, Marbled Murrelets, Rhinoceros Auklets, and Tufted Puffins are all cool water species and reach the southern limits of their breeding range within California. Pelagic Cormorants and Pigeon Guillemots breed as far south as the northern Channel Islands, as did Common Murres and Tufted Puffins until the early part of this century. Breeding Common Murres and Tufted Puffins can now be found only as far south as Monterey County in central California. Marbled Murrelets probably breed no farther south than the coastal forests in Santa Cruz County, although they have been observed as far south as Point Sal during the breeding season. Probably the southernmost breeding location of the Rhinoceros Auklet is at Point Arguello (501 011). The southern range limit of breeding Fork-tailed Storm-Petrels lies in the islands of Trinidad Bay.

Point Conception and the northern Channel Islands are considered the boundary zone between warm and cold waters in California. There is no clean division of water masses in this area, however. The region is, instead, a complex oceanographic zone. The principal oceanographic components are a cold southerly-flowing offshore current (the California Current), a cold northerly-flowing offshoot of the California Current (the Southern California Countercurrent), and a cold southerly-flowing inshore current (the Southern California Coastal Current), all of which are separated in part by bodies of warm water. At this complex junction of water masses, Black Storm-Petrels, Brown Pelicans, Pelagic Cormorants, Pigeon Guillemots, and Xantus' Murrelets reach the limits of their breeding ranges.

Populations of seabirds living at the edges of their breeding ranges are often small. This is best illustrated in California by Fork-tailed Storm-Petrels, Black Storm-Petrels, and Tufted Puffins. These populations may be particularly susceptible to changing environmental conditions and distur-

bance. If local extinction should occur, as it has in the case of the Tufted Puffin in the Channel Islands, re-establishment could take a very long time.

Breeding activity of seabirds in California is related to the hydrographic cycle by its synchrony with a period of upwelling that usually begins in March. During this period, strong northwest winds develop and surface waters along the coast move southerly and offshore. Cold, high-salinity waters upwell along the coast to replace surface waters moving away from the shore. Once these cold, nutrient-rich waters reach the photosynthetic zone, they trigger a phytoplankton bloom which in turn triggers an increase first of zooplankton and later of fish and squid. Bolin and Abbot (1963) have shown that in Monterey Bay, phytoplankton begins increasing in late January and peaks in June. Seabirds of all species in California concentrate their breeding activities from as early as late winter through June and early July, coinciding with the time of peak plankton production.

Productivity of plankton along the coast decreases in late summer and early fall during the oceanic period of the hydrographic cycle (Bolin and Abbot 1963). At this time of year, the strong northwest winds abate. Cold, surface waters sink and are replaced by warm, low-nutrient waters from offshore. Lack of food at this time of year may help explain the cessation of breeding activity and the occurrence of periodic die-offs of young birds, especially Common Murres.

The intensity and duration of the upwelling period may influence the number of birds breeding and their productivity. This may explain the decreases in numbers of Brandt's Cormorants which we observed at many sites in California in 1980 from the numbers we observed in 1979, which was apparently a banner year for seabirds in California.

During the fall and winter, warm, nutrient-depleted waters intrude into the California coastal zone. These coastal waters move slowly northward, pushed by predominantly southerly winds to form a countercurrent (Schwartzlose 1963). If, during the following period of upwelling, northwest winds are not strong and persistent, upwelling will be weak. Water temperatures will be higher, plankton productivity lower, and the numbers of breeding seabirds and their productivity will decline. Fluctuations in these oceanic conditions occur yearly, so variation in the number of breeding seabirds and their productivity is

clouds

Cape Mendocino

Pt. Arena

Pt. Reyes

SAN FRANCISCO

Monterey Bay

Pt. Sur

The timing and success of breeding of many California seabirds is related to the upwelling of cold, nutrient-rich water. This enhanced infrared satellite photograph shows cold water masses (lighter in color) upwelling along the coast, particularly near prominent points.

Photo compliments of NOAA

Buchon

common.

More prolonged changes in climate can also influence breeding populations of seabirds. Cassin's Auklets, now the most abundant seabirds on the Farallon Islands, were rare on those islands in the mid-1800's (Ainley and Lewis 1974). These auklets are cold water birds found from the Pacific coast of Baja California, Mexico, north to the Gulf of Alaska and the Aleutian Islands. In California, the breeding period of this species coincides with the period of upwelling of cold, nutrient-rich waters when zooplankton is most abundant. According to Hubbs (1948), the ocean climate from 1853 to the 1870's was dominated by a northward intrusion of warm water. Ainley and Lewis (1974) believe this northward intrusion of warm water extended as far north as the San Francisco-Farallones region and may explain the scarcity of Cassin's Auklets on the Farallon Islands during that time. Additional evidence of this was found during two other warm water periods in recent years when Cassin's Auklet productivity on the Farallon Islands was significantly lower than in cold water years (Ainley and Lewis 1974).

Gradual changes in seabird populations may also occur in response to the gradual degradation and formation of nesting habitat. Many islands and rocks along the California coast are eroding away. During this process, the habitat changes and it may become more suitable to some species and less suitable to others. For example, younger islands with deep soil layers are preferred by burrowing species such as storm-petrels, Cassin's Auklets, Rhinoceros Auklets, and Tufted Puffins. As the soil erodes away, islands become less suitable to these species. Cormorants may colonize the barer regions of the island and speed soil and vegetation loss. Once an island is stripped of soil and vegetation it may be suitable only for cormorants, murre, and, to a lesser extent, Western Gulls.

Examples of nesting islands in different stages of their evolution are evident up and down the California coast. Point Sur, at the north end of Big Sur, and Trinidad Head in northern California are obvious islands-in-the-making, although they are still attached to the mainland. Pewetole Island, north of Trinidad Head, is a forested island recently cut off from the mainland, still accessible to predators at low tide, and at the present time inhabited only by Black Oystercatchers. This island appears to offer excellent petrel habitat and could become an important colony once the channel between it and the

mainland deepens. Little River Rock (325 035) is a treeless but heavily vegetated island in northern California, accessible to humans by wading at low tide. Little River Rock is the largest storm-petrel colony in California but it has recently been colonized by Double-crested Cormorants which are degrading the habitat for burrowing species (Harris pers. comm.).

Flatiron Rock (325 023) is an almost bare island in northern California presently inhabited by large numbers of Common Murres, Brandt's Cormorants, Western Gulls, and a very few Pigeon Guillemots and Tufted Puffins. Clay (unpubl. field notes) in 1911 reported Tufted Puffins as numerous there and also found nests of Pigeon Guillemots, Cassin's Auklets, and Leach's Storm-Petrels. We found the burrow nesting habitat to be poor in quality and used by few birds during our visits to the island in 1980.

These examples show a continuum in the evolution of seabird nesting habitat from future islands, to new islands with deep soil, to older islands with less soil, suitable only for surface nesting seabirds, and finally to wave-washed rocks unsuitable for nesting.

Seabirds themselves can be active agents in the evolution of nesting habitat. Pelicans, cormorants and gulls remove plants for nest building and their excrement sometimes kills vegetation. Burrowing species contribute to the destruction of their own nesting habitat by digging burrows and removing soil. Puffin Island, in the Chamisso Island National Wildlife Refuge in Alaska, is a vivid example. There, a burrowing population of Horned Puffins has created long, deep furrows in the sod where burrows have collapsed, accelerating recession of the vegetative cover from the nesting area and hastening the removal of soil through erosion (DeGange and Sows unpubl. data).

Seabird numbers and productivity vary naturally from year to year and also over longer periods of time. Man's activities have in the past had largely adverse effects on California's seabirds. Additional conflicts in the future are likely, but still avoidable. We hope that planners will carefully consider the welfare of seabirds when making coastal policy decisions. To this end, the catalog of California seabird colonies will be useful. Seabird populations in this state can flourish indefinitely, as long as they can satisfy their basic needs - food, sufficient habitat, a clean environment, and freedom from disturbance. In this sense, "management" of seabirds should be directed towards meeting these needs.




SPECIES ACCOUNTS

Common Murres at Point Reyes (429 001). How many? Our count is at bottom of page 21.

Photo by Anthony R. DeGange

Fork-tailed Storm-Petrel (*Oceanodroma furcata*)



Fork-tailed Storm-Petrels are small seabirds often found far from land over the open ocean. They usually feed at the ocean's surface on plankton but are known to follow fishing vessels and to feed on scraps and fishing offal. Although the species occurs in California, its center of abundance appears to be the Aleutian Islands and the Gulf of Alaska (Sowls et al. 1978).

Fork-tailed Storm-Petrels breed on offshore rocks and islands safe from mainland predators. Throughout their range they nest in both rocky crevices and, to a lesser extent, burrows in soil.

To avoid diurnal predators, colony activity occurs during the darkest hours of the night. Adults mate, exchange incubation and brooding duties, and feed chicks only during the night, remaining in the burrow or returning to offshore waters by day. For this reason Fork-tailed Storm-Petrels are rarely seen at the breeding colonies during the day. Their nocturnal habits make detection of colonies difficult and estimation of populations imprecise.

CALIFORNIA COLONIES


Fork-tailed Storm-Petrels have been identified at six sites in California, all north of Eureka (Harris 1974, this study). The largest of these, Little River Rock (325 035), is inhabited by approximately 200 birds. The population at Castle Rock (325 006) is estimated at 100 birds (Osborne 1972), and the other four colonies

together probably contain fewer than 100 birds (Harris 1974, present study). All major colonies of Fork-tailed Storm-Petrels in California have probably been found, but additional small colonies may still exist.

HISTORICAL STATUS AND VULNERABILITY


Published data indicate that since the 1930's, Fork-tailed Storm-Petrels have disappeared from three California sites and been found at an additional four sites. A major colony of storm-petrels was extirpated from Whaler Island (325 045), Del Norte County, after construction of a breakwater to the island in the 1930's (Osborne 1972). Clay and Dawson found Fork-tailed Storm-Petrels nesting on Blank Rock (325 023) in 1916 (Dawson 1923) but this species no longer breeds there (Osborne 1972). Soil erosion probably led to their disappearance from these two islands. Fork-tailed Storm-Petrels have recently been found on Little River Rock (325 035), Prisoner Rock (325 027), and Tolowa Rocks (325 007) (Osborne 1972, Harris 1974, this study). These recent discoveries probably reflect a more thorough search for nests rather than an increase in population and colonization of new sites.

Fork-tailed Storm-Petrels readily desert their nests if disturbed by humans during incubation or while parents are brooding recently hatched chicks. Evidence from studies of an Alaskan




population shows that extremely unfavorable weather conditions or insufficient food supplies will cause parents to temporarily abandon eggs and chicks (Boersma et al. 1980). Such temporary abandonment of nests reduces viability of eggs, causes death among chicks, and lengthens the breeding season (Boersma and Wheelwright 1979, Boersma et al. 1980).

Fork-tailed Storm-Petrels are most vulnerable to oil pollution during the summer months when their movements are restricted to nearshore areas by breeding activities (Lensink et al. 1978, Wiens et al. 1978.) While these petrels generally feed in waters over the continental shelf (Lensink et al. 1978), they are usually uncommon in the coastal zone of California and become more abundant only during years of unseasonably cold water (Ainley 1976). Considering this species' small population size, restricted number of breeding sites, and low reproductive potential, any major disturbances to their breeding colonies could be disastrous to the California populations.



Fork-tailed Storm-Petrels, like all procellariiformes, have a tube-nose.

Leach's Storm-Petrel (*Oceanodroma leucorhoa*)



World Breeding Range

Leach's Storm-Petrels are the most abundant of the storm-petrels breeding in California and are probably the most pelagic of the four species. Although breeding colonies are confined to the northern hemisphere, wintering birds range south to tropical waters in both the Pacific and Atlantic Oceans (Palmer 1962).

Like all storm-petrels, Leach's Storm-Petrels are nocturnal on the breeding colonies, an adaptation which reduces their susceptibility to diurnal predators such as gulls. Nests are usually located in burrows or, less frequently, in rock crevices (Palmer 1962). Leach's Storm-Petrels have a well-developed olfactory system (Bang 1966, Stager 1967) and Grubb (1973, 1974) has suggested that these birds, which often nest in crowded colonies in dense spruce forests, may locate their burrows by odor.

Like most seabirds, Leach's Storm-Petrels exhibit relatively long lifespans and low mortality rates for their size. Individuals that survive the hazardous first year of life can live up to 24 years and possibly longer (Graham 1980). Additional references on this well-studied species include Ainley et al. (1974, 1976) Ainslie and Atkinson (1937), Gross (1935), Harris (1974), Huntington (1963), Morse and Buchheister (1979), Threlfall (1974), and Wilbur (1969).

CALIFORNIA COLONIES


Leach's Storm-Petrels are known or suspected to breed at 13 sites along the California coastline.

While most sites are located in the northern part of the state, recent evidence suggests that small numbers of Leach's Storm-Petrels may also nest in the Channel Islands (Hunt et al. 1979).

The largest colony in California is located at Little River Rock (325 035), which has 10,000 birds (Harris 1974). Other major colonies are Castle Rock (325 006) with 5,000 birds, the Farallon Islands (429 012) with 1,400 birds, Trinidad Bay Rocks (325 054) with 1,640 birds, and Prisoner Rock (325 027) with 160 birds.

Colonies are suspected to exist at Fish Rocks (404 003), Prince Island (325 003), and Tolowa Rocks (325 007), although nests of this species have not been found at these locations. On both Fish Rocks and Prince Island suitable nesting habitat is available and Leach's Storm-Petrels with clearly visible incubation patches have been mist-netted and banded. We are confident that Leach's Storm-Petrels breed at Fish Rocks because of our recapture of banded birds there and the island's isolation from other known Leach's Storm-Petrel colonies. At Prince Island no recaptures of banded birds were made and it is possible that the birds we caught were from nearby colonies at Castle Rock (325 006) and Goat Island, Oregon. At Tolowa Rocks, the less common Fork-tailed Storm-Petrels were found nesting in burrows. Many unexamined burrows were present and it seems likely that Leach's Storm-Petrels nest there.

All major colonies of Leach's Storm-Petrels in California have probably been identified, but



additional small colonies may exist on almost any island with suitable habitat.

HISTORICAL STATUS AND VULNERABILITY

Limited published data suggest that Leach's Storm-Petrels have declined in number in California since the turn of the century. Breeding colonies were once found on Whaler Island (325 045), Blank Rock (325 024), Flatiron Rock (325 023), and Green Rock (325 020). They have been extirpated from the first three islands and only one dead petrel was found on Green Rock during a survey in 1970 (Osborne, 1972). On Whaler Island, a colony of 20,000 storm-petrels was destroyed after construction of a breakwater to the island in the late 1930's and the breakwater's subsequent strengthening in the early 1950's. The island was quarried for rock and the introduction of rats hastened the colony's demise (Osborne 1972). Storm-petrels on Blank, Flatiron, and Green Rocks may have been reduced in number or eliminated by over-collecting and accelerated soil erosion caused by early egg collectors and by erosion caused by nesting cormorants and murres.

Harris (pers. comm.) believes that the recently established breeding population of Double-crested Cormorants on Little River Rock (325 035) is preempting and destroying storm-petrel nesting habitat. This Double-crested Cormorant colony has increased substantially in recent years, from two pairs in 1974 to about 50 pairs in 1980

(Yocom and Harris 1975, this study). Nearby Trinidad Bay Rocks (325 054) may be receiving the petrels displaced from Little River Rock. For example, Button Rock (325 054) had no nesting storm-petrels in 1970 (Osborne 1972), but in 1980 approximately 1,000 Leach's Storm-Petrels were actively breeding there. Nevertheless, the loss of nesting habitat through soil erosion and the displacement of birds by cormorants may be two of the most significant threats to storm-petrels in California.

Predators such as River Otters (*Lutra canadensis*) and Mink (*Mustela vison*) can also be detrimental to storm-petrel colonies. Osborne (1972) found about 90 dead Leach's Storm Petrels on Prisoner Rock during surveys in 1969, 1970, and 1972 and attributed these losses to mink. In 1980 we observed 45 Leach's Storm-Petrel carcasses on Prisoner Rock and suspect a river otter was the predator. Despite this loss, our estimate of Leach's Storm-Petrels for this colony remains similar to Osborne's. The population of Leach's Storm-Petrels on the Farallon Islands appears relatively stable in size (Ainley and Lewis 1974).

Leach's Storm-Petrels are vulnerable to contamination by oil. The period of greatest susceptibility is from February to October when they are most abundant off coastal California. During the winter they are uncommon within 30 kilometers of shore (Ainley 1976) and are unlikely to be affected by coastal oil spills.

Ashy Storm-Petrel (*Oceanodroma homochroa*)



Ashy Storm-Petrels, like other storm-petrels, are diminutive birds well suited to oceanic life. Their breeding range overlaps with that of their close relative, the Leach's Storm-Petrel, but they occupy different feeding niches. The Ashy Storm-Petrel forages in the waters of the California Current, just off the continental shelf, while the Leach's Storm-Petrel feeds over a vast pelagic range (Ainley et al. 1974).

Ashy Storm-Petrels and other members of the family Hydrobatidae feed on small invertebrates and fish caught at the ocean surface. All hydrobatid young are fed a peculiar smelling oil which the adults regurgitate. This oil, or "petroleum," as labelled by Grinnell (1897), provides a concentrated energy source for growth of the young and allows adults to carry more food than if they return with whole prey.

Ashy Storm-Petrels usually nest in natural rock crevices, although the Farallon Island population uses rock walls and building foundations as well (Ainley et al. 1974). Adults are nocturnal at the colonies and may only return with food every few nights. Foraging trips lasting several days probably allow storm-petrels to feed over a larger range to optimize their effort.


The nocturnal habits of Ashy Storm-Petrels may serve to reduce predation by normally diurnal Western Gulls. On the Farallon Islands, Ainley et al. (1974) found that only one percent of the storm-petrels were taken by Western Gulls each year. In addition, Ashy Storm-Petrel young

fledge late in the year after many of the gulls have left the Farallon Islands and by this strategy may avoid a potentially serious post-fledging mortality.

CALIFORNIA COLONIES

With the exception of one small colony in the Los Coronados Islands of Mexico, estimated to contain about six birds (Jehl pers. comm.), the entire known world's population of Ashy Storm-Petrels nests on islands off the California coast. More than 75 percent (4,000 birds) of the recorded population nests on the Farallon Islands (429 012). The remainder of the population, except for a small colony at Bird Rock (404 010), nests in the Channel Islands.

Nine colony sites have been found in the Channel Islands. Major colonies are located on Prince Island (501 004) with 600 birds, Castle Rock (501 005) with 200 birds, and Santa Barbara Island (524 009) with 250 birds. Additional small colonies are located on San Miguel Island (501 006), and small islets offshore of Santa Barbara and Santa Cruz Islands. Although additional small colonies of Ashy Storm-Petrels may exist in the Channel Islands and elsewhere along the California coast, the largest colonies have probably been identified. All identified colonies together contain approximately 5,200 birds. It seems unlikely that the population exceeds 10,000 birds, allowing for possible underestimation of known colonies and the existence



| Breeding Chronology | | Clutch = 1 (1) | | | | | | | | | |
|---|------|---|------|-----|------|------|------|------|------|------|------|
| Northern California | | Incubation Period = 42 days Nesting Period = 76 days | | | | | | | | | |
| Not Breeding | | | | | | | | | | | |
| <i>Numbers in parentheses correspond to the references from which we obtained the data.</i> | | | | | | | | | | | |
| Farallon Islands | | (2) | | | | | | | | | |
| | | | | | | | | | | | |
| Channel Islands | | (28, 29) | | | | | | | | | |
| | | | | | | | | | | | |
| Jan. | Feb. | Mer. | Apr. | May | June | July | Aug. | Sep. | Oct. | Nov. | Dec. |

of non-breeding birds and some small undiscovered colonies.

Preserve. The remainder of the Channel Islands have recently been designated a National Park.

HISTORICAL STATUS AND VULNERABILITY

Populations of Ashy Storm-Petrels along the California coast have probably changed little in size over the years, although little information on their historical status exists. Ainley and Lewis (1974) discuss the history of Ashy Storm-Petrels on the Farallon Islands where observations of storm-petrels were made as early as 1862. Relevant historical material for the Channel Islands is summarized by Hunt et al. (1979).

Ashy Storm-Petrel colonies can be affected by disturbance by humans and terrestrial predators. Adults are vulnerable to surface oil slicks, but fortunately they disperse widely along the coast, a habit which reduces the chances that a large percentage of the population will contact a particular pollutant. However, during the fall large numbers of Ashy Storm-Petrels are known to concentrate in Monterey Bay (Ainley 1976).

The small world population of Ashy Storm-Petrels has restricted breeding and wintering ranges. Each known area of concentration, both during breeding and non-breeding seasons, is valuable to the species. Fortunately, the most important nesting sites in California are protected, the Farallon Islands as a National Wildlife Refuge and Santa Cruz Island as a Nature Conservancy

Black Storm-Petrel (*Oceanodroma melania*)



World Breeding Range

The Black Storm-Petrel merits the distinction of being the rarest breeding seabird on the California coast. They are known to nest in California only at two sites in the Channel Islands which together contain approximately 150 birds (Hunt et al. 1979). Although Black Storm-Petrels were not discovered nesting in California until 1976 (Pitman and Speich 1976), they have been known to breed in the nearby Los Coronados Islands since 1898 (Anthony 1898).

Fall dispersal from the breeding colonies is generally southward but wintering birds have been observed in offshore waters from San Francisco south to Ecuador. They seem to prefer relatively warm ocean waters. Black Storm-Petrels feed primarily on small fish and invertebrates taken near the ocean surface and on garbage discarded by passing ships (Anthony 1898, Willet 1933, Murphy 1936).

CALIFORNIA COLONIES

Black Storm-Petrels nest in California only on Santa Barbara Island (524 008) and nearby Sutil Island (524 009) in the Channel Islands (Hunt et al. 1979). The population estimate of 150 breeding birds was deduced primarily by mist net banding and recapture during several nights in 1977 (Hunt et al. 1979). Since Black Storm-Petrels nest in low densities in scattered natural crevices and burrows of other species, censusing is extremely difficult (Bent 1922, Palmer 1962) and little is known of this bird's breeding biology.


Additional nesting locations may exist in southern California.

Breeding Black Storm-Petrels are present 8 kilometers south of the U.S.-Mexico border in Los Coronados Islands. This population is estimated at approximately 200 birds and appears stable (Jehl pers. comm.).

HISTORICAL STATUS AND VULNERABILITY

The size of historical breeding populations of Black Storm-Petrels in California is unknown, but it seems unlikely that this species has ever been common. Small numbers of breeding petrels nesting on Santa Barbara Island could easily have been overlooked by previous investigators (Hunt et al. 1979).

Small peripheral breeding populations such as the Channel Island colonies are extremely vulnerable to extirpation (MacArthur and Wilson 1967). The Santa Barbara and Sutil Island colonies could be destroyed by disturbance either of the breeding grounds or of offshore wintering areas, and care should be taken to protect these sites. Population declines at the more populous colonies in Mexico may have a negative effect on the California colonies by reducing potential breeding recruitment. Fortunately Santa Barbara and Sutil Islands and the nearest Mexican breeding islands are protected as sanctuaries by their respective governments.



Black Storm-Petrels are considerably larger than Ashy Storm-Petrels.

Photo by Robert L. Pitman

Brown Pelican (*Pelecanus occidentalis*)



The Brown Pelican is one of the most conspicuous and easily identified members of the marine avifauna of California. It is included on the endangered species list of the U.S. Fish and Wildlife Service. In California, Brown Pelicans are slowly increasing in number, but their continued recovery is uncertain.

The large number of Brown Pelicans in California during summer, fall, and early winter belies the actually small breeding population. Many birds migrate northward from Mexico after breeding in spring. These birds feed and molt in California and southern Oregon before returning to Mexico in early winter.

Brown Pelicans in California and Baja California, Mexico, build large stick nests on the ground (Gress 1970). The lusterless, white eggs are incubated by adult pelicans using their webbed feet; a habit characteristic of many birds in the order Pelecaniformes (pelicans, boobies, cormorants, frigatebirds, and tropicbirds). Brown Pelicans feed by making spectacular plunges into the water. Throughout their range, fish are the chief food (Palmer 1962). The Northern Anchovy (Anderson et al. 1975, 1980) makes up nearly the entire diet of breeding birds in California.

Reproductive success of Brown Pelicans can vary markedly from year to year. Changes in oceanographic conditions and in the distribution and abundance of forage fish are two interrelated factors that may account for this fluctuation.

CALIFORNIA COLONIES


Brown Pelicans breed regularly in California only on West Anacapa Island (502 007). In

recent years they have also nested intermittently on Santa Barbara Island (524 008) and Scorpion Rock (502 010).

HISTORICAL STATUS AND VULNERABILITY

The California breeding range of the Brown Pelican formerly extended as far north as Bird Island (454 009) near Monterey. Pelicans have bred only sporadically on this island since the colony was discovered in 1927, and the last successful nesting attempt was in 1959 (Williams 1927, Baldrige 1973).

Historically, West Anacapa Island has been the island most consistently used for nesting by Brown Pelicans in California. Before 1929, birds nested primarily on East Anacapa Island but establishment of a lighthouse there likely caused the breeding population to shift to West Anacapa Island. Population estimates for Brown Pelicans on Anacapa Island have fluctuated considerably over the years and are summarized by Anderson and Anderson (1976) and Hunt et al. (1979). Historical records also exist of Brown Pelicans nesting on Prince Island (501 004), Santa Cruz Island, and Santa Barbara Island (524 008). Brown Pelicans were last recorded nesting on Prince Island in 1939 (Sumner 1939). The only record of pelicans nesting on Santa Cruz Island was made by Wright in 1909 (Willett 1912), although up to 160 birds have nested on nearby Scorpion Rock (502 010) in 1972, 1974, and 1975 (Anderson and Anderson 1976). Brown Pelicans were first observed breeding on Santa Barbara Island in 1911 (Willett 1912) and have nested intermittently there until 1980 (Gress



| Breeding Chronology | | Clutch = 2-3 (20,21,29) |
|---|------|-----------------------------|
| | | Incubation Period = 30 days |
| | | Nesting Period = 13 weeks |
| Northern California | | |
| Not Breeding | | |
| Numbers in parentheses correspond to the references from which we obtained the data. | | |
| Bird Island (454 008) | | |
| ? | ? | egg laying (7) |
| ? | ? | hatching |
| No nesting attempts since 1966. Breeding chronology from combined years 1933 to 1959. See text. | | |
| ? | ? | fledging |
| ? | ? | adults present |
| Channal Islands | | |
| | | egg laying (7,20) |
| | | hatching |
| | | fledging |
| | | adults present |
| Jan. | Feb. | Mar. |
| Apr. | May | June |
| July | Aug. | Sep. |
| Oct. | Nov. | Dec. |

pers. comm.).

In the late 1960's and early 1970's, the reproductive success of Brown Pelicans declined considerably in California and northern Mexico. From 1969 to 1971 only 12 chicks fledged out of 2,368 nesting attempts (Gress et al. 1973, Anderson and Anderson 1976). The breeding failures of Brown Pelicans during this period were related to the high levels of DDE, the principal metabolite of DDT, in the marine environment (Schreiber and Delong 1969, Schreiber and Riseborough 1972, Riseborough et al. 1971, Jehl 1973, Anderson and Anderson 1976).

Brown Pelicans in California feed at the top of a food chain that also includes plankton and anchovies. At each higher level of this food chain, concentrations of pesticides were magnified until, in Brown Pelicans, metabolism and deposition of calcium in eggs were impaired and egg shell thicknesses were reduced as much as 50 percent from normal (Anderson et al. 1975). Breaking of thin-shelled eggs under the weight of incubating adults reduced hatching success to almost zero (Gress et al. 1973). Dumping of DDT into the sewage system of the Los Angeles area ceased in 1970 and since 1972 the reproductive success of the Brown Pelican in southern California and northern Mexico has improved. Ten years after the DDT dumping ban, DDE levels have stabilized at lower levels than in the past, but the effects of this chemical on the Brown Pelican continue.


Brown Pelicans reach the northern limit of their breeding range in southern California. Historically, breeding populations of Brown

Pelicans in southern California have fluctuated in response to environmental conditions. Current thought suggests that these populations increase during periods of ocean warming (Baldrige 1973, Anderson and Anderson 1976). The recent history of this natural population flux has been complicated since the 1950's by a consistent decline in the numbers of Brown Pelicans because of environmental contamination by chlorinated hydrocarbons (Anderson and Anderson 1976).

Although the threat of environmental contamination by pesticides has diminished, the future of the Brown Pelican in California is not necessarily secure. Brown Pelicans can be seriously affected by oil spills since they plunge dive to feed and often sit on the water. They are limited to nearshore areas where oil spills are likely to be most common and severe. Brown Pelicans in southern California feed almost exclusively on Northern Anchovies, a fish also in great demand by man. A sustained high commercial catch could deplete the fish stocks necessary for successful pelican nesting. Any changes in anchovy management must take into account the requirements of a potentially expanding population of Brown Pelicans.

Breeding Brown Pelicans are highly susceptible to disturbance. Reproductive success is lower in colonies that have been disturbed by man than in those undisturbed (Anderson and Keith 1980). Increases in the number of tourists at several colonies in Mexico could cause a serious decrease in the reproductive success of this species and might have important effects on southern California populations.

Double-crested Cormorant (*Phalacrocorax auritus*)



Double-crested Cormorants are the most widespread of all cormorants in North America. They are also the only cormorant in the United States and Canada regularly found in freshwater habitats. In California, Double-crested Cormorants are found breeding along the coast and inland near large rivers and lakes. Despite their widespread breeding distribution, they are probably the least abundant of the cormorants in California.

Double-crested Cormorants nest in a variety of habitats. Along the coast they nest on offshore rocks and islands, on abandoned wharf timbers, and on power poles in coastal bays. Cormorants living inland nest in trees or snags, around lakes, or on islands within the lakes. They construct nests of sticks or matted vegetation gathered near the colony.


Double-crested Cormorants are sleek and strong swimmers that prey on shallow-water fish (Robertson 1974). After their fishing sessions, they are frequently seen extending their wings to dry. Cormorant feathers become completely saturated during underwater swimming and require periodic drying (Rijke 1968). Many Double-crested Cormorants which nest on coastal rocks and islands feed in nearby bays and rivers of the mainland. Even birds nesting as far offshore as the Farallon Islands (429 012) may come to the coast to feed if local food supplies are poor (Ainley pers. comm.).

CALIFORNIA COLONIES

Double-crested Cormorant colonies are located in the Channel Islands and Farallon Islands and on nearshore rocks and islands north of San Francisco. There are 17 coastal sites listed in this catalog. The largest of these sites is Prince Island (325 003) with 450 birds. Other large colonies are Old Arcata Wharf (325 038) with 340 birds and the Farallon Islands (429 012) with 180 birds. The remaining 14 coastal sites have 150 or fewer birds. The total breeding population on the coast of California now contains about 1,900 birds. The largest inland population in California breeds near Tule Lake, Siskiyou County (Kelly pers. comm.).

HISTORICAL STATUS AND VULNERABILITY

Populations of Double-crested Cormorants on the Channel Islands may have declined in size significantly since the turn of the century, but numbers may now be increasing (Hunt et al. 1979). The reasons for the prolonged decline are unknown. However, in the late 1960's and early 1970's pesticide contamination caused thinning of eggshells of Double-crested Cormorants and Brown Pelicans in the Channel Islands, considerably lowering the reproductive success of these two species (Gress et al. 1973). Eggshell thinning in Double-crested Cormorants has also



been documented at the Old Arcata Wharf (325 038) colony in northern California (Ayers 1975).

On the Farallon Islands, Double-crested Cormorants were once the second most abundant species of cormorant, numbering in the low thousands (Ainley and Lewis, 1974). This population of cormorants declined in size between the 1800's and the early 1900's as a result of disturbance by commercial egg collectors. The population has not yet recovered, although egg collecting stopped long ago. Its failure to do so may be related to the disappearance of the Pacific Sardine (*Sardinops caerulea*) from central and northern California (Ainley and Lewis 1974).

We compared the number of Double-crested Cormorants observed in the region north of Cape Mendocino during our study with Osborne's (1972) results and found that numbers had increased at three sites. Nests were absent from two other sites, but we found six additional colonies unreported by Osborne. The total number of Double-crested Cormorants in this region has apparently increased from 530 in 1970 to 1,200 in 1980. These few data suggest that Double-crested Cormorants may be increasing in number on the north coast of California, but since yearly variations in nesting effort occur and cormorants have shown a tendency to switch nesting islands often, caution in such speculation is recommended.

Human disturbance of Double-crested

Cormorant colonies can be very destructive (Ayers 1975). Cormorant eggs and chicks are vulnerable to gull predation when adults are frightened off their nests by human intrusion (Kury and Gochfeld 1975). Inland colonies have probably been disrupted to a greater extent than any other Double-crested Cormorant colonies in the state because of lake development and recreation (Kelly pers. comm.).

Little is known of the vulnerability of cormorants to oil, but few oiled birds have been found after California oil spills (Smail et al. 1972, Berkner pers. comm.). Cormorants are mobile and it is likely they can avoid oil spills to some degree. Unlike other seabirds, cormorants spend large amounts of time out of the water. The greatest numbers of Double-crested Cormorants are found along the coast in winter, since many inland breeding birds move to the coast at this time of year.

Brandt's Cormorant (*Phalacrocorax penicillatus*)



Brandt's Cormorants are the most abundant and conspicuous of the cormorants nesting on the California coast. Present the length of the California coast in summer, they leave areas of breeding concentration on the north coast and the Farallon Islands in early winter and disperse along the central and southern coast (Osborne 1972, DeSante and Ainley 1980).

Brandt's Cormorants usually nest on the flat tops of offshore islands or, less frequently, on inaccessible mainland bluffs and cliff ledges. During the breeding season, these cormorants present a striking appearance with their bright blue throat pouches and white feather plumes on the sides of their heads. At colonies, Brandt's Cormorants are opportunistic gatherers of nesting material (Hunt et al. 1979). They collect nearby grasses and herbaceous plants and pluck seaweeds from close tidal rocks. Once nests are constructed, continual additions are made, often with material stolen from neighboring nests (Palmer 1962).

Nesting adults stand on their clutches of chalky blue eggs, incubating with their webbed feet. The young are born without feathers, but soon are covered with coal black down. Nestlings feed by inserting their heads down the throats of their parents and removing partly digested fish remains.

Strong swimmers and divers, Brandt's Cormorants prey on various species of fish (Hubbs et al. 1970, Scott 1973, Baltz and Morejohn 1977). Clay (1911) has reported

Brandt's Cormorants caught in fishing nets at depths as great as 70 meters. These cormorants frequently feed in large flocks, often in company with other seabirds (Bent 1922).

CALIFORNIA COLONIES



Brandt's Cormorants usually form large colonies compared to most other California nesting seabirds. The largest aggregation of Brandt's Cormorants is on the Farallon Islands (429 012), where 28,000 birds nested in 1979 (Ainley pers. comm.). At least 13 colonies contain more than 1,000 birds.

Over the years, Brandt's Cormorant colonies shift from one location to another (Hunt et al. 1979, this study). Two hundred birds were recorded nesting on Casket Rock (379 009) in 1969; no nests were observed in 1979, but 330 birds nested there in 1980. Similar fluctuations occurred at White Rock (379 010), "333 Point" (379 032), and Arched Rock (404 006). Reasons for these movements are not well understood, but cormorants may have abandoned Prince Island (501 004) in 1977 because of a heavy flea infestation (Hunt et al. 1979).

HISTORICAL STATUS AND VULNERABILITY

Brandt's Cormorant populations in the Channel Islands have declined in size since they were first recorded there in the late 1800's (Hunt

Percent of California Breeding Population



et al. 1979). Hunt et al. (1979) speculate that they were affected first by human disturbance and later by the accumulation of pesticide residues. Thin eggshells, similar to those caused by DDE concentrations in Brown Pelicans and Double-crested Cormorants on the Channel Islands, were seen in Brandt's Cormorant eggs on San Nicolas Island (524 011) and Lion Rock (477 011) (Hunt et al. 1979, Frame 1972).

Brandt's Cormorants on the Farallon Islands declined in number during a period of high human disturbance in the mid-1800's. Populations began to increase in size after this period of exploitation, and by 1972 there were 22,000 Brandt's Cormorants breeding on the islands (Ainley and Lewis 1974). About 28,000 Brandt's Cormorants now occupy the Farallon Islands (Ainley pers. comm.).

Our population estimates for colonies along the remainder of the California coast are nearly double population figures from 1969 and 1970 (Osborne and Reynolds 1971). The difference may be due, at least in part, to more accurate censusing rather than to real population changes. It may also reflect an unusually high nesting effort in 1979.


Changes in ocean conditions from year to year apparently influence breeding populations of Brandt's Cormorants. Periods of upwelling, which bring cold, rich waters to the surface and trigger plankton blooms, are of great importance to seabirds. When warmer ocean waters prevail,

the quantity of food drops. Breeding populations of seabirds become smaller and reproductive success declines. Favorable ocean conditions in 1979 caused a boom year for Brandt's Cormorants on the Farallon Islands, where up to 28,000 birds nested. Conditions in 1980 were less favorable, and only about 16,000 birds nested there (Ainley pers. comm.).

Brandt's Cormorants are vulnerable to disturbance during the breeding season. Adults flush from their nests readily when approached by boats, low flying aircraft, or humans on foot. Once parents are away from the nests, Western Gulls are able to prey upon eggs and chicks. Repeated disturbance can cause permanent colony desertion.

Reported cormorant deaths from oil spills are not frequent (Berkner pers. comm.), and Brandt's Cormorants made up only one percent of the recovered birds in the 1971 San Francisco oil spill (Smail et al. 1972). The relative low number of oiled cormorants found on beaches may reflect a greater tendency to sink than in other seabird species (Harris per. comm.). Brandt's Cormorants are likely the most vulnerable of all cormorants to localized oil spills because of their large breeding concentrations.

Pelagic Cormorant (*Phalacrocorax pelagicus*)



The Pelagic Cormorant is the most ubiquitous cormorant in California. These smallest of the California cormorants can be seen during any season in their rocky coastal feeding grounds, where they propel themselves underwater with their strong webbed feet in pursuit of fish and shrimp (Robertson 1974, Hatler et al. 1978). Clay (1911) reported that Pelagic Cormorants are capable of diving to depths of up to 140 meters.

Pelagic Cormorants nest in scattered groups whose locations sometimes shift from one year to the next (Benz and Garrett 1978, Nysewander and Barbour 1979). Situated anywhere from hundreds of feet above the ocean to just within the spray zone, they raise their young in platform nests of seaweed built on small outcrops and ledges. These cliffside colonies stand out because of the summer whitewash they receive and can be seen for great distances.


Although Pelagic Cormorants are shy birds, their nesting activities may be observed at a judicious distance. One of the best locations in the state for observing their breeding behavior is Salt Point State Park (see Appendix B).

Pelagic Cormorants are often found nesting close to other cormorants. In these locations, direct competition is apparently reduced by staggered nesting chronologies and by differences in nest site selection, behavior, and in selection of food types, food sizes, and feeding locations (Benz and Garrett 1978, Robertson 1974).

CALIFORNIA COLONIES

Pelagic Cormorants nest in suitable habitat along the entire coast of California. Forty-four percent of the California population nest on offshore islands, while 56 percent nest on precipitous cliffs of the mainland. In some regions, small groups of nesting Pelagic Cormorants are scattered in a continuous band along the coast. In these areas our designation of colonies has sometimes been arbitrary. That is, the limits of colonies are often assumed for convenience to be geographical landmarks such as coves or points of land, and frequently long stretches of coastline are included under a single colony number. For example, the Triplett Gulch colony (404 021), one of the largest listed in the catalog, encompasses approximately two kilometers of coastline and numerous offshore rocks. Fish Rocks colony (404 003) on the other hand, although of similar magnitude, consists of two discreet islands in this same vicinity.

Although Pelagic Cormorants occur throughout the coastal region, certain areas of concentration stand out. Areas immediately north of San Francisco have a disproportionately large percentage of nesting birds, as do the Farallon Islands (429 012). Pelagic Cormorants occur in decreasing numbers farther and farther south of San Francisco to the southern terminus of their nesting range. This California distribution may reflect available nesting habitat or perhaps more subtle oceanographic or biological factors.



| Breeding Chronology | | Clutch = 3 - 7 (35, 37, 39) |
|----------------------------|--|-------------------------------|
| | | Incubation Period = 33 days |
| | | Nesting Period = 40 - 50 days |
| Northern California | egg laying ? hatching ? fledging ? adults present | (35) |
| Farallon Islands | egg laying hatching fledging adults present | (1) |
| Channel Islands | egg laying ? hatching ? fledging ? adults present | (29) |
| Jan. | Feb. | Mar. |
| Apr. | May | June |
| July | Aug. | Sep. |
| Oct. | Nov. | Dec. |

HISTORICAL STATUS AND VULNERABILITY

Detailed information on the historical status of Pelagic Cormorants exists for only limited portions of the California coast. In the Channel Islands there has been little change in either total number or distribution during the last century (Hunt et al. 1979). In contrast, Pelagic Cormorant populations on the Farallon Islands (429 012) declined greatly in size during the 1850 to 1900 period of egg collecting (Ainley and Lewis 1974). The population has been recovering throughout this century and is still increasing in 1980 (Ainley pers. comm.).


Historical population estimates for northwest California are available from Osborne and Reynolds (1971), although differences in time of survey and survey technique limit comparisons with our 1979-80 data. The tendency of Pelagic Cormorants to move nest sites in succeeding years (Benz and Garrett 1978, Nysewander and Barbour 1979), makes surveys of large areas desirable for this species.

Shoreline use and development pose a great threat to Pelagic Cormorants in California. Cormorants can be disturbed by any human activity near colonies. Approach to nesting birds by boats, planes, and humans on foot may force adults off their nests, leaving eggs and young chicks unprotected. Chicks and eggs may be knocked from nests and predation by Western Gulls and Common Raven may increase following the adults' panicked retreat.

Pelagic Cormorants, like other members of the order Pelecaniformes, may be vulnerable to pesticide pollution. The egg shell thinning, egg breakage, and subsequent population declines experienced by both Brown Pelicans and Double-crested Cormorants in southern California (Gress et al. 1973) are yet undocumented for Pelagic Cormorants (Hunt et al. 1979).

Oil spills in California have resulted in few known cormorant deaths to date (Aldrich 1938, Moffitt and Orr 1938, Smail et al. 1972, and Berkner pers. comm.). Because of their widespread distribution and ability to shift colony sites, Pelagic Cormorant populations are relatively resistant to localized oil slicks. Individual cormorants may avoid surface oil (Berkner pers. comm.), and their habit of spending nights and much of the day roosting on rocks further reduces vulnerability to oil pollution (Smail et al. 1972).

Black Oystercatcher (*Haematopus bachmani*)



Black Oystercatchers are shorebirds of the outer coast of the northwest Pacific. Adults establish breeding territories on mainland rocky beaches and offshore rocks and islands. An oystercatcher nest, composed of a scrape lined with pebbles and shell fragments, is surprisingly difficult to find. One to three cryptically colored eggs are placed directly on the pebbles.

Black Oystercatcher young are precocial and may leave the nest within hours of hatching. Although they remain near the nest at first, within a few days chicks follow adults to intertidal foraging areas. The California mussel (*Mytilus californianus*) is the chief food of oystercatchers in the Channel Islands (Hunt et al. 1979) as well as in northern California (Helbing 1977), and limpets and chitons make up most of the remainder of the diet. Chicks at the nest are frequently fed crabs (Hartwick 1976, Helbing 1977).

Mortality among eggs and chicks is apparently high. Hartwick (1974) lists gull predation as an important cause of mortality. In addition, chicks and eggs are frequently washed "overboard" from nests by storm waves.

During the winter, oystercatchers are gregarious (Webster 1941) and can be observed feeding along rocky portions of the California coast. With their bright orange bills, pink feet, and loud distinctive call, these birds are conspicuous.


CALIFORNIA POPULATION

Black Oystercatchers are a non-colonial nesting species, although they are usually found on the same offshore islands and rocks as colonial nesting seabirds. They establish large nesting and feeding territories and thus distribute themselves along the available coastal habitat. Actual nests were pinpointed only for a small percentage of the sites listed in this catalog. Nesting was indicated more often from the territorial defense behavior of adults. This method obviously has limitations since approach to a nest must be close enough to initiate a reaction from the adults. For this reason the catalog total for this species is almost certainly low. The actual breeding population size is probably about 1,000 birds.

Information presented in this catalog gives a good representation of the overall breeding pattern of this species, a population of single nesting pairs widely dispersed along the entire California coastline. Concentrations of 242 Black Oystercatchers in the Channel Islands and 40 breeding birds in the Farallon Islands (429 012) represent nearly half of the catalog breeding total.

HISTORICAL STATUS & VULNERABILITY

Black Oystercatchers disappeared from the



Farallon Islands in the 1860's, possibly as a result of too much human disturbance. A few birds were seen in 1903, but oystercatchers were not observed there on a regular basis until 1956. The breeding population of Black Oystercatchers on the Farallon Islands increased to 16 by 1959 and to 40 in 1972 (Ainley and Lewis 1974). Since that time the population has stabilized and may be at its maximum (Ainley pers. comm.). Historical population information for areas other than the Farallon Islands is almost nonexistent.

Black Oystercatchers require clean and undisturbed rocky coastlines for nesting and feeding. To the extent that these areas are disturbed by humans, reproductive success will be reduced. Oil spills, which foul rocky coastlines where oystercatchers feed, could seriously affect the food supplies of this species, but losses of birds from direct oiling would probably be low. Long-term degradation of intertidal habitat would almost certainly cause population declines.



Black Oystercatchers

Photo by Ian C. Tait

Western Gull (*Larus occidentalis*)



Western Gulls are the breeding gull of the California coast. They breed as far south as Baja California, Mexico, and as far north as Washington and southern British Columbia. Western Gulls in Washington and British Columbia are sympatric with Glaucous-winged Gulls (*Larus glaucescens*) with which they hybridize extensively (Hoffman et al. 1978).

Western Gulls nest in a wide variety of habitats, but usually are found in the greatest densities on the flatter portions of islands and offshore rocks. Some nest on the mainland and these nests are always confined to areas inaccessible to mammalian predators such as steep slopes and cliff faces. Western Gulls will even nest on man-made structures. Their nests are substantial and are usually constructed of vegetation gathered near the colonies. Western Gulls usually lay clutches of from one to three eggs, although in the Channel Islands clutches of from four to six eggs result from female-female pairing. The eggs in these supernormal clutches are usually infertile and do not hatch (Hunt and Hunt 1977).

Western Gulls feed on a variety of prey. Important food items from around the Farallon and Channel Islands include anchovies, rockfish (*Sebastes*), Pacific Sauries (*Cololabis saira*), midshipmen (*Porichthys*), cephalopods, euphausiids, barnacles, and offal (Ainley and Sanger 1979, Hunt et al. 1979). Like large gulls elsewhere in the world, Western Gulls often feed on human refuse at dumps scattered along the coast.

CALIFORNIA COLONIES


Although Western Gulls breed widely along

the California coast, most of the breeding population is concentrated at a few sites. The 32,000 gulls of the Farallon Islands (429 012) make up more than 60 percent of the entire breeding population in California. Other large colonies in California are at Middle Anacapa Island (502 008) with 5,000 Western Gulls, Santa Barbara Island (524 008) with 2,300 gulls, San Nicolas Island (524 011) with 1,800 gulls, Castle Rock (325 006) with 1,350 gulls, and Prince Island (501 004) with 960 gulls. Most of the Western Gull colonies in California, however, are much smaller. Sixteen of the remaining sites have between 100 and 500 birds, 22 sites have between 50 and 100 birds, and 115 sites have fewer than 50 birds.

HISTORICAL STATUS AND VULNERABILITY

Western Gulls are probably the least likely of California seabirds to suffer population declines as a result of man's activities. The population may in fact be growing as the result of an abundant food supply at garbage dumps. Increases in numbers of large gulls may not be desirable since these birds can harm other seabirds and interfere with aircraft at airports.

Increases in the size of several populations of large gulls have been attributed to the availability of human food wastes and sewage (Drury 1979, Kadlec and Drury 1968, Vermeer 1963). Both Herring Gulls (*Larus argentatus*) and Great Black-backed Gulls (*Larus marinus*) in eastern North America have increased in number and caused substantial damage to tern and Atlantic Puffin (*Fratercula arctica*) colonies by usurping optimal nesting habitat, stealing food (kleptoparasitism), and eating eggs and chicks (Nettleship 1972, Nisbet 1973).



Populations of Western Gulls in California have probably also increased in size during the last two decades, but documentation is difficult to obtain, since historical data for much of the California coast are lacking. Osborne and Reynolds (1971) censused many of the large Western Gull colonies in central and northern California, but their data may not be comparable with ours. Certainly differing survey techniques account for some of the differences between the two sets of data. We were able to make a comparison of Osborne and Reynolds' data and our data for 26 sites and found more Western Gulls at 20 sites in 1979 and 1980 than in 1970, fewer at four sites, and no change at two sites. The apparent net increase in numbers of breeding Western Gulls at these 26 sites is about 1,600 birds. In addition, we found many previously undiscovered sites. This probably reflects in part, our more complete coverage of the coast. These comparisons suggest that the number of Western Gulls in California may have increased during the last decade.



Other evidence suggesting that numbers have increased comes from the Farallon Islands and Prince Island (501 004). The number of Western Gulls on the Farallon Islands plummeted in the mid-late 1800's primarily because of egg collecting and disturbance from domestic animals (Ainley and Lewis 1974). The population recovered in size to about 23,000 birds in 1959 and remained stable until 1972 (Ainley and Lewis 1974). Since then the population has increased to 32,000 birds and there appears to be a surplus of adult-plumaged birds. On Prince Island, a population of about 500 birds in 1968 (Huber 1968) increased to about 1,000 birds in 1976 (Hunt et al. 1979). On Santa Barbara Island, however, there has been a

marked decline in numbers of Western Gulls since 1972, which appears to be related to the abundance of anchovies (Hunt and Butler 1980).

The effects of an increasing population of Western Gulls on other seabirds are difficult to assess. Western Gulls are the most important predators of storm-petrels and Cassin's Auklets on the Farallon Islands (Manuwal 1974, Ainley et al. 1974), and further increases in Western Gull numbers may increase the rate of predation. Increases in Western Gull numbers elsewhere in California could have a similar effect on small alcids and storm-petrels. Western Gulls kleptoparasitize cormorants, Rhinoceros Auklets, and probably Tufted Puffins. The present rate of incidence is unknown but may increase if gull populations continue to expand.

This species is probably one of the least vulnerable to oil spills of all seabird species nesting in California, since they are highly mobile and frequently return to land to rest and roost. Western Gulls, like other surface nesting seabirds, are susceptible to disturbances while nesting. Disturbance in a particularly dense colony may result in intraspecific pirating of eggs and cannibalism. Chicks frightened from their territories may be killed by neighboring gulls or become lost and starve. Nevertheless, the future of the Western Gull in California looks secure. With the present pattern of waste disposal in California, Western Gulls will probably continue to increase in number. Because of their relatively high reproductive potential, an excess of non-breeding adults, and their ability to feed on a wide variety of prey, they would likely make a rapid recovery from any decline.

Common Murre (*Uria aalge*)



Common Murres are some of the most highly colonial of all seabirds. Island and mainland colonies are usually densely packed shoulder to shoulder with these noisy, gregarious birds. Common Murres breed in both the North Pacific and North Atlantic Oceans and are some of the most abundant seabirds in the northern hemisphere.

Common Murres prefer to nest on wide, flat cliff ledges and the tops of islands. A large, single egg is laid on bare rock or soil and is narrowly pointed at one end and broad and rounded at the other. Murre eggs vary greatly in color, ranging from white to buff, brown, reddish, blue, or green. They are almost always marked with dark dots, blotches, or intricate scribbling (Harrison 1978). The unique pattern of each egg probably aids individual recognition by adults (Johnson 1941).

Murre chicks are fed by both parents and jump from the colonies to the waters below when only partly grown. They are accompanied at sea by only one parent, usually the male (Varoujean pers. comm.).

Common Murres are good fliers and are capable of foraging long distances from their colonies. They dive to considerable depths and include fish, crustaceans, and cephalopods in their diet (Ogi and Tsujita 1973, 1977). Common Murres are often seen in coastal California during the fall and winter months (Ainley 1976) and make frequent landfalls at their colonies during these seasons.

CALIFORNIA COLONIES

In California, Common Murres breed from


Castle Rock (325 006) in the northern part of the state south to Hurricane Point Rocks (454 011) at the north end of the Big Sur coast. They are known to breed at 19 sites in California and a few non-breeders have been seen on three additional islands. These three islands, Kibesillah Rock (379 004), White Rock (379 010), and Gualala Point Island (404 004), all appear to have suitable nesting habitat and should be watched for future nesting.

Colonies of Common Murres, although easy to find, are difficult to census. Variables such as time of year, time of day, and the unknown breeding status of many individuals complicate an already difficult task (see Materials and Methods). The estimates of murre numbers presented here and in the tables include the number we actually counted or estimated, plus two-thirds of that number to account for members of the breeding pair away from the colony (Ainley 1976).

Colonies of Common Murres in California vary greatly in size, from as few as 50 birds on Sisters Rocks (325 008) to 126,000 birds on Castle Rock. Other large colonies of murres exist at the Farallon Islands (429 012) with 60,000 birds, Green Rock (325 020) with 55,000 birds, False Klamath Rock (325 010) with 26,500 birds, and Flatiron Rock (325 023) with 24,000 birds.

HISTORICAL STATUS AND VULNERABILITY

Two lines of evidence suggest that Common Murres are presently increasing in number in California. First, in 1979 and 1980 Common Murres were found breeding at four sites where murres were not observed by Osborne and Reynolds (1971), although they censused these



same Islands for other species. These islands are: Sisters Rocks, Blank Rock (325 024), Pilot Rock (325 026), and Cape Vizcaino (379 002). Murres may have been present at Cape Vizcaino during the years of Osborne's work but could have left the colony prior to his survey in August. Second, there are 14 breeding colonies of Common Murres for which both Osborne and Reynolds (1971) and we have estimates. Our estimates greatly exceed theirs in all cases, usually by a factor of two, three, four, or more. Even if the two-thirds attendance factor is subtracted from our estimates, our totals still exceed Osborne and Reynolds' in all but two cases. In the two instances where ours are lower, Castle Rock and Green Rock, the two estimates are similar.

Apparently murre numbers have been increasing throughout much of this century. Osborne (1972) found that the population of Common Murres in the region from Cape Mendocino to the Oregon border has increased from a few thousand birds in the 1910's to about 143,000 birds in 1970. The history of Common Murre populations at two other sites also suggests that numbers are increasing. Clay (unpubl. field notes) makes no mention of Common Murres at Flatiron Rock between 1910 and 1934, but Osborne estimated that 10,000 birds were present there in 1970. Our estimate for this site in 1979 is 24,000 birds. Clay (unpubl. field notes) estimated 2,000 birds at Green Rock in 1941, compared to Osborne's estimate of 40,000 in 1970 and our estimate of 55,000 in 1980.


Common Murres on the Farallon Islands are also increasing in number but in this case the

increase follows a documented severe population reduction. Between 1854 and 1959 the population dropped from 400,000 birds to between 6,000 and 7,000 birds. A commercial egg harvest and oil pollution were the primary causes of this reduction (Ainley and Lewis 1974). With strict protection, the population increased to 20,500 birds in 1972 and to 60,000 birds or more at the present time.

Common Murres formerly bred on Prince Island (501 004) in the Channel Islands but no longer do so. Hunt et al. (1979) states, "Since the tiny colony at Prince Island was so far south of the nearest murre colony, it seems likely that repeated visits by early egg collectors, coupled with the slim possibility of recruitment from other colonies, could have eliminated murres as a breeding species. . . ."

Nesting Common Murres are very sensitive to disturbance by boats, low-flying aircraft, and humans on foot. When disturbed, adults flush from the colonies and may knock eggs and chicks from nest sites. The remaining chicks and eggs are subject to increased predation from gulls and ravens. Common Murres are highly vulnerable to oil contamination and were some of the most frequently oiled birds in the 1971 San Francisco oil spill (Smail et al. 1972). They are common in the coastal zone of California throughout the year and spend large amounts of time on the water. They appear to be highly social during both the breeding and non-breeding seasons and frequently congregate on waters adjacent to their colonies. Future oil spills along the California coast could kill large numbers of this species.

Pigeon Guillemot (*Cepphus columba*)



Pigeon Guillemots inhabit the nearshore zone and are usually found along stretches of rock coastline. They are most easily observed in the early morning, before the egg laying season, when both members of each pair frequent waters adjacent to their colonies.

Pigeon Guillemots usually nest in natural rock crevices, talus, and boulder beaches (Thoresen and Booth 1958, Drent 1965). They also use burrows dug into loose conglomerate bluffs and man-made structures, such as wharf timbers, drain pipes, and within truck tires slipped on wharf pilings (Campbell 1977, this study). In some regions of California, Pigeon Guillemots and introduced Rock Doves (*Columba livia*) may be competing for nesting space.

Pigeon Guillemots are some of the few alcids to regularly lay two eggs (Bent 1946, Thoresen and Booth 1958, Drent 1965). Eggs are laid on bare rock, soil, or sometimes on a bed of pebbles and shell fragments. Guillemots usually feed close to shore and the proximity of the feeding grounds to the colonies may help explain their ability to sometimes raise two chicks. Pigeon Guillemots, like all members of the family Alcidae, dive for food using their wings for propulsion. In California, fish are the principal food of guillemots during the breeding season (Follett and Ainley 1976). This appears to be true throughout their breeding range although near Kodiak, Alaska, Pigeon Guillemots are known to eat small crabs and shrimp (Krasnow et al. 1978).

Following breeding, Pigeon Guillemots largely disappear from the California coastline and


do not reappear until just before the next year's breeding season. Their wintering range is presently unknown but we suspect that a northward movement of birds takes place.

CALIFORNIA COLONIES

In California, Pigeon Guillemots breed from the Oregon border south to Santa Barbara Island. They are found breeding in large aggregations of up to 3,000 birds, in smaller groups of only a few birds, or as isolated pairs scattered along the coast in suitable habitat. Delimiting colonies is often difficult, especially in those regions where Pigeon Guillemots are spread along the coast. In many cases, colony boundaries have been based on geographical landmarks and cover large sections of coastline.

The catalog total of Pigeon Guillemots in California is about 12,000. We feel that this number is conservative, although for any individual nesting site our estimates may be either high or low. Censusing Pigeon Guillemots is at best an inexact science and is complicated by several factors (see Materials and Methods). Although many Pigeon Guillemot colonies were surveyed in both 1979 and 1980, only the best of the estimates for these two years are included in this catalog.

The Farallon Islands (429 012), with 3,000 birds, have the largest population of Pigeon Guillemots in California. The coastline between Davenport and Point Santa Cruz (454 021) is inhabited by about 1,300 guillemots. Other locations with large numbers are Point Arguello



| Breeding Chronology | | Clutch = 1 - 2 (1, 18) |
|---------------------|--|----------------------------------|
| | | Incubation Period = 30 - 32 days |
| | | Nesting Period = 35 - 45 days |
| Northern California | egg laying hatching fledging adults present | (35, 42) |
| Farallon Islands | egg laying hatching fledging adults present | (1) |
| Channel Islands | egg laying hatching fledging adults present | (29) |

Jan. | Feb. | Mar. | Apr. | May | June | July | Aug. | Sep. | Oct. | Nov. | Dec.

(501 010), Fish Rocks (404 003), Castle Rock (325 006), Sugarloaf Island (325 041), and Prince Island (325 003). Generally, however, Pigeon Guillemot colonies are small. More than half the sites we investigated had fewer than 30 birds.

HISTORICAL STATUS AND VULNERABILITY

Few data pertaining to the historical status of Pigeon Guillemots are available. On the Farallon Islands, Pigeon Guillemots escaped early persecution by commercial egg collectors but later fell victims to oil pollution (Ainley and Lewis 1974). The guillemot population of the Farallon Islands reached an all-time low of 200 in 1911. Since then it has recovered steadily, to 1,000 birds in 1959, 2,000 in 1972, and 3,000 at present (Ainley pers. comm.).

Elsewhere along the California coast it may appear from the data that Pigeon Guillemot numbers have increased dramatically. However, we do not feel there is sufficient information to make this judgement. Previous investigators largely overlooked Pigeon Guillemots since they often nest in low densities and usually do not form distinct colonies. Censusing Pigeon Guillemots requires much time and manpower and access to many nesting sites is poor. Time of day and of year can greatly influence survey results and some previous surveys were conducted after Pigeon Guillemots had finished nesting.

Compared to other seabirds such as Common Murres and Brandt's Cormorants, Pigeon Guillemots are not highly prone to disturbance, primarily

because of their comparatively low nesting densities and inaccessible nest sites. Pigeon Guillemots will, however, readily desert their nests if disturbed during incubation or brooding.

Like murres, Pigeon Guillemots are very vulnerable to oil pollution. Guillemots spend large amounts of time on the water, usually close to land where oil exploration and development are concentrated. Fortunately, the population of Pigeon Guillemots in California is widely distributed along the coast and any oil spill would most likely affect only local birds.



Pigeon Guillemots occasionally nest in man-made structures like this tire on a Crescent City dock. Photo by Anthony R. DeGange

Marbled Murrelet (*Brachyramphus marmoratus*)



Drawing by Allan Brooks, compliments of *The Murrelet*, A Journal of Northwest Ornithology and Mammalogy.

The Marbled Murrelet is the only breeding alcid in California that has become adapted to nesting habitats inland from coastal rocks and beaches. The locations of Marbled Murrelet nests are the least known of all the seabirds breeding in California. Only four nests have been found throughout the species' entire range; one in Siberia (Kuzyakin 1963), one in California (Binford et al. 1975, Singer and Verardo 1975), and two on East Amatuli Island in the Barren Islands, Alaska (Simon 1980). Kiff (in press) has recently reviewed the known eggs and nests of this species.

Of the four nests, both the Siberian and California nests were found in trees, but the Alaskan nests were found on the tundra of a treeless island. The Siberian nest was found in the upper branch of a Larch (*Larix dehurica*) 6.8 meters above the ground (Kuzyakin 1963). The California nest was found 45 meters above the ground on a moss-covered limb of a Douglas-fir (*Pseudotsuga menziesii*) in Big Basin Redwoods State Park, Santa Cruz County (Binford et al. 1975). This nest contained a Marbled Murrelet chick sitting in a small depression encircled by droppings.


Binford et al. (1975) theorize that the pale green egg, the cinnamon brown breeding plumage of the adult, and the light brown nestling are cryptic adaptations for nesting in trees. The entire breeding population of Marbled Murrelets in California is suspected to nest in trees.

Marbled Murrelets seen at sea during the summer are often in pairs and are usually within 1 to 2 kilometers of the coast. Breeding birds return to their nests in the evening and depart at dawn. We have observed individual birds, pairs, and groups of up to 60 birds in the breeding season flying over the tree tops at the margin of old growth Coast Redwood (*Sequoia sempervirens*) forests. An amazing display of this behavior can be seen at Prairie Creek Redwoods State Park in Humboldt County (Appendix B). Marbled Murrelets may also use coastal forests in winter as evidenced by calling birds flying over the redwood forests during this season (Strachan pers. comm.).

Marbled Murrelets like all other alcids, spend a large percentage of their time on the ocean. They feed on fish and less frequently on crustaceans (Sealy 1975b).

CALIFORNIA POPULATION

We observed Marbled Murrelets during the breeding season on coastal waters from the California-Oregon border south to Point Sal, Santa Barbara County. However, two areas of concentration stand out: coastal waters from Eureka to the California-Oregon border and from Santa Cruz to Half Moon Bay. These two regions respectively account for 76 and 14 percent of our 185 Marbled Murrelet sightings made during the 1979 breeding season. During this season our



coverage of the central and northern California coasts was virtually complete. These two regions were again censused in 1980, when we made 390 sightings of Marbled Murrelets, but our coverage of the coastline in that year was less complete. Both regions of high Marbled Murrelet concentration are offshore of mature stands of coniferous trees. This suggests that murrelets may require these trees for nesting. After breeding, Marbled Murrelets disperse along the coast of California. They have been recorded as far south as Imperial Beach, San Diego County (McCaskie 1980).

It is difficult to estimate the breeding population of Marbled Murrelets in California, but we speculate that it is about 2,000 birds. This estimate may be conservative since this small alcid's breeding habits are poorly known. It is difficult to see them at sea in other than perfect conditions, and it is likely that other unobserved murrelets were farther out to sea during our boat surveys. Our observations of Marbled Murrelets were made from a boat incidental to surveys of other nesting seabirds. These surveys were not designed to census Marbled Murrelets in the most accurate fashion but we hope these results shed some light on the species' nesting distribution in the state. Further work on Marbled Murrelets is certainly needed and our individual sight records may be of future use to anyone attempting a more complete survey of this species. All records of our observations are included in the Colony


Status Records and in our field notes (Appendix A).

HISTORICAL STATUS AND VULNERABILITY

There is little information on the historical status of Marbled Murrelets in California. Disturbance to nesting Marbled Murrelets probably has been and will continue to be primarily through the destruction of nesting habitat. Populations of Marbled Murrelets may have been reduced by the destruction of virgin coastal forests, although no data are available. The old growth stands of the coast redwood alone have been reduced in area from an estimated 809,000 hectares (2,000,000 acres) to 93,000 hectares (230,000 acres) (Veirs pers. comm.). We suspect that Marbled Murrelets were formerly more abundant than they are today.

Marbled Murrelets are vulnerable to oil contamination since they are often found on waters very close to land. An oil spill along the coastlines of Humboldt - Del Norte Counties or San Mateo - Santa Cruz Counties could endanger a murrelet population that is highly concentrated during the summer months along those two stretches of coastline.

Xantus' Murrelet (*Endomychura hypoleuca*)



The breeding range of the Xantus' Murrelet is restricted to the Channel Islands and the west coast of Baja California, Mexico. This species and the closely related Craveri's Murrelet (*Endomychura craveri*) are thought to be reproductively isolated, even though a small zone of sympatry exists in the San Benitos Islands, Mexico (Jehl and Bond 1975). Before intensive research was begun on Xantus' Murrelets in 1975 by Hunt et al. (1979), little was known about their life history. Most of the information in this account was taken from that study.

Xantus' Murrelets nest primarily in rock crevices along or near cliff ledges, but also under bushes, in ground vegetation, in abandoned rabbit burrows, under old pelican nests, and in man-made debris (Hunt et al. 1979). These murrelets, unlike most alcids, usually lay two eggs annually. Eggs are incubated under the wings, next to lateral brood patches on each side of the body.


During the breeding season, Xantus' Murrelets spend daylight hours either in the nest or foraging at sea. Other colony activities, such as nest-site selection, incubation shift changes, and fledging, occur at night (Hunt et al. 1979). Xantus' Murrelet chicks are highly precocial and fledge at about two days of age. The small, flightless, downy young leave their nests at night and scurry to the shoreline. Upon reaching the ocean, they plunge in and head far out to sea with their parents. Chicks waylaid during the night or

attempting to leave the nests during the day are quickly eaten by Western Gulls.

Xantus' Murrelets dive for food and feed extensively on larval fish. Northern Anchovies, Pacific Sauries and rockfish (family Scorpaenidae) are the most important species taken by Xantus' Murrelets in the Channel Islands (Hunt et al. 1979). Of these, Northern Anchovies are the most important and their availability may dramatically influence the breeding success of Xantus' Murrelets (Hunt and Butler 1980). Xantus' Murrelets often forage in the immediate vicinity of their colonies during the breeding season, but disperse widely thereafter.

CALIFORNIA COLONIES

All California colonies of Xantus' Murrelets are in the Channel Islands. Santa Barbara Island (524 008), where 2,000 to 4,000 birds are estimated to breed, is the most important colony for this species in California. Hunt et al. (1979) have conducted studies of this species' breeding biology and at-sea distribution at this site. All remaining colonies of Xantus' Murrelets in California are small. Of these, Prince Island (501 004) and Sutil Rock (524 009) are the largest, each with 150 birds, followed by East Anacapa Island (502 009) with fewer than 40 birds, Snag Rock (524 007) with 30 birds, and Gull Rock



(524 001) with two birds. Xantus' Murrelets probably also breed at Scorpion Rock (502 010) and Castle Rock (501 005), and small numbers may occasionally breed at other locations in the Channel Islands (Hunt et al. 1979).

HISTORICAL STATUS AND VULNERABILITY

The population of Xantus' Murrelets on Santa Barbara Island is apparently recovering from a drastic decline. Between 1897 and 1908, feral cats (*Felis catus*) were introduced onto Santa Barbara Island. Few data on the size of the murrelet population prior to the cats' introduction exist, but Sumner (1939) states, "At one time large colonies of auklets and murrelets were present on the island, but none have been recorded in recent years and it is supposed that they have been exterminated by these feral cats". By 1975 the population of cats was reduced to perhaps a single animal and Xantus' Murrelets are now some of the most abundant of breeding seabirds on the island (Hunt et al. 1979).

Natural predators of Xantus' Murrelets include the Peregrine Falcon (*Falco peregrinus*), Deer Mouse (*Peromyscus maniculatus*), and the Island Fox (*Urocyon littoralis*). Peregrine Falcons were once common residents of the Channel Islands, but now are only present as migrants. Their decreased presence may have contributed to the Xantus' Murrelet recovery on

Santa Barbara Island (Hunt et al. 1979).

An insular subspecies of Deer Mouse resides on each of the eight large Channel Islands (Nelson and Goldman 1931). They are known to prey on eggs and possibly chicks of the Xantus' Murrelet, but their presence is not a deterrent to successful reproduction (Hunt et al. 1979, Winnet et al. 1979).

The Island Fox is present on all large Channel Islands, except Anacapa and Santa Barbara Islands, the only two islands with large seabird colonies. The presence of foxes on the other large islands may account for small populations of seabirds there.

Because Xantus' Murrelets, like other alcids, spend a lot of time on the water and dive for food, they are vulnerable to oil spills. Location of spills in the California Bight during the breeding season would be the most critical, since adults and recently hatched flightless chicks would be concentrated near their colonies.



Xantus' Murrelet Chick

Cassin's Auklet (*Ptychoramphus aleuticus*)



The Cassin's Auklet is one of the most widespread members of the family Alcidae in the North Pacific. Cassin's Auklets build their nests in burrows on offshore islands that have a sufficient mantle of soil. These tiny alcids are nocturnal at their breeding colonies and are likely the most pelagic of all the California alcids (Hunt et al. 1979). A population is present on the Farallon Islands (429 012) all year, but wintering northcoast birds are found between 10 and 50 miles offshore (Manuwal 1974a, Yocom and Harris 1975).

Throughout their range Cassin's Auklets usually nest in burrows, but on the Farallon Islands birds also may use rock crevices, debris piles, cracks under buildings, and large caves (Thoresen 1964). Each female lays a single creamy white egg, but may lay a second egg if the first egg is destroyed (Manuwal 1974a). Adult Cassin's Auklets develop two incubation patches on the body, one beneath each wing (Manuwal 1974b). These incubation patches are found only among several species of alcids, including Xantus' Murrelets, Rhinoceros Auklets, and Tufted Puffins. Breeding Cassin's Auklets also develop a gular pouch, used to store food for young that are fed by regurgitation at night (Speich and Manuwal 1974). Small fish and pelagic crustaceans form the mainstay of the diet of Cassin's Auklets (Manuwal 1974a, Hunt et al. 1979).


CALIFORNIA COLONIES

Cassin's Auklets breed in California from the Channel Islands to Castle Rock (325 006). Of the known colonies in California the Farallon Islands colony is by far the largest, containing 105,000 auklets. Of the 23,000 Cassin's Auklets nesting in the Channel Islands, 20,000 are found on Prince Island (501 004). Castle Rock, near the Oregon border, has an estimated population of 3,600 birds.

Cassin's Auklets are difficult to census because of their nocturnal lifestyle, burrow nesting habits, and highly pelagic nature. We found no new colonies during our surveys and have made no new population estimates for this species.

HISTORICAL STATUS

Surprisingly, Cassin's Auklets were rare on the Farallon Islands in the mid-1800's. Ainley and Lewis (1974) relate this scarcity to a period of more than two decades when warm, tropical water moved north along the California coast. They hypothesize that populations of Cassin's Auklets increased when cold water returned to the region. Now Cassin's Auklets are the most abundant birds on the Farallon Islands.




Osborne (1972) estimated that numbers of Cassin's Auklets on Castle Rock increased from 100 seen in 1959 by Thoresen (1964) to 3,600 in 1970. Cassin's Auklets formerly bred on Flatiron Rock (325 023) as late as 1934 (Clay unpubl. field notes). Osborne (1972) believes that soil erosion was the principal reason for their extirpation from this island.

Western Gulls prey heavily on Cassin's Auklets at Castle Rock and the Farallon Islands (Thoresen 1964). Young are pulled by gulls from shallow burrows and adults are killed at night when they unfortunately land at the feet of roosting gulls (Thoresen 1964).

Cassin's Auklets are vulnerable to disturbance from humans and to the depredations of introduced predators such as rats. Cassin's Auklets may desert their nests if disturbed during incubation and their burrows can easily be caved in by unwary visitors to their colonies. Fortunately, all colonies of Cassin's Auklets in California except Green Rock (325 020) are protected.

Cassin's Auklets feed from the ocean surface in large social flocks where they are highly vulnerable to oil contamination (Hunt et al. 1979). An oil spill near the Farallon Islands, where 80 percent of the state's population breeds, would be particularly damaging to this species.

Rhinoceros Auklet (*Cerorhinca monocerata*)



The Rhinoceros Auklet is an uncommon breeding seabird in California. It derives its name from the keratinous "horn" found on its bill during the breeding season. Although this species' common name implies it is an auklet, the Rhinoceros Auklet is more closely related to the puffins. Rhinoceros Auklets are excellent divers and feed on small fish and cephalopods (Heath 1915, Richardson 1961, Leschner 1976).

Rhinoceros Auklets nest primarily in burrows dug into the ground on both forested and un-forested islands. Burrows may be up to 6 meters in length and often fork two or three times before ending in a nesting cavity (Heath 1915, Willett 1915). The recent discovery of Rhinoceros Auklets at Sea Lion Caves, Oregon (Scott et al. 1974, Varoujean and Pitman 1980) and at caves in the conglomerate cliffs at Point Arguello (501 010) indicates that this species may also nest in rocky mainland habitats.


Rhinoceros Auklets almost always enter and leave colonies at night when feeding chicks. This predominantly nocturnal behavior may have evolved as a means to reduce kleptoparasitism by gulls. In California and Oregon, Rhinoceros Auklets can often be observed on or near colonies during the day, but farther north they appear to be strictly nocturnal. This difference remains unexplained but may be related to the availability of food and its proximity to the colonies. Despite their diurnal tendencies in California, Rhinoceros Auklet colonies are some of the most difficult to find and census of all colonies of breeding seabirds in the state.

CALIFORNIA COLONIES

Rhinoceros Auklets are known from eight sites in California, but breeding has been confirmed at only three: Prince Island (325 003), Castle Rock (325 006), and the Farallon Islands (429 012). At the remaining five sites we have observed Rhinoceros Auklets in breeding plumage on or near the colony and suspect breeding occurs. Small numbers of Rhinoceros Auklets likely occur at several more sites, particularly in northern California.

Up to five birds were seen on Green Rock (325 020) at one time and birds were observed entering burrows on several occasions. As many as 38 Rhinoceros Auklets have been seen in the water next to or flying in the vicinity of Green Rock at one time. Rhinoceros Auklets have been suspected to breed at this site for several years (LeValley pers. comm.). At Gualala Point Island (404 004), Fish Rock (404 003), and Arched Rock (404 006), the presence of birds on the water immediately adjacent to the rock or doing "fly-by's", and the presence of suitable burrows, strongly suggests breeding at these sites. Rhinoceros Auklets are also suspected to breed at Little River Rock (325 035); (Harris pers. comm.).

Point Arguello (501 010) may support a mainland colony of breeding Rhinoceros Auklets in California. We observed a maximum of 24 birds on 11 June 1980. A minimum of 13 birds were discovered entering and leaving small caves in the cliffs on 17 and 18 July 1980. An examination of these caves was inconclusive.



HISTORICAL STATUS AND VULNERABILITY

Rhinoceros Auklets were first found breeding at Castle Rock (325 006) in 1917 when Clay (pers. comm. in Osborne 1972) claimed to have found one nest. Clay, who periodically visited many of the seabird islands in northern California, makes no further mention of this species. Osborne (1972), after his 1969 and 1970 surveys, estimated a population of between 100 and 150 Rhinoceros Auklets on Castle Rock. He revisited the island in 1977 and felt the population had increased to 200 birds (Osborne pers. comm.). To avoid disturbing the seabirds at Castle Rock we conducted no new groundwork there during this study.

Rhinoceros Auklets were known to breed on the Farallon Islands in the early 1800's but disappeared in the 1860's, possibly as a result of collecting by overzealous scientists. They were not observed there again until 1971, and in 1972, two or three pairs were present (Ainley and Lewis 1974). Presently about 100 Rhinoceros Auklets are suspected to breed on the Farallon Islands and the population is thought to be expanding (Ainley pers. comm.).

Before 1979, Rhinoceros Auklets were known to nest only as far south as the Farallon Islands. Although our observations at Point Arguello do not constitute a breeding record we are confident that they are breeding there or will do so in the near future. This would represent a range extension of some 350 kilometers.


Rhinoceros Auklets are very sensitive to

disturbance during the nesting period. Adults will readily desert their nests if disturbed during incubation or brooding. Their burrows are often near the surface of the ground and are easily collapsed.

Like all alcids, Rhinoceros Auklets are extremely vulnerable to oil spills. During the breeding season, they concentrate at two sites: Castle Rock and the Farallon Islands. Oil slicks or other pollution in the vicinity of these colonies could affect a large portion of California's breeding population. During winter, California waters support large numbers of Rhinoceros Auklets, many from colonies further north (Briggs 1980).

The available data indicate an increasing population of Rhinoceros Auklets in California. Significant increases in numbers have been observed at the two largest colonies in the state, Castle Rock and the Farallon Islands, and Rhinoceros Auklets have been found breeding or are suspected to breed at six additional sites. These recent increases and the discovery of new nesting sites in Oregon (Scott et al. 1974, Varoujean and Pitman, 1979) and British Columbia (Hatler et al. 1978) indicate that this population increase may be widespread along the west coast of North America.

Tufted Puffin (*Lunda cirrhata*)



Tufted Puffins are among the most abundant and conspicuous of the seabirds in the North Pacific, although they are the least common alcid nesting in California. The species' center of abundance appears to be the western Gulf of Alaska and the Aleutian Islands (Sowls et al. 1978). These colorful, comical seabirds can often be seen standing in front of their nesting burrows, especially in early morning.


Tufted Puffins usually nest in earth burrows at the edges of cliffs or on the grassy slopes of islands. Tufted Puffins in California also use burrows or small caves found in loose sandstone or unconsolidated conglomerate rock. In California, extensive areas of ideal nesting habitat exist on only a few islands, so many colonies are small and undoubtedly will remain so. Except on the Farallon Islands, lack of adequate nesting habitat may ultimately be one of the major factors limiting expansion of the Tufted Puffin population in California.

Tufted Puffins can sometimes be observed carrying fish in their bills to their chicks at colonies. Preferred foods include small fish, cephalopods, and crustaceans (Hatch et al. 1979). Although Tufted Puffins are diurnal, fledglings apparently leave their burrows and go to sea only under cover of darkness. In fall, adult puffins lose their brightly colored bill sheathes. Both fledglings and adults head far to sea and during winters are only occasionally seen near land.

CALIFORNIA COLONIES

Tufted Puffins are found from Prince Island (325 003) in northern California south to Hurricane Point Rocks (454 011) at the northern tip of the Big Sur coast. We list 14 sites at which Tufted Puffins have been recorded but breeding has been recently documented at only five of these: Prince Island, Castle Rock (325 006), Green Rock (325 020), Puffin Rock (325 021), and the Farallon Islands (429 012). With the exception of Little River Rock (325 035), Tufted Puffins have been observed near burrows at the remaining sites. Although Harris (1974) listed Tufted Puffins as possible breeders on Little River Rock, where the habitat appears suitable for this species, we did not observe birds there. Tufted Puffins were regularly observed at Piedras Blancas Rock (477 007) in 1979 (Rauzon pers. comm.), but not in 1980 (Ron Jameson pers. comm.).

The largest Tufted Puffin colonies in California are on Castle Rock and the Farallon Islands. Each contains about 100 birds (Ainley pers. comm. this study). All remaining locations contain ten or fewer birds. Most Tufted Puffin colonies in California have been identified, but a few undocumented pairs may be present at scattered locations, primarily in northern California.



HISTORICAL STATUS AND VULNERABILITY

Since the early 1900's, the Tufted Puffin's range in California has contracted northward and its population has declined in size. Tufted Puffins were formerly found breeding in the northern Channel Islands (Willett 1910), but they no longer do so (Hunt et al. 1979). The southernmost suspected breeding location today is Hurricane Point Rocks (454 011) in central California.

The Farallon Island population of Tufted Puffins was once much larger than it is today. The several thousand birds present in the early 1900's decreased in number to a low of 26 in 1959 (Ainley and Lewis 1974). Ainley and Lewis (1974) state that oil pollution was the major cause of this decline and suggest that the crash of the Pacific Sardine population has been the major factor keeping this population depressed.

Elsewhere in California, little information on the historical status of this species is available. Tufted Puffins once nested on Blank Rock (325 024) during the earlier part of this century (Clay unpubl. field notes), but they have since disappeared from this island, probably because of soil erosion. Clay also reported Tufted Puffins on Flatiron Rock (325 023) as "numerous" in 1911, but since then their nesting habitat has apparently deteriorated greatly. Osborne (1972) found only

two Tufted Puffins breeding on Flatiron Rock in 1970 and we list only two on this site during the 1979 and 1980 breeding seasons. Tufted Puffins in California are concentrated around two major breeding colonies: Castle Rock and South Farallon Island. Floating oil near either of these islands or repeated human disturbance could be disastrous to the population. Fortunately, both islands are protected, the former as a Nature Conservancy Preserve and the latter as a National Wildlife Refuge. Anyone attempting to land on either island must obtain prior permission. The remaining islands are not officially protected, but because of their rugged topography and inaccessibility they have so far received little attention from man.



The first graph illustrates the initial phase of the study, showing a steady increase in the measured variable over the first half of the period. This is followed by a sharp decline, reaching a minimum point before a final recovery. The second graph, in contrast, shows a more consistent upward trend throughout the entire duration, with a slight plateau or change in slope near the end of the data series.

The second graph provides a detailed view of the later stages of the experiment. It highlights the significant increase in the variable's value during the final quarter, which may be attributed to specific experimental conditions or interventions. The overall data suggests a cumulative effect over time, with the final values being notably higher than those in the earlier stages.

Catalog of California

Seabird Colonies

**MAPS &
TABLES:**



How to Use Maps And Tables


A few minutes taken to carefully read this section should make your use of these maps and tables much easier. Each Colony in this report is included on one of 11 U.S. Geological Survey maps which cover the California coast. An index to these maps appears on the facing page. They are numbered under a U.S. Fish and Wildlife Service system covering the entire United States. The first three digits of the six-digit catalog number for each colony is the map number. All data in the following maps and tables are organized into eleven sections corresponding to these maps.

Once you have determined which of these eleven maps covers your area of interest, turn to that section. Heading each section is a map of that area showing the locations of all colonies within that area. The numbers that appear here (001, 002, 003, and so on) are the colony identifiers, each specific for a colony area within that map. These are the last three digits of the six-digit catalog number. Note that these numbers are not sequential along the coast. Many new


colonies have been identified since catalog numbers were initially assigned by Varoujean, (1979). We have retained these initial numbers and added new colony numbers as necessary.

A sample colony listing is given below. Note that the populations are given in number of breeding birds and not pairs. The reference (1, 2, etc.) at the end of each data line corresponds to the proper citation, page 341, from which we obtained the information. If further detail is needed about a site, these sources should be consulted. For information on the archiving of our U.S. Fish and Wildlife Service field notes and photographs see appendix A, page 351.

Since there are many landforms with similar or identical names along the coast, such as "Bird Rocks", "White Rocks", or "Castle Rocks", the catalog number is important in distinguishing sites. Therefore we list it after mentioning a site in the text. If you know the name but not the catalog number of a site you are interested in, check appendix C. It lists all colony areas alphabetically and their catalog numbers.




MAP INDEX:



Dots keyed to map sections.

- 25 ●
- 379 ●
- 404 ●
- 429 ●
- 454 ●
- 477 ●
- 501 ●
- 502 ●
- 524 ●
- 525 ●
- 545 ●



325

Eureka


The maps on the facing page and following page are indexes to the locations of colonies within map 325, Eureka. Note that all colonies on the map are not numbered consecutively from north to south, since many previously unreported colonies have been added since initial colony numbers were assigned by Varoujean (1979). On the pages following these two maps, all colonies are listed sequentially and a detailed map of each is provided.

Numbers of breeding seabirds will vary from year to year. Below are the approximate numbers of breeding seabirds within this region.

| | |
|-----------------------------------|-------------|
| Fork-tailed Storm-Petrel. | 350 |
| Leach's Storm-Petrel. | 17,000 |
| Brandt's Cormorant. | 7,000 |
| Double-crested Cormorant. | 1,000* |
| Pelagic Cormorant | 3,000 |
| Black Oystercatcher | 100 |
| Western Gull. | 3,500 |
| Common Murre. | 250,000 |
| Pigeon Guillemot. | 2,500 |
| Marbled Murrelet. | no estimate |
| Cassin's Auklet | 3,600 |
| Rhinoceros Auklet | 250 |
| Tufted Puffin | 150 |


* coastal population only.


325 (North) Eureka





325 (South) Eureka






(001) Cone Rock 41°58'21"N, 124°13'02"W

| | | | |
|-------------------|-------|---|----|
| Pelagic Cormorant | 0 | (DeGange, Lester & Sowls, 7/2/80, B, I) | 42 |
| Western Gull | 10 | (DeGange, Lester & Sowls, 7/2/80, B, III) | 42 |
| Pigeon Guillemot | 8 | (DeGange, Lester & Sowls, 7/2/80, B, III) | 42 |
| Total | 18 | | |
| Pelagic Cormorant | 12-20 | (Osborne, 7/16/69, A) | 35 |
| Pelagic Cormorant | 14 | (Lester & Rodstrom, 6/3/79, B, III) | 42 |
| Western Gull | 16 | (Osborne, 7/16/69, A) | 35 |

(002) Hunter Rocks 41°57'22"N, 124°12'41"W

| | | | |
|---------------------|-----|---|----|
| Brandt's Cormorant | 680 | (DeGange & Nelson, 7/25/80, A, II) | 42 |
| Pelagic Cormorant | 122 | (DeGange, Lester & Sowls, 7/2/80, B, II) | 42 |
| Black Oystercatcher | 2 | (DeGange, Lester & Sowls, 7/2/80, B, III) | 42 |
| Western Gull | 38 | (DeGange, Lester & Sowls, 7/2/80, B, III) | 42 |
| Pigeon Guillemot | 120 | (DeGange, Lester & Sowls, 7/2/80, B, III) | 42 |
| Total | 962 | | |
| Brandt's Cormorant | 320 | (Osborne, 7/24/69, L) | 35 |
| Brandt's Cormorant | 584 | (Lester, 7/12/79, A, II) | 42 |
| Pelagic Cormorant | 50 | (Osborne, 7/24/69, L) | 35 |
| Pelagic Cormorant | 60 | (Osborne, 1970) | 35 |
| Pelagic Cormorant | 30 | (Lester & Rodstrom, 6/4/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Osborne, 6/24/69) | 35 |
| Western Gull | 30 | (Osborne, 7/24/69, L) | 35 |
| Western Gull | 20 | (Lester & Rodstrom, 6/4/79, B, III) | 42 |
| Pigeon Guillemot | 2 | (Osborne, 7/24/69, L) | 35 |



Cone Rock

Photo by Art Sows


003 Prince Island 41°57'04"N, 124°12'41"W

| | | | |
|--------------------------|--------------|---|----|
| Leach's Storm-Petrel | P | (DeGange, Lester & Sows, 7/3/80, L) | 42 |
| Brandt's Cormorant | 0 | (DeGange, Lester & Sows, 7/2/80, BL, II) | 42 |
| Double-crested Cormorant | 450 | (DeGange, Lester & Sows, 7/2/80, BL, II) | 42 |
| Pelagic Cormorant | 146 | (DeGange, Lester & Sows, 7/2/80, B, II) | 42 |
| Black Oystercatcher | 6 | (DeGange, Lester & Sows, 5/21/80, L, III) | 42 |
| Western Gull | 420 | (DeGange, Lester & Sows, 5/21/80, L, II) | 42 |
| Pigeon Guillemot | 450 | (DeGange, Lester & Sows, 5/21/80, L, III) | 42 |
| Rhinoceros Auklet | 12 | (DeGange, Lester & Sows, 7/3/80, L, III) | 42 |
| Tufted Puffin | 8 | (DeGange, Lester & Sows, 7/3/80, L, III) | 42 |
| Total | 1,492 | | |
| Brandt's Cormorant | 0 | (Osborne, 1969) | 35 |
| Brandt's Cormorant | 34 | (Osborne, 6/17/70, L) | 35 |
| Double-crested Cormorant | 180 | (Osborne, 6/17/70, L) | 35 |
| Double-crested Cormorant | 406 | (Lester & Rodstrom, 6/3/79, L, I) | 42 |
| Pelagic Cormorant | 80 | (Osborne, 6/17/70, L) | 35 |
| Pelagic Cormorant | 40 | (Lester & Rodstrom, 6/3/79, L, II) | 42 |
| Black Oystercatcher | 2 | (Osborne, 6/17/70, L) | 35 |
| Black Oystercatcher | 5 | (Lester & Rodstrom, 6/3/79, L, III) | 42 |
| Western Gull | 100 | (Osborne, 6/17/70, L) | 35 |
| Western Gull | 294 | (Lester & Rodstrom, 6/3/79, L, II) | 42 |
| Pigeon Guillemot | 28 | (Osborne, 6/17/70, L) | 35 |

P = probably present

004 Smith River was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).

005 Lake Talawa Beach was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).



Prince Island

Photo by Art Sows

006 Castle Rock 41°45'37"N, 124°15'W

Castle Rock is the second most important seabird colony in California. It presently has the largest breeding populations of Common Murres and Rhinoceros Auklets in California as well as important populations of Fork-tailed and Leach's Storm-Petrels, and Tufted Puffins. It is a major hauling area for California sea lions (*Zalophus californianus*) and Stellers sea lions (*Eumetopias jubata*) and is a pupping grounds for Harbor seals (*Phoca vitulina*). Elephant Seals (*Mirounga angustirostris*) are often present in low numbers.

Castle Rock is the primary spring staging grounds for the endangered Aleutian Canada Goose (*Branta canadensis leucopareia*). The island serves as a safe night roost for the geese as most feeding occurs in nearby fields.

Until 1979, Castle Rock was privately owned and in the 1920's sheep grazed its slopes. Speculators have contemplated guano mining, rock quarrying, and construction of a tourist attraction on the island. Fortunately, in 1979, the Nature Conservancy purchased Castle Rock and it will soon be protected as a refuge by the U.S. Fish and Wildlife Service. See Appendix B.


| | | | |
|--------------------------|---------|--|----|
| Fork-tailed Storm-Petrel | 100 | (Osborne, 1970, L) | 35 |
| Leach's Storm-Petrel | 5,000 | (Osborne, 1970, L) | 35 |
| Brandt's Cormorant | 2,200 | (DeGange & Nelson, 7/25/80, A, II) | 42 |
| Pelagic Cormorant | 340 | (Lester, Nakagawa & Vasey, 6/19/80, B, III) | 42 |
| Black Oystercatcher | 6 | (Lester, Nakagawa & Vasey, 6/19/80, B, III) | 42 |
| Western Gull | 1,350 | (Lester & Rodstrom, 7/12/79, A, & 7/19/79, A, III) | 42 |
| Common Murre | 126,000 | △ (Lester & Rodstrom, 7/12/79, A, & 7/19/79, A, III) | 42 |
| Pigeon Guillemot | 800 | (Lester, Nakagawa & Vasey, 6/19/80, B, III) | 42 |
| Cassin's Auklet | 3,600 | (Osborne, 1970, L) | 35 |
| Rhinoceros Auklet | 200+ | (Osborne, 1977, L) | 34 |
| Tufted Puffin | 100 | (Lester, 1980, BL, III) | 42 |
| Total | 139,596 | | |

| | | | |
|---------------------|---------|---|----|
| Brandt's Cormorant | 1,758 | (Osborne, 1970, L) | 35 |
| Brandt's Cormorant | 2,010 | (Lester & Rodstrom, 7/12/79, A & 7/19/79, A, III) | 42 |
| Pelagic Cormorant | 100 | (Osborne, 1970, L) | 35 |
| Pelagic Cormorant | 96 | (Lester & Rodstrom, 5/21/79, B, III) | 42 |
| Black Oystercatcher | 2 | (Osborne, 1970, L) | 35 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 5/21/79, B, III) | 42 |
| Western Gull | 1,200 | (Osborne, 1970, L) | 35 |
| Common Murre | 80,000 | (Osborne, 1970, L) | 35 |
| Cassin's Auklet | 100 | (Thoresen, 4/16 & 8/25/59, L) | 41 |
| Rhinoceros Auklet | X | (Clay, 1917, L) | 35 |
| Cassin's Auklet | X | (Clay, 5/20/34, L) | 35 |
| Rhinoceros Auklet | 100-150 | (Osborne, 1970, L) | 35 |
| Tufted Puffin | 50 | (Osborne, 1970, L) | 35 |

△ Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/2/80 aerial survey (also times 1.67) is 131,600

007 "Tolowa Rocks" 41°45'15"N, 124°14'W

| | | | |
|--------------------------|-----|---|----|
| Fork-tailed Storm-Petrel | 60 | (Lester, 6/20/80, L, III) | 42 |
| Leach's Storm-Petrel | ? | (Lester, 6/20/80, L) | 42 |
| Pelagic Cormorant | 92 | (Lester, 6/19 & 6/20/80, B, II) | 42 |
| Black Oystercatcher | 8 | (Lester, 6/19 & 6/20/80, BL, II) | 42 |
| Western Gull | 116 | (Lester, 6/19 & 6/20/80, BL, II) | 42 |
| Pigeon Guillemot | 40 | (Lester, 6/19 & 6/20/80, BL, III) | 42 |
| Total | 316 | | |
| Pelagic Cormorant | 24 | (Osborne, 9/14/70, M, census of one rock) | 35 |
| Pelagic Cormorant | 36 | (Lester & Rodstrom, 5/21/79, B, I) | 42 |
| Western Gull | 24 | (Lester & Rodstrom, 5/21/79, B, II) | 42 |



Castle Rock



Photo by Gary Lester

008 White Rock 41°44'46"N, 124°13'44"W

| | | | |
|---------------------|-----------|--------------------------------------|----|
| Black Oystercatcher | 2 | (Lester & Berner, 6/20/80, L, I) | 42 |
| Western Gull | 74 | (Lester & Berner, 6/20/80; L, II) | 42 |
| Pigeon Guillemot | 10 | (Lester & Rodstrom, 5/21/79, B, III) | 42 |
| Total | <u>86</u> | | |
| Black Oystercatcher | 2 | (Osborne, 7/17/69, L) | 35 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 5/21/79, B, III) | 42 |
| Western Gull | 40 | (Osborne, 7/17/69, L) | 35 |
| Western Gull | 24 | (Lester & Rodstrom, 5/21/79, B, II) | 42 |

009 Sister Rocks 41°39'29"N, 124°08'47"W

| | | | |
|---------------------|------------|-------------------------------------|----|
| Brandt's Cormorant | 42 | (DeGange & Nelson, 7/25/80, A, II) | 42 |
| Pelagic Cormorant | 22 | (Berner & Lester, 6/20/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Western Gull | 40 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Common Murre | 50 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Pigeon Guillemot | 40 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Total | <u>196</u> | | |
| Brandt's Cormorant | 100 | (Osborne, 7/69, M) | 35 |
| Brandt's Cormorant | 8 | (DeGange & Lester, 5/22/79, B, II) | 42 |
| Pelagic Cormorant | 20 | (Osborne, 7/69, M) | 35 |
| Pelagic Cormorant | 14 | (DeGange & Lester, 5/22/79, B, II) | 42 |
| Black Oystercatcher | 2 | (DeGange & Lester, 5/22/79, B, III) | 42 |
| Western Gull | 4 | (DeGange & Lester, 5/22/79, B, II) | 42 |
| Pigeon Guillemot | 40 | (DeGange & Lester, 5/22/79, B, III) | 42 |



(010) False Klamath Rock 41°35'40"N, 124°06'36"W

| | | | |
|--------------------------|--------|---|----|
| Brandt's Cormorant | 356 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Double-crested Cormorant | 84 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Pelagic Cormorant | 110 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Western Gull | 80 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Common Murre | 26,500 | △ (Lester, 6/19&7/12/79, A, III) | 42 |
| Pigeon Guillemot | 160 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Total | 27,290 | | |
| Brandt's Cormorant | 370 | (Osborne, 7/1/70, M) | 35 |
| Brandt's Cormorant | 486 | (Lester & Rodstrom, 6/19&7/12/79, A, III) | 42 |
| Double-crested Cormorant | 12 | (Osborne, 1970, M) | 35 |
| Double-crested Cormorant | 2 | (DeGange & Lester, 5/22/79, B, III) | 42 |
| Pelagic Cormorant | 18 | (Osborne, 1970, M) | 35 |
| Pelagic Cormorant | 44 | (DeGange & Lester, 5/22/79, B, III) | 42 |
| Western Gull | 50 | (Osborne, 1970, M) | 35 |
| Western Gull | 80 | (DeGange & Lester, 5/22/79, B, III) | 42 |
| Common Murre | 20,000 | (Osborne, 1970, M) | 35 |
| Pigeon Guillemot | X | (Osborne, 1970, M) | 35 |

△ Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/2/80 aerial survey (also times 1.67) is 37,600.



(011) Flint Rock Head 41°31'31"N, 124°05'00"W

| | | | |
|-------------------|---|----------------------|----|
| Pelagic Cormorant | 4 | (Osborne, 8/6/69, M) | 35 |
|-------------------|---|----------------------|----|

(012) White Rock 41°30'56"N, 124°05'06"W

White Rock is one of the most important Brown Pelican roosts in northern California, with up to 1,000 birds present from August through October.

| | | | |
|--------------------------|-----|-------------------------------------|----|
| Brandt's Cormorant | 240 | (DeGange & Nelson, 7/25/80, A, II) | 42 |
| Double-crested Cormorant | 60 | (Lester, 6/2/80, M, III) | 42 |
| Pelagic Cormorant | 12 | (Lester & Rodstrom, 6/5/79, B, I) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/5/79, B, II) | 42 |
| Western Gull | 24 | (Lester & Rodstrom, 6/5/79, B, III) | 42 |
| Pigeon Guillemot | 6 | (Lester & Rodstrom, 6/5/79, B, III) | 42 |
| Total | 344 | | |
| Brandt's Cormorant | 200 | (Osborne, 1970) | 35 |
| Brandt's Cormorant | 514 | (Lester, 6/19&7/12/79, A, II) | 42 |



013 Redding Rock 41°20'29"N, 124°10'26"W

| | | | |
|--------------------|-------|---------------------------------------|----|
| Brandt's Cormorant | 158 | (DeGange, 7/9/80, A, II) | 42 |
| Western Gull | 20 | (Berner & Lester, 6/30/80, B, III) | 42 |
| Common Murre | 2,100 | △ (DeGange, 7/9/80, A, III) | 42 |
| Pigeon Guillemot | 8 | (Berner & Lester, 6/30/80, B, III) | 42 |
| Total | 2,286 | | |
| Brandt's Cormorant | 80 | (Osborne, 5/12/70, A) | 35 |
| Brandt's Cormorant | 158 | (Lester & Sows, 5/15&7/12/79, A, III) | 42 |
| Pelagic Cormorant | X | (Osborne, 5/12/70, A) | 35 |
| Western Gull | X | (Osborne, 5/12/70, A) | 35 |
| Western Gull | 40 | (Lester & Sows, 5/15&7/12/79, A, III) | 42 |
| Common Murre | 600 | (Osborne, 5/12/70, A) | 35 |



Redding Rock

Photo by Anthony DeGange

△ Estimate is number of birds present times 1.67, see page .10. Briggs et al.'s estimate for 7/2/80 aerial survey (also times 1.67) is 1,700

014

Big Lagoon was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).

P
A
C
I
F
I
C

013



Redding Rock
Lighthouse (Aband.)

+ 41° 20'
124° 10'

41° 20'
124° 05'

Section from U.S.G.S.
1:62,500 scale map:

Orick, Calif.



(015) "Cormorant Rock" 41°08'32"N, 124°09'39"W

| | | | |
|---------------------|-----------|-------------------------------------|----|
| Pelagic Cormorant | 14 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Black Oystercatcher | 2 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Western Gull | 2 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Total | <u>18</u> | | |
| Pelagic Cormorant | 4 | (Osborne, 1970, M) | 35 |


(016) Wedding Rock 41°08'28"N, 124°09'32"W

| | | | |
|------------------|----|----------------------------|----|
| Pigeon Guillemot | 60 | (DeGange, 5/15/79, M, III) | 42 |
| Pigeon Guillemot | 44 | (Osborne, 1969-70, M) | 35 |

(017) "Sea Gull Rock" 41°05'21"N, 124°09'07"W

| | | | |
|--------------------------|------------|--|----|
| Double-crested Cormorant | 136 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Pelagic Cormorant | 106 | (Lester & Stewart, 6/23/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Western Gull | 40 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Pigeon Guillemot | 12 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Total | <u>306</u> | | |
| Double-crested Cormorant | 48 | (Benz & Garret, 1978, M) | 43 |
| Double-crested Cormorant | 96 | (Lester & Rodstrom, 5/9/79, M, III) | 42 |
| Pelagic Cormorant | 40 | (Benz & Garret, 1978, M) | 43 |
| Pelagic Cormorant | 62 | (Lester, McKay & Rodstrom, 8/1/79, B, I) | 42 |
| Black Oystercatcher | 2 | (Lester, McKay & Rodstrom, 8/1/79, B, I) | 42 |
| Western Gull | 20 | (Benz & Garrett, 1978, M) | 43 |
| Western Gull | 40 | (Lester, McKay & Rodstrom, 8/1/79, B, I) | 42 |
| Pigeon Guillemot | 4 | (Benz & Garrett, 1978, M) | 43 |
| Western Gull | 20 | (Osborne, 6/1/69) | 35 |
| Pigeon Guillemot | X | (Osborne, 6/1/69) | 35 |

X = present



018 "Sea Lion Rock" 41°05'40"N, 124°09'49"W


| | | | |
|--------------------------|-----|--|----|
| Pelagic Cormorant | 36 | (Lester & Stewart, 6/23/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Western Gull | 28 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Pigeon Guillemot | 20 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Total | 106 | | |
| Double-crested Cormorant | 16 | (Osborne, 6/18/70, L) | 35 |
| Pelagic Cormorant | 34 | (Osborne, 6/18/70, L) | 35 |
| Pelagic Cormorant | 16 | (Lester, McKay & Rodstrom, 8/1/79, B, I) | 42 |
| Western Gull | 24 | (Osborne, 6/18/70, L) | 35 |
| Western Gull | 26 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |

019 White Rock 41°05'13"N, 124°09'33"W

| | | | |
|--------------------------|----------------|--|---|
| Pelagic Cormorant | 70 | (Lester, McKay & Rodstrom, 8/1/79, B, II) | 4 |
| Western Gull | 20 | (Lester, McKay & Rodstrom, 8/1/79, B, II) | 4 |
| Common Murre | 2,600 Δ | (Lester, Rodstrom & Sows, 5/15/79, A, & 6/19/79, A, III) | 4 |
| Pigeon Guillemot | 24 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 4 |
| Tufted Puffin | P | (Osborne, 6/18/70, M) | 3 |
| Total | 2,714 | | |
| Double-crested Cormorant | 24 | (Osborne, 1970, M) | 3 |
| Pelagic Cormorant | 62 | (Osborne, 1970, M) | 3 |
| Western Gull | 10-20 | (Osborne, 6/18/70, M) | 3 |
| Common Murre | 1,200 | (Osborne, 6/18/70, M) | 3 |

P = probably present

Δ Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/2/80 aerial survey (also times 1.67) is 3,300.



020 Green Rock 41°04'32"N, 124°09'48"W

| | | | |
|--------------------------|-----------|--|----|
| Fork-tailed Storm-Petrel | 50 | (Osborne, 6/18/70, L) | 35 |
| Leach's Storm-Petrel | X | (Osborne, 6/18/70, L) | 35 |
| Brandt's Cormorant | 216 | (DeGange, 7/9/80, A, II) | 42 |
| Pelagic Cormorant | 48 | (Lester & Stewart, 6/23/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Osborne, 1969-70, L) | 35 |
| Western Gull | 40 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Common Murre | 55,000 | △ (DeGange, 7/9/80, A, III) | 42 |
| Pigeon Guillemot | 28 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Cassin's Auklet | 50 | (Osborne, 6/18/70, L) | 35 |
| Rhinoceros Auklets | 6 | (DeGange, Lester & Sows, 1980, M, III) | 42 |
| Tufted Puffin | 10 | (Osborne, 6/18/70, L) | 35 |
| Total | 55,420 | | |
| Fork-tailed Storm-Petrel | X | (Talmadge, 1930's, L) | 35 |
| Leach's Storm-Petrel | X | (Talmadge, 1930's, L) | 35 |
| Brandt's Cormorant | X | (Talmadge, 1930's, L) | 35 |
| Brandt's Cormorant | 202 | (Osborne, 6/28/69, L) | 35 |
| Brandt's Cormorant | 76 | (Osborne, 6/70, L) | 35 |
| Brandt's Cormorant | 440 | (Lester, 6/19/79, A, III) | 42 |
| Pelagic Cormorant | X | (Talmadge, 1930's, L) | 35 |
| Pelagic Cormorant | 4 | (Osborne, 1969-70, L) | 35 |
| Pelagic Cormorant | 52 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Western Gull | 44 | (Osborne, 6/18/70, L) | 35 |
| Common Murre | X | (Talmadge, 1930's, L) | 35 |
| Common Murre | 2,000 | (Clay, 5/10/41, L) | 35 |
| Common Murre | 40-48,000 | (Osborne, 6/18/70, L) | 35 |
| Pigeon Guillemot | X | (Talmadge, 1930's, L) | 35 |
| Pigeon Guillemot | 6 | (Osborne, 6/18/70, L) | 35 |
| Tufted Puffin | X | (Talmadge, 1930's, L) | 35 |


△ Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/2/80 aerial survey (also times 1.67) is 28,300.

021 "Puffin Rock" 41°04'18"N, 124°09'32"W

| | | | |
|---------------------|----|--|----|
| Pelagic Cormorant | 8 | (Lester & Stewart, 6/23/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Stewart, 6/23/80, BL, III) | 42 |
| Western Gull | 44 | (Lester & Stewart, 6/23/80, BL, II) | 42 |
| Pigeon Guillemot | 10 | (Lester & Stewart, 6/23/80, BL, III) | 42 |
| Tufted Puffin | 6 | (DeGange, Lester & Sows, 1980, M, II) | 42 |
| Total | 70 | | |
| Pelagic Cormorant | 8 | (Osborne, 1970, M) | 35 |
| Pelagic Cormorant | 14 | (Lester, McKay & Rodstrom, 8/1/79, B, II) | 42 |
| Western Gull | 40 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Black Oystercatcher | 2 | (Osborne, 1969-70, M) | 35 |
| Pigeon Guillemot | 12 | (Osborne, 1970, M) | 35 |
| Tufted Puffin | 6 | (Osborne, 1970, M) | 35 |

022 "Little Pewetole Rock" 41°04'N, 124°09'W

| | | | |
|---------------------|---|---|----|
| Pelagic Cormorant | 4 | (Osborne, 1970, M) | 35 |
| Black Oystercatcher | 2 | (Lester, Nelson & Reetz, 7/20/79, B, I) | 42 |
| Total | 6 | | |



Green Rock

Photo by Anthony DeGange

023 Flatiron Rock 41°03'34"N, 124°09'39"W


| | | | |
|----------------------|------------|---|--|
| Brandt's Cormorant | 1,540 | (DeGange, 7/9/80, A, III) | |
| Pelagic Cormorant | 4 | (Lester & Rodstrom, 5/9/79, M) | |
| Black Oystercatcher | 2 | (Osborne, 1969-70, LM) | |
| Western Gull | 40 | (Osborne, 1969-70, LM) | |
| Common Murre | 24,000 | △ (Lester & Rodstrom, 5/15, 6/19 & 7/12/79, A, III) | |
| Pigeon Guillemot | 2 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | |
| Tufted Puffin | 2 | (Lester & DeGange, 1980, M, II) | |
| Total | 24,590 | | |
| Leach's Storm-Petrel | X | (Clay, 5/22/10, 6/10/34, L) | |
| Brandt's Cormorant | 2,400 | (Clay, 6/10/34) | |
| Brandt's Cormorant | 260 | (Osborne, 1969) | |
| Brandt's Cormorant | 400 | (Osborne, 6/18/70) | |
| Brandt's Cormorant | 1,206 | (Lester, Rodstrom & Sows, 5/15, 6/19 & 7/12/79, A, III) | |
| Common Murre | ? | (Clay, 1910-1912 & 1934) | |
| Common Murre | 10,000 | (Osborne, 1970, LM) | |
| Pigeon Guillemot | X | (Clay, 5/22/10) | |
| Pigeon Guillemot | 2 | (Osborne, 6/18/70) | |
| Cassin's Auklet | X | (Clay, 1910-11, 1934, L) | |
| Tufted Puffin | "numerous" | (Clay, 7/11/11, L) | |
| Tufted Puffin | "sparse" | (Clay, 6/10/34, L) | |
| Tufted Puffin | 4-6 | (Hallmark, early 1950's) | |
| Tufted Puffin | 2 | (Osborne, 6/3/70) | |
| Tufted Puffin | 2 | (Lester, McWay & Rodstrom, 8/1/79, B, III) | |

△ Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/2/80 aerial survey (also times 1.67) is 17,700.

024 Blank Rock 41°03'15"N, 124°09'26"W

| | | | |
|--------------------------|-------|---|----|
| Brandt's Cormorant | 52 | (DeGange, 7/9/80, A, I) | 42 |
| Pelagic Cormorant | 0 | (Lester & Stewart, 6/23/80, B, I) | 42 |
| Black Oystercatcher | 2 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Western Gull | 80 | (Lester & Stewart, 6/22/80, M, III) | 42 |
| Common Murre | 1,000 | △ (DeGange, 7/9/80, A, III) | 42 |
| Pigeon Guillemot | 20 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Total | 1,154 | | 35 |
| Fork-tailed Storm-Petrel | X | (Dawson & Clay, 6/18/16, L) | 35 |
| Fork-tailed Storm-Petrel | 0 | (Osborne, 1965, 1969, 1970, L) | 35 |
| Leach's Storm-Petrel | X | (Dawson & Clay, 6/18/16, L) | 35 |
| Leach's Storm-Petrel | 0 | (Osborne, 1965, 1969, 1970, L) | 35 |
| Brandt's Cormorant | 0 | (Osborne, 1969) | 42 |
| Brandt's Cormorant | 280 | (Lester & Rodstrom, 5/15, 6/19 & 7/12/79, A, III) | 42 |
| Pelagic Cormorant | 6 | (Lester, Nelson & Reetz, 7/20/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester, Nelson & Reetz, 7/20/79, B, III) | 35 |
| Western Gull | X | (Dawson & Clay, 6/18/16, L) | 35 |
| Western Gull | 90 | (Osborne, 6/18/70, L) | 42 |
| Western Gull | 100 | (Lester, Nelson & Reetz, 7/20/79, B, III) | 42 |
| Pigeon Guillemot | 20 | (Lester, Nelson & Reetz, 7/20/79, B, III) | 35 |
| Tufted Puffin | X | (Dawson & Clay, 6/18/16, L) | |

△ Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/2/80 aerial survey (also times 1.67) is 400



Flatiron Rock

Photo by Art Sowls

025 Trinidad Head 41°03'09"N, 124°08'58"W

| | | | |
|-------------------|------------|---|----|
| Pelagic Cormorant | 202 | (Lester & Stewart, 6/23/80, B, II) | 42 |
| Pigeon Guillemot | 60 | (Lester, Nelson & Reetz, 7/20/79, B, III) | 42 |
| Total | <u>262</u> | | |
| Pelagic Cormorant | 198 | (Osborne, 1970, L) | 35 |
| Pelagic Cormorant | 94 | (Lester, Nelson & Reetz, 7/20/79, B, III) | 42 |
| Pigeon Guillemot | 40 | (Osborne, 1970, L) | 35 |

026 Pilot Rock 41°03'06"N, 124°09'09"W


| | | | |
|---------------------|--------------------|---|----|
| Brandt's Cormorant | 0 | (DeGange, 7/9/80, A; Lester & Stewart, 6/23/80, B, I) | 42 |
| Pelagic Cormorant | 8 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Black Oystercatcher | 2 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Western Gull | 40 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Common Murre | 2,500 ^Δ | (DeGange, 7/9/80, A, III) | 42 |
| Pigeon Guillemot | 20 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Total | <u>2,570</u> | | |
| Brandt's Cormorant | 160 | (Osborne, 1969, L) | 35 |
| Brandt's Cormorant | 40 | (Lester, 6/19/79, A, III) | 42 |
| Pelagic Cormorant | 24 | (Osborne, 1969, L) | 35 |
| Pelagic Cormorant | 8 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Western Gull | 20 | (Osborne, 1969, L) | 35 |
| Western Gull | 14 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Common Murre | X | (Osborne, 1969) | 35 |
| Pigeon Guillemot | 2 | (Osborne, 1969, L) | 35 |

^Δ Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/2/80 aerial survey (also times 1.67) is 1,500.

027 Prisoner Rock 41°03'07"N, 124°08'34"W


| | | | |
|--------------------------|------------|---|----|
| Fork-tailed Storm-Petrel | X | (Osborne, 1970-72, L) | 35 |
| Leach's Storm-Petrel | 160 | (Lester, Nelson & Reetz, 7/20/79, L, III) | 42 |
| Western Gull | 2 | (Lester, Nelson & Reetz, 7/20/79, L, III) | 42 |
| Pigeon Guillemot | 4 | (Lester, Nelson & Reetz, 7/20/79, L, III) | 42 |
| Total | <u>166</u> | | |
| Leach's Storm-Petrel | X | (Clay, 6/5/10&6/24/12, L) | 35 |
| Leach's Storm-Petrel | 150-200 | (Osborne, 1970-72, L) | 35 |
| Pelagic Cormorant | 4 | (Osborne, 1970-72, L) | 35 |

X = present,



Section from U.S.G.S.
1:24,000 scale map:


Trinidad & Crannel,
Calif.



- 028 "Unnamed Rock" - see 054
- 029 "Mr'rp Rock" - see 054
- 030 Cap Rock - see 054
- 031 "Luffenholtz Rocks" - see 054
- 032 "Tepona Rock" - see 054
- 033 "Halfmoon Rock" - see 054
- 034 "Snag Rock" - see 054
- 035 Little River Rock 41°02'08"N, 124°07'16"W

| | | | |
|--------------------------|--------|--|----|
| Fork-tailed Storm-Petrel | 200 | (Harris, 1965-72, L) | 24 |
| Leach's Storm-Petrel | 10,000 | (Harris, 1965-72, L) | 24 |
| Double-crested Cormorant | 100 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Pelagic Cormorant | 12 | (Lester & Stewart, 6/23/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Western Gull | 60 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Pigeon Guillemot | 60 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Rhinoceros Auklet | P | (Harris, 1965-72, L) | 24 |
| Tufted Puffin | P | (Harris, 1965-72, L) | 24 |
| Total | 10,434 | | |
| Double-crested Cormorant | 4 | (Harris, 8/8/74, L) | 23 |
| Double-crested Cormorant | 78 | (Harris, 6/1/77, L) | 23 |
| Double-crested Cormorant | 120 | (Lester, McKay & Rodstrom, 8/1/79, B, IV) | 42 |
| Pelagic Cormorant | 10-20 | (Harris, 1965-72, L) | 24 |
| Pelagic Cormorant | 8 | (Lester, McKay & Rodstrom, 8/1/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Harris, 1965-72, L) | 24 |
| Western Gull | 50-60 | (Harris, 1965-72, L) | 24 |
| Western Gull | 62 | (Harris, 6/8/74, L) | 23 |
| Western Gull | 84 | (Harris, 6/1/77, L) | 23 |
| Western Gull | 60 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Pigeon Guillemot | 30-40 | (Harris, 1965-72, L) | 24 |

P = probably present



Little River Rock

Photo by Art Sowls

036 Clam Beach was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).

037 "Mad River" was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).

038 Old Arcata Wharf 40°50'59"N, 124°05'58"W


| | | | |
|--------------------------|-----|------------------------------------|----|
| Double-crested Cormorant | 340 | (Sowls & Stewart, 6/19/80, B, III) | 42 |
| Double-crested Cormorant | 322 | (Ayers, 1971) | 5 |
| Double-crested Cormorant | 352 | (Ayers, 1972) | 5 |
| Double-crested Cormorant | 424 | (Ayers, 5/15/73) | 5 |
| Caspian Tern | X | (Harris, 6/16/66) | 23 |

X = present



Double-crested Cormorants, Old Arcata Wharf

Photo by Art Sowls



039 Humboldt Bay was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).

040 False Cape Rocks 40°30'38"N, 124°23'40"W


| | | | |
|---------------------|--------------------|--------------------------------------|----|
| Brandt's Cormorant | 400 | (Lester & Sows, 7/23/80, A, II) | 42 |
| Pelagic Cormorant | 170 | (Lester & Rodstrom, 7/26/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 7/26/79, B, III) | 42 |
| Western Gull | 220 | (Lester & Rodstrom, 7/26/79, B, III) | 42 |
| Common Murre | 8,000 ^Δ | (Lester & Rodstrom, 8/2/79, A, II) | 42 |
| Pigeon Guillemot | 150 | (Lester & Rodstrom, 7/26/79, B, III) | 42 |
| Total | 8,942 | | |
| Brandt's Cormorant | 406+ | (Osborne, 7/69, A) | 35 |
| Brandt's Cormorant | 640 | (Lester & Rodstrom, 8/2/79, A, II) | 42 |
| Pelagic Cormorant | P | (Osborne, 7/69, A) | 35 |
| Western Gull | X | (Osborne, 7/69, A) | 35 |
| Common Murre | 1,600 | (Osborne, 7/69, A) | 35 |
| Pigeon Guillemot | X | (Osborne, 7/69, A) | 35 |

X = present, P = probably present


^Δ Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/2/80 aerial survey (also times 1.67) is 11,000.

Section from U.S.G.S.
1:24,000 scale map:

Ferndale, Calif.



$40^{\circ}32'30''$
 $124^{\circ}22'30''$



041 Sugarloaf Island 40°26'18"N, 124°24'41"W

| | | | |
|--------------------------|--------------|--------------------------------------|----|
| Brandt's Cormorant | 200 | (Osborne, 1970, LM) | 35 |
| Double-crested Cormorant | 32 | (Osborne, 1970, LM) | 35 |
| Pelagic Cormorant | 400 | (Osborne, 1969-70, LM) | 35 |
| Black Oystercatcher | 6 | (Nelson & Sows, 7/26/79, B, III) | 42 |
| Western Gull | 320 | (Nelson & Sows, 7/26/79, B, III) | 42 |
| Pigeon Guillemot | 240 | (Nelson & Sows, 7/26/79, B, III) | 42 |
| Tufted Puffin | 4 | (Lester & Rodstrom, 5/10/79, M, III) | 42 |
| Total | <u>1,202</u> | | |
| Cormorant (unid.) | 100 | (Nelson & Sows, 7/26/79, B, III) | 42 |
| Brandt's Cormorant | 182 | (Nelson & Sows, 7/26/79, B, III) | 42 |
| Double-crested Cormorant | ? | (Nelson & Sows, 7/26/79, B) | 42 |
| Double-Crested Cormorant | 6 | (Osborne, 1969, LM) | 35 |
| Pelagic Cormorant | 210+ | (Nelson & Sows, 7/26/79, B, III) | 42 |
| Black Oystercatcher | X | (Osborne, 1969-70, LM) | 35 |
| Western Gull | 300 | (Osborne, 1969-70, LM) | 35 |
| Pigeon Guillemot | 200 | (Osborne, 1970, LM) | 35 |
| Tufted Puffin | 4 | (Osborne, 1970, LM) | 35 |

X = present

042 Steamboat Rock 40°24'54"N, 124°24'09"W

| | | | |
|--------------------|--------------------|---|----|
| Brandt's Cormorant | 494 | (Lester & Sows, 7/23/80, A, II) | 42 |
| Pelagic Cormorant | 0 | (Lester, Nelson, Rodstrom & Sows, 7/26/79, B, II) | 42 |
| Western Gull | 60 | (Lester, Nelson, Rodstrom & Sows, 7/26/79, B, III) | 42 |
| Common Murre | 4,500 ^Δ | (Lester & Rodstrom, 7/24/79, A, Lester, Nelson, Rodstrom & Sows, 7/26/79, B, III) | 42 |
| Pigeon Guillemot | 2 | (Lester, Nelson, Rodstrom & Sows, 7/26/79, B, III) | 42 |
| Total | <u>5,056</u> | | |
| Brandt's Cormorant | 340 | (Osborne, 1969-70, AM) | 35 |
| Brandt's Cormorant | 640 | (Lester & Rodstrom, 7/24/79, A, Lester, Nelson, Rodstrom & Sows, 7/26/79, B, II) | 42 |
| Pelagic Cormorant | 4 | (Osborne, 1969-70, AM) | 35 |
| Western Gull | X | (Osborne, 1969-70, AM) | 35 |
| Common Murre | 600 | (Osborne, 1969-70, AM) | 35 |

^Δ Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/2/80 aerial survey (also times 1.67) is 5,100.

043 Sea Lion Rock 40°19'35"N, 124°21'38"W

| | | | |
|-------------------|---|--------------------------------------|----|
| Cormorant (unid.) | 0 | (Nelson & Rodstrom, 7/18/79, B) | 42 |
| Western Gull | 2 | (Nelson & Rodstrom, 7/18/79, B, III) | 42 |
| Total | 2 | | |
| Cormorant (unid.) | X | (Osborne, 5/3/69, M) | 35 |

044 Point St. George Lighthouse 41°50'N, 124°22'W

| | | | |
|-------------------|----|---------------------------|----|
| Pelagic Cormorant | 12 | (Lester, 7/12/79, A, III) | 42 |
|-------------------|----|---------------------------|----|

No detailed map available see page 59.




045 "Whaler Island", Crescent City breakwater, Steamboat Rock and unnamed rocks. 41°45'N, 124°13'W.

| | | | |
|--------------------------|----------|---|----|
| Brandt's Cormorant | 40 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Pelagic Cormorant | 2 | (Berner & Lester, 6/20/80, B, I) | 42 |
| Black Oystercatcher | 4 | (Berner & Lester, 6/20/80, BL, III) | 42 |
| Western Gull | 24 | (Berner & Lester, 6/20/80, BL, III) | 42 |
| Pigeon Guillemot | 72 | (Berner & Lester, 6/20/80, BLM, III) | 42 |
| Total | 142 | | |
| Fork-tailed Storm-Petrel | X | (Clay, 5/14/16&1939, L; Talmadge, early 1930's) | 35 |
| Leach's Storm-Petrel | X | (Clay, 5/14/16&1939, L; Talmadge, early 1930's) | 35 |
| Fork-tailed Storm-Petrel | } 20,000 | (Howell, 7/16/19, L) | 35 |
| Leach's Storm-Petrel | | | |
| Black Oystercatcher | X | (Talmadge, early 1930's) | 35 |
| Western Gull | X | (Talmadge, early 1930's) | 35 |
| Pigeon Guillemot | X | (Howell, 7/16/19, L) | 35 |
| Cassin's Auklet | ? | (Clay, 3/22/25, L) | 35 |

046 Unnamed Small Rocks 41°42'N, 124°08'W

| | | | |
|--------------------------|-----|-------------------------------------|----|
| Double-crested Cormorant | 22 | (Berner & Lester, 6/20/80, B, II) | 42 |
| Pelagic Cormorant | 66 | (Berner & Lester, 6/20/80, B, II) | 42 |
| Black Oystercatcher | 6 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Western Gull | 28 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Pigeon Guillemot | 100 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Total | 222 | | |
| Double-crested Cormorant | 2 | (DeGange & Lester, 5/22/79, B, II) | 42 |
| Pelagic Cormorant | 6 | (DeGange & Lester, 5/22/79, B, I) | 42 |
| Black Oystercatcher | P | (DeGange & Lester, 5/22/79, B) | 42 |
| Western Gull | 8 | (DeGange & Lester, 5/22/79, B, III) | 42 |

X = present, P = probably present



(047) "Easy Triangle Rocks" 41°40'22"N, 124°08'30"W

| | | | |
|---------------------|----|-------------------------------------|----|
| Pelagic Cormorant | 54 | (Berner & Lester, 6/20/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Western Gull | 8 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Pigeon Guillemot | 20 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Total | 84 | | |
| Pelagic Cormorant | 20 | (DeGange & Lester, 5/22/79, B, II) | 42 |
| Black Oystercatcher | P | (DeGange & Lester, 5/22/79, B, III) | 42 |
| Western Gull | 12 | (DeGange & Lester, 5/22/79, B, II) | 42 |
| Pigeon Guillemot | 10 | (DeGange & Lester, 5/22/79, B, III) | 42 |

P = probably present

(048) "Rock R" 41°40'00"N, 124°08'30"W




| | | | |
|---------------------|-----|-------------------------------------|----|
| Brandt's Cormorant | 140 | (DeGange & Nelson, 7/25/80, A, II) | 42 |
| Pelagic Cormorant | 10 | (Berner & Lester, 6/20/80, B, II) | 42 |
| Western Gull | 4 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Pigeon Guillemot | 2 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Total | 156 | | |
| Brandt's Cormorant | 188 | (Lester, 6/19&7/12/79, A, I) | 42 |
| Pelagic Cormorant | 4 | (DeGange & Lester, 5/22/79, B, I) | 42 |
| Black Oystercatcher | 2 | (DeGange & Lester, 5/22/79, B, III) | 42 |

(049) "Last Chance Rock" 41°38'05"N, 124°07'30"W

| | | | |
|--------------------------|----|------------------------------------|----|
| Double-crested Cormorant | 4 | (Berner & Lester, 6/20/80, B, II) | 42 |
| Pelagic Cormorant | 40 | (Berner & Lester, 6/20/80, B, II) | 42 |
| Western Gull | 4 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Total | 48 | | |
| Pelagic Cormorant | 6 | (DeGange & Lester, 5/22/79, B, II) | 42 |
| Western Gull | 2 | (DeGange & Lester, 5/22/79, B, II) | 42 |

(050) Footsteps Rock 41°37'00"N, 124°07'10"W

| | | | |
|---------------------|-----|-------------------------------------|----|
| Pelagic Cormorant | 36 | (Berner & Lester, 6/20/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Western Gull | 4 | (Berner & Lester, 6/20/80, B, II) | 42 |
| Pigeon Guillemot | 60 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Total | 102 | | |
| Pelagic Cormorant | 20 | (DeGange & Lester, 5/22/79, B, I) | 42 |
| Black Oystercatcher | 2 | (DeGange & Lester, 5/22/79, B, III) | 42 |
| Pigeon Guillemot | 50 | (DeGange & Lester, 5/22/79, B, III) | 42 |





051 "Radar Station Rocks" 41°33'30"N, 124°06'00"W

| | | | |
|--------------------------|-----------|-------------------------------------|----|
| Double-crested Cormorant | 20 | (Lester & Rodstrom, 6/5/79, B, III) | 42 |
| Pelagic Cormorant | 34 | (Lester & Rodstrom, 6/5/79, B, II) | 42 |
| Black Oystercatcher | P | (Lester & Rodstrom, 6/5/79, B) | 42 |
| Western Gull | X | (Lester & Rodstrom, 6/5/79, B) | 42 |
| Pigeon Guillemot | 20 | (Lester & Rodstrom, 6/5/79, B, III) | 42 |
| Total | <u>74</u> | | |

X = present, P = probably present

052 Palmer's Point to Scotty Point (except 017) 41°07'N, 124°09'W

| | | | |
|---------------------|------------|--|----|
| Pelagic Cormorant | 100 | (Lester & Stewart, 6/23/80, B, II) | 42 |
| Black Oystercatcher | 10 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Western Gull | 20 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Pigeon Guillemot | 40 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Total | <u>170</u> | | |
| Pelagic Cormorant | 146 | (Lester, McKay & Rodstrom, 8/1/79, B, II) | 42 |
| Black Oystercatcher | 6 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Western Gull | 20 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Pigeon Guillemot | 50 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |






053 Scotty Point to Megwill Point (except 018 - 021)
41°05'N, 124°09'W

| | | | |
|---------------------|-----|--|----|
| Brandt's Cormorant | 2 | (Lester & Stewart, 6/23/80, B, II) | 42 |
| Pelagic Cormorant | 134 | (Lester & Stewart, 6/23/80, B, II) | 42 |
| Black Oystercatcher | 6 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Western Gull | 16 | (Lester & Stewart, 6/23/80, B, III) | 42 |
| Pigeon Guillemot | 60 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Total | 218 | | |
| Pelagic Cormorant | 96 | (Lester, McKay & Rodstrom, 8/1/79, B, II) | 42 |
| Black Oystercatcher | X | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Western Gull | 14 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |

X = present






(054) Trinidad Bay Rocks: "Double", "Mr'rp", Cap, "Split", "Button",
 "Luffenholtz", "Tepona", "Halfmoon", "Snag" and unnamed small
 rocks 41°03'N, 124°08'W

| | | | |
|--------------------------|-------|--|----|
| Fork-tailed Storm-Petrel | X | (Osborne, 1969-70, L) | 35 |
| Leach's Storm-Petrel | 1,640 | (Lester, SOWLS & Stewart, 1980, BL, III) | 42 |
| Pelagic Cormorant | 22 | (Lester & Stewart, 6/23/80, B, II) | 42 |
| Black Oystercatcher | 10 | (Lester & Stewart, 6/23/80, BL, III) | 42 |
| Western Gull | 22 | (Lester & Stewart, 6/23/80, BL, III) | 42 |
| Pigeon Guillemot | 60 | (Lester & Stewart, 6/23/80, BL, III) | 42 |
| Total | 1,754 | | |
| Leach's Storm-Petrel | 600 | (Osborne, 1969-70, L) | 35 |
| Pelagic Cormorant | 62 | (Osborne, 1969-70, L) | 35 |
| Pelagic Cormorant | 56 | (Lester, McKay & Rodstrom, 8/1/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Osborne, 1969-70, L) | 35 |
| Black Oystercatcher | 2 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Western Gull | X | (Osborne, 1969-70, L) | 35 |
| Western Gull | 12 | (Lester, McKay & Rodstrom, 8/1/79, B, III) | 42 |
| Pigeon Guillemot | 20 | (Osborne, 1969-70, L) | 35 |

X = present



Section from U.S.G.S.
1:24,000 scale map:

Trinidad & Crannel,

Calif.

Km




055 Three Brothers & Hair Seal Rocks 40°19'40"N, 124°21'58"W



| | | | |
|--------------------|------------|--------------------------------------|----|
| Brandt's Cormorant | 110 | (Nelson & Rodstrom, 7/18/79, B, II) | 42 |
| Pelagic Cormorant | 6 | (Nelson & Rodstrom, 7/18/79, B, I) | 42 |
| Western Gull | 4 | (Nelson & Rodstrom, 7/18/79, B, III) | 42 |
| Total | <u>120</u> | | |

056 "Cormorant Hotel" 40°02'10"N, 124°04'50"W


| | | | |
|-------------------|------------|--|----|
| Pelagic Cormorant | 280 | (Lester, Nelson, Rodstrom & Sows, 7/18/79, MB, II) | 42 |
| Western Gull | 2 | (Lester, Nelson, Rodstrom & Sows, 7/18/79, MB, I) | 42 |
| Total | <u>282</u> | | |



Section from U.S.G.S.
1:24,000 scale map:
Petrolia, Calif.



Section from U.S.G.S.
1:24,000 scale map:
Shelter Cove, Calif.





⑤⑦ Point St. George 41°47'N, 124°15'W

| | | | |
|---------------------|-----------|------------------------------------|----|
| Pelagic Cormorant | 14 | (Berner & Lester, 6/20/80, B, I) | 42 |
| Black Oystercatcher | 8 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Western Gull | 20 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Pigeon Guillemot | 40 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Total | <u>82</u> | | |

⑤⑧ Wilson Rock 41°35'45"N, 124°06'37"W

| | | | |
|---------------------|-----------|------------------------------------|----|
| Pelagic Cormorant | 2 | (Berner & Lester, 6/20/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Western Gull | 8 | (Berner & Lester, 6/20/80, B, III) | 42 |
| Total | <u>12</u> | | |





379


Ukiah


The map on the facing page is an index to the locations of colonies within map 379, Ukiah. Note that all colonies on the map are not numbered consecutively from north to south, since many previously unreported colonies have been added since initial colony numbers were assigned by Varoujean (1979). On the pages following this map, all colonies are listed sequentially and a detailed map of each is provided.

Numbers of breeding seabirds will vary from year to year. Below are the approximate numbers of breeding seabirds within this region.

| | |
|-------------------------------|-------------|
| Brandt's Cormorant. | 6,000 |
| Pelagic Cormorant | 4,000 |
| Black Oystercatcher | .70 |
| Western Gull. | 500 |
| Common Murre. | 6,000 |
| Pigeon Guillemot. | 1,000 |
| Marbled Murrelet. | no estimate |
| Rhinoceros Auklet | P |
| Tufted Puffin | .10 |

379 Ukiah






(001) "Rockport Rocks" 39°44'10"N, 123°50'00"W

| | | | |
|---------------------|-----|--------------------------------------|----|
| Brandt's Cormorant | 0 | (Lester & Rodstrom, 6/12/79, B, II) | 42 |
| Pelagic Cormorant | 250 | (Lester & Rodstrom, 6/12/79, B, III) | 42 |
| Black Oystercatcher | 2 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Western Gull | 10 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Pigeon Guillemot | 20 | (Lester & Rodstrom, 6/12/79, B, III) | 42 |
| Total | 282 | | |
| Brandt's Cormorant | X | (Osborne, 8/26/69, M) | 36 |

X = present

(002) Cape Vizcaino 39°43'34"N, 123°49'55"W

| | | | |
|--------------------|-------|---|----|
| Brandt's Cormorant | 3,080 | (Lester & Sows, 7/23/80, A, II) | 42 |
| Pelagic Cormorant | 120 | (Lester & Rodstrom, 6/12/79, B, III) | 42 |
| Western Gull | 60 | (Lester & Rodstrom, 6/12/79, B, III) | 42 |
| Common Murre | 5,800 | (Briggs & Lewis, 5/7/80, A, III) | 42 |
| Pigeon Guillemot | 8 | (Lester, Sows & Stewart, 7/12/80, M, III) | 42 |
| Total | 9,068 | | |
| Brandt's Cormorant | 1,000 | (Osborne, 8/26/69, M) | 36 |
| Brandt's Cormorant | 3,662 | (Lester & Rodstrom, 8/2/79, A, III) | 42 |
| Pelagic Cormorant | 50 | (Osborne, 8/26/69, M) | 36 |
| Western Gull | 40 | (Osborne, 8/26/69, M) | 36 |



Cape Vizcaino

Photo by Gary Lester

003 Chris Rocks 39°42'51"N, 123°48'07"W

| | | | |
|-------------------|----|----------------------------------|----|
| Pelagic Cormorant | 54 | (Lester & Sows, 7/19/79, B, II) | 42 |
| Western Gull | 6 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Total | 60 | | |
| Pelagic Cormorant | 40 | (Osborne, 8/25/69, M) | 36 |





Chris Rock

Photo by Tim Osborne

004 Kibesillah Rock 39°34'49"N, 123°46'51"W

| | | | |
|--------------------|-----|--------------------------------------|----|
| Brandt's Cormorant | 350 | (Lester & Sows, 7/23/80, A, II) | 42 |
| Pelagic Cormorant | 92 | (Lester & Rodstrom, 6/12/79, B, III) | 42 |
| Western Gull | 20 | (Lester & Rodstrom, 6/12/79, B) | 42 |
| Total | 462 | | |
| Brandt's Cormorant | 150 | (Osborne, 8/26/69, M) | 36 |
| Brandt's Cormorant | 490 | (Lester & Rodstrom, 8/2/79, A, III) | 42 |

005 MacKerricher Beach was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).



Kibesillah Rock

Photo by Gary Lester


006 Goat Island Area 39 18'28"N, 123 48'49"W

| | | | |
|---------------------|-------|---|----|
| Brandt's Cormorant | 1,240 | (Lester & Sows,7/23/80,A,II) | 42 |
| Pelagic Cormorant | 134 | (Lester & Sows,6/5/80,BM,II) | 42 |
| Black Oystercatcher | 6 | (DeGange & Lester & Nelson,6/5/80,BL,III) | 42 |
| Western Gull | 2 | (DeGange & Lester & Nelson,6/5/80,BL,II) | 42 |
| Pigeon Guillemot | 120 | (Sows,6/5/80,BM,III) | 42 |
| Tufted Puffin | 4 | (DeGange, Nelson & Sows,LM,II) | 42 |
| Total | 1,506 | | |
| Brandt's Cormorant | 500 | (Osborne,8/26/69,L) | 36 |
| Brandt's Cormorant | 1,400 | (Lester & Rodstrom,8/2/79,A,III) | 42 |
| Pelagic Cormorant | 30 | (Osborne,8/26/69,L) | 36 |
| Pelagic Cormorant | 38 | (Lester & Rodstrom,6/21/79,B,III) | 42 |
| Black Oystercatcher | 2 | (Osborne,8/26/69,L) | 36 |
| Black Oystercatcher | 2 | (Rodstrom,5/17/79,M,III) | 42 |
| Western Gull | 24 | (Lester & Rodstrom,6/21/79,B,III) | 42 |
| Pigeon Guillemot | 12 | (Lester & Rodstrom,6/21/79,B,III) | 42 |



Main nesting island ("a" on map).

Photo by Gary Lester



007 "Devil's Basin" 39°10'14"N, 123°44'50"W


| | | | |
|---------------------|-----|---|----|
| Brandt's Cormorant | 300 | (Lester & Sows, 7/23/80, A, III) | 42 |
| Pelagic Cormorant | 132 | (Lester, Sows & Stewart, 7/12/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Nelson, Sows & Stewart, 6/6/80, B, II) | 42 |
| Western Gull | 14 | (Lester, Sows & Stewart, 7/12/80, B, III) | 42 |
| Pigeon Guillemot | 20 | (Lester, Sows & Stewart, 7/12/80, B, III) | 42 |
| Total | 468 | | |
| Brandt's Cormorant | 350 | (Osborne, 8/25/69, M) | 36 |
| Brandt's Cormorant | 380 | (Lester & Rodstrom, 8/2/79, A, III) | 42 |
| Pelagic Cormorant | 70 | (Osborne, 8/25/69, M) | 36 |
| Pelagic Cormorant | 52 | (Lester & Rodstrom, 6/22/79, B, II) | 42 |
| Western Gull | X | (Osborne, 8/25/69, M) | 36 |
| Western Gull | 6 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |

X = present



Most Brandt's Cormorants nest on this rock in "Devils Basin."

Photo by Art Sows



(008) Wharf Rocks 39°07'49"N, 123°43'24"W

| | | | |
|---------------------|------------|--|----|
| Pelagic Cormorant | 90 | (Lester, Sowls & Stewart, 7/12/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester, Sowls & Stewart, 7/12/80, B, II) | 42 |
| Western Gull | 10 | (Lester, Sowls & Stewart, 7/12/80, B, III) | 42 |
| Pigeon Guillemot | 34 | (Lester, Sowls & Stewart, 7/12/80, B, III) | 42 |
| Total | <u>136</u> | | |
| Pelagic Cormorant | 20 | (Osborne, 8/25/69, L) | 36 |
| Pelagic Cormorant | 62 | (Lester & Rodstrom, 6/22/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/22/79, B) | 42 |
| Western Gull | 20 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |



(009) Casket Rock 39°07'49"N, 123°43'39"W

| | | | |
|--------------------|------------|---|----|
| Brandt's Cormorant | 330 | (Lester & Sowls, 7/23/80, A, II) | 42 |
| Pelagic Cormorant | 0 | (Lester, Sowls & Stewart, 7/12/80, B, II) | 42 |
| Western Gull | 2 | (Lester, Sowls & Stewart, 7/12/80, B, II) | 42 |
| Pigeon Guillemot | 10 | (Lester, Sowls & Stewart, 7/12/80, B, III) | 42 |
| Total | <u>342</u> | | |
| Brandt's Cormorant | 100+ | (Osborne, 8/25/69, M) | 36 |
| Brandt's Cormorant | 0 | (Lester & Rodstrom, 6/22/79, B, 8/2/79, A, I) | 42 |
| Pelagic Cormorant | X | (Osborne, 8/25/69, M) | 36 |
| Pelagic Cormorant | 2 | (Lester & Rodstrom, 6/22/79, B, II) | 42 |

(010) White Rock 39°05'42"N, 123°43'11"W

| | | | |
|--------------------|-----------|--------------------------------------|----|
| Brandt's Cormorant | 0 | (Lester & Sowls, 7/23/80, A, II) | 42 |
| Western Gull | 40 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |
| Pigeon Guillemot | 10 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |
| Total | <u>50</u> | | |
| Brandt's Cormorant | 200 | (Osborne, 8/25/69, M) | 36 |
| Brandt's Cormorant | 448 | (Lester & Rodstrom, 8/2/79, A, III) | 42 |
| Pelagic Cormorant | X | (Osborne, 8/25/69, M) | 36 |
| Western Gull | X | (Osborne, 8/25/69, M) | 36 |

X = present





① Point No Pass 39°58'40"N, 123°59'40"W

| | | | |
|-------------------|-----------|----------------------------------|----|
| Pelagic Cormorant | 68 | (Lester & Sows, 7/19/79, B, II) | 42 |
| Western Gull | 2 | (Lester & Sows, 7/19/79, B, II) | 42 |
| Pigeon Guillemot | 2 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Total | <u>72</u> | | |

② High Tip 39°55'30"N, 123°57'10"W

| | | | |
|---------------------|-----------|----------------------------------|----|
| Pelagic Cormorant | 80 | (Lester & Sows, 7/19/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Western Gull | 4 | (Lester & Sows, 7/19/79, B, II) | 42 |
| Pigeon Guillemot | 4 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Total | <u>90</u> | | |




013 Anderson Cliffs 39°52'30"N, 123°54'30"W

| | | | |
|--------------------|------------|----------------------------------|----|
| Brandt's Cormorant | 304 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Pelagic Cormorant | 132 | (Lester & Sows, 7/19/79, B, II) | 42 |
| Western Gull | 4 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Pigeon Guillemot | 40 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Total | <u>480</u> | | |

014 Mistake Point to Big White Rock 39°51'30"N, 123°53'30"W

| | | | |
|-------------------|------------|----------------------------------|----|
| Pelagic Cormorant | 132 | (Lester & Sows, 7/19/79, B, II) | 42 |
| Western Gull | 2 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Pigeon Guillemot | 100 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Total | <u>234</u> | | |





(015) Usal Bay 39°48'45"N, 123°50'30"W

| | | | |
|-------------------|------------|----------------------------------|----|
| Pelagic Cormorant | 62 | (Lester & Sows, 7/19/79, B, II) | 42 |
| Western Gull | 2 | (Lester & Sows, 7/19/79, B, II) | 42 |
| Pigeon Guillemot | 40 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Total | <u>104</u> | | |

(016) Soldier Frank Point 39°45'18"N, 123°50'15"W

| | | | |
|-------------------|-----------|----------------------------------|----|
| Pelagic Cormorant | 18 | (Lester & Sows, 7/19/79, B, II) | 42 |
| Western Gull | 20 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Pigeon Guillemot | 20 | (Lester & Sows, 7/19/79, B, III) | 42 |
| Total | <u>58</u> | | |



017 Hardy Rock & "Union Landing" 39°42'20"N, 123°38'20"W



| | | | |
|-------------------|-----------|---|---|
| Pelagic Cormorant | 46 | (Lester, Rodstrom & Sows, 6/10/79, B, 8/8/79, M, III) | 4 |
| Western Gull | 8 | (Lester & Sows, 8/8/79, M, III) | 4 |
| Pigeon Guillemot | 6 | (Lester, Rodstrom & Sows, 6/10/79, B, 8/8/79, M, III) | 4 |
| Total | <u>60</u> | | |

018 Westport 39°38'00"N, 123°47'20"W

| | | | |
|---------------------|------------|--------------------------------------|----|
| Pelagic Cormorant | 178 | (Lester & Rodstrom, 6/13/79, M, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/13/79, M, III) | 42 |
| Western Gull | 4 | (Lester & Rodstrom, 6/13/79, M, II) | 42 |
| Pigeon Guillemot | 4 | (Lester & Rodstrom, 6/13/79, M, III) | 42 |
| Total | <u>188</u> | | |

019 "Chadbourne Rocks" 39°37'02"N, 123°47'W

| | | | |
|-------------------|----|--------------------------------------|----|
| Pelagic Cormorant | 74 | (Lester & Rodstrom, 6/13/79, BM, II) | 42 |
|-------------------|----|--------------------------------------|----|




②0 "Strawberry Cove" 39°35'37"N, 123°47'10"W

| | | | |
|---------------------|-----------|---------------------------------------|----|
| Pelagic Cormorant | 84 | (Lester & Rodstrom, 6/13/79, BM, I) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/13/79, BM, III) | 42 |
| Pigeon Guillemot | 10 | (Lester & Rodstrom, 6/13/79, BM, III) | 42 |
| Total | <u>96</u> | | |

②1 "Newport Rocks" except Kibesillah Rock 39°34'49"N, 123°46'51"W

| | | | |
|---------------------|------------|---|----|
| Pelagic Cormorant | 192 | (Lester & Rodstrom, 6/13/79, BM, & 6/20/79, M, III) | 42 |
| Black Oystercatcher | 4 | (Lester & Rodstrom, 6/20/79, M, III) | 42 |
| Western Gull | 2 | (Lester & Rodstrom, 6/20/79, M, II) | 42 |
| Pigeon Guillemot | 28 | (Lester & Rodstrom, 6/13/79, BM, III) | 42 |
| Total | <u>226</u> | | |






022 "Georgia Pacific" 39°27'N, 123°48'45"W

| | | | |
|---------------------|-----------|--------------------------------------|----|
| Pelagic Cormorant | 32 | (Lester & Rodstrom, 6/13/79, M, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/13/79, M, III) | 42 |
| Western Gull | 4 | (Lester & Rodstrom, 6/13/79, M, II) | 42 |
| Total | <u>38</u> | | |

023 Caspar Anchorage 39°22'N, 123°49'10"W

| | | | |
|---------------------|-----------|--------------------------------------|----|
| Pelagic Cormorant | 58 | (Lester & Rodstrom, 6/12/79, B, I) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/12/79, B, III) | 42 |
| Pigeon Guillemot | 2 | (Lester & Rodstrom, 6/12/79, B, III) | 42 |
| Total | <u>62</u> | | |







024 Point Cabrillo to Jack Peters Gulch 39°20'N, 123°49'W

| | | | |
|---------------------|------------|---|----|
| Pelagic Cormorant | 192 | (Lester & Rodstrom, 6/11&6/21/79, B, III) | 42 |
| Black Oystercatcher | 4 | (Lester & Rodstrom, 6/14/79, M, III) | 42 |
| Pigeon Guillemot | 38 | (Lester & Rodstrom, 6/11&6/21/79, B, III) | 42 |
| Total | <u>234</u> | | |

Section from U.S.G.S.
1:24,000 scale map:

Mendocino, Calif.



025 Mendocino 39°18'10"N, 123°47'50"W


| | | | |
|---------------------|-----------|---|----|
| Pelagic Cormorant | 52 | (Nelson & Sows, 6/5/80, B, I) | 42 |
| Black Oystercatcher | 2 | (DeGange, Lester & Nelson, 6/5/80, BL, I) | 42 |
| Pigeon Guillemot | 32 | (Lester & Stewart, 6/5/80, M, III) | 42 |
| Total | <u>86</u> | | |
| Pelagic Cormorant | 44 | (Sows, 5/18/79, M, II) | 42 |
| Pigeon Guillemot | 50 | (Sows, 5/18/79, M, III) | 42 |

026 Mendocino Bay 39°17'30"N, 123°47'40"W

| | | | |
|---------------------|------------|--|----|
| Pelagic Cormorant | 86 | (DeGange, Lester & Sows, 6/5/80, B, I) | 42 |
| Black Oystercatcher | 2 | (DeGange, Lester & Nelson, 6/5/80, B, III) | 42 |
| Pigeon Guillemot | 20 | (DeGange, Nelson & Sows, 6/5/80, B, III) | 42 |
| Total | <u>108</u> | | |
| Pelagic Cormorant | 50 | (Lester & Rodstrom, 6/21/79, B, III) | 42 |
| Pigeon Guillemot | 16 | (Lester & Rodstrom, 6/21/79, B, III) | 42 |

027 "Van Damme Cove" 39°16'10"N, 123°47'28"W

| | | | |
|---------------------|------------|---|----|
| Pelagic Cormorant | 26 | (DeGange, Nelson & Stewart, 6/5/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester, Sows & Stewart, 6/6/80, BL, III) | 42 |
| Western Gull | 140 | (Lester & Rodstrom, 5/18/79, BL, III) | 42 |
| Pigeon Guillemot | 120 | (DeGange, Lester & Nelson, 6/5/80, BL, III) | 42 |
| Tufted Puffin | 2 | (Lester, Sows & Stewart, 6/6/80, L, II) | 42 |
| Total | <u>290</u> | | |
| Pelagic Cormorant | 56 | (Lester & Rodstrom, 5/18/79, BL, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 5/18/79, BL, III) | 42 |
| Pigeon Guillemot | 30 | (Lester & Rodstrom, 5/18/79, BL, III) | 42 |
| Tufted Puffin | 4 | (Lester & Rodstrom, 5/18/79, BL, II) | 42 |




028 Schoolhouse Creek to Albion River 39°15'N, 123°46'30"W

| | | | |
|---------------------|------------|--|----|
| Pelagic Cormorant | 436 | (DeGange, Nelson & Stewart, 6/5/80, B, II) | 42 |
| Black Oystercatcher | 14 | (DeGange, Nelson & Stewart, 6/5/80, B, III) | 42 |
| Western Gull | 34 | (DeGange, Nelson & Stewart, 6/5/80, B, III) | 42 |
| Pigeon Guillemot | 68 | (Lester & Rodstrom, 6/21/79, B, III) | 42 |
| Total | <u>552</u> | | |
| Pelagic Cormorant | 336 | (Lester & Rodstrom, 5/18/79, B, 6/21/79, B, II) | 42 |
| Black Oystercatcher | 4 | (Lester & Rodstrom, 5/18/79, B, 6/21/79, B, III) | 42 |
| Western Gull | 10 | (Lester & Rodstrom, 5/18/79, B, 6/21/79, B, III) | 42 |

(029) Albion Cove to Navarro River 39°12'30"N, 123°46'20"W

| | | | |
|---------------------|------------|---|----|
| Pelagic Cormorant | 266 | (Nelson, Sowls & Stewart, 6/6/80, B, II) | 42 |
| Black Oystercatcher | 8 | (Nelson, Sowls & Stewart, 6/6/80, B, II) | 42 |
| Western Gull | 16 | (Nelson, Sowls & Stewart, 6/6/80, B, III) | 42 |
| Pigeon Guillemot | 30 | (Nelson, Sowls & Stewart, 6/6/80, B, III) | 42 |
| Total | <u>430</u> | | |
| Pelagic Cormorant | 80 | (Lester & Rodstrom, 6/21/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/21/79, B, III) | 42 |




$\pm 39^{\circ}12'30''$
 $123^{\circ}47'30''$

029

Section from U.S.G.S.
1:24,000 scale map:

Albion, Calif.





030 Cavanaugh Cove to Gunderson Rock, except Wharf Rock (008) and Casket Rock (009) 39°08'N, 123°44'W

| | | | |
|---------------------|------------|--|----|
| Brandt's Cormorant | 4 | (Lester, Sowls & Stewart, 7/12/80, B, III) | 42 |
| Pelagic Cormorant | 410 | (Lester, Sowls & Stewart, 7/12/80, B, II) | 42 |
| Black Oystercatcher | 8 | (Lester, Sowls & Stewart, 7/12/80, B, III) | 42 |
| Western Gull | 20 | (Lester, Sowls & Stewart, 7/12/80, B, III) | 42 |
| Pigeon Guillemot | 100 | (Lester, Sowls & Stewart, 7/12/80, B, III) | 42 |
| Total | <u>542</u> | | |
| Pelagic Cormorant | 398 | (Lester & Rodstrom, 6/22/79, B, II) | 42 |
| Black Oystercatcher | 8 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |
| Western Gull | 4 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |

031 "Bonee Cliffs" 39°07'N, 123°42'45"W

| | | | |
|-------------------|------------|--------------------------------------|----|
| Pelagic Cormorant | 176 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |
| Pigeon Guillemot | 40 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |
| Total | <u>216</u> | | |



AREA 379, Ukiah (cont'd.)

032 "333 Point" 39°05'N, 123°42'30"W



| | | | |
|---------------------|------------|--|----|
| Brandt's Cormorant | 360 | (Lester & Sows, 7/23/80, A, II) | 42 |
| Pelagic Cormorant | 100 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |
| Total | <u>462</u> | | |
| Brandt's Cormorant | 0 | (Lester & Rodstrom, 6/22/79, B, 8/2/79, A, II) | 42 |


033 Bridgeport Landing 39°03'45"N, 123°41'50"W

| | | | |
|-------------------|-----------|--------------------------------------|----|
| Pelagic Cormorant | 16 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |
| Western Gull | 2 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |
| Total | <u>18</u> | | |

034 Mallo Pass Creek 39°02'20"N, 123°41'50"W

| | | | |
|-------------------|-----------|--------------------------------------|----|
| Pelagic Cormorant | 20 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |
| Western Gull | 4 | (Lester & Rodstrom, 6/22/79, B, II) | 42 |
| Pigeon Guillemot | 20 | (Lester & Rodstrom, 6/22/79, B, III) | 42 |
| Total | <u>44</u> | | |





404

Santa Rosa


The map on the facing page is an index to the locations of colonies within map 404, Santa Rosa. Note that all colonies on the map are not numbered consecutively from north to south, since many previously unreported colonies have been added since initial colony numbers were assigned by Varoujean (1979). On the pages following this map, all colonies are listed sequentially and a detailed map of each is provided.


Numbers of breeding seabirds will vary from year to year. Below are the approximate numbers of breeding seabirds within this region.

| | |
|------------------------------------|-------------|
| Leach's Storm-Petrel | 100 |
| Ashy Storm-Petrel | .14 |
| Brandt's Cormorant | 4,000 |
| Double-crested Cormorant | 100* |
| Pelagic Cormorant | 4,000 |
| Black Oystercatcher | .60 |
| Western Gull | 1,100 |
| Pigeon Guillemot | 1,200 |
| Marbled Murrelet | no estimate |
| Rhinoceros Auklet | .20 |
| Tufted Puffin | .10 |

* coastal population only.

404 Santa Rosa







(001) Sea Lion Rocks 38°55'07"N, 123°43'45"W

| | | | |
|---------------------|----|--------------------------------------|----|
| Pelagic Cormorant | 6 | (Lester & Rodstrom, 5/31/79, B, III) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 5/31/79, B, III) | 42 |
| Western Gull | 2 | (Lester & Rodstrom, 5/31/79, B, III) | 42 |
| Pigeon Guillemot | 60 | (Lester & Rodstrom, 5/31/79, B, III) | 42 |
| Total | 70 | | |
| Pelagic Cormorant | 40 | (Osborne, 8/25/69, M) | 36 |
| Western Gull | P | (Osborne, 8/25/69, M) | 36 |
| Pigeon Guillemot | 2 | (Osborne, 8/25/69, M) | 36 |

P = probably present

(002) "Iverson Landing" 38°50'39"N, 123°38'37"W

| | | | |
|---------------------|-----|---|----|
| Pelagic Cormorant | 96 | (Lester, Sows & Stewart, 7/13/80, B, II) | 42 |
| Black Oystercatcher | 4 | (Lester, Sows & Stewart, 7/13/80, B, III) | 42 |
| Pigeon Guillemot | 30 | (Lester, Sows & Stewart, 7/13/80, B, III) | 42 |
| Total | 130 | | |
| Pelagic Cormorant | 120 | (Osborne, 8/25/69, M) | 36 |
| Pelagic Cormorant | 108 | (Lester & Rodstrom, 5/31/79, B, II) | 42 |



003 Fish Rocks 38°48'00"N, 123°35'31"W

The Fish Rocks colonies are some of the most important seabird colonies along the northern coast of California. They are inhabited by a great diversity of seabirds and are also important hauling areas for California sea lions and Harbor seals.

| | | | |
|----------------------|-------|--|----|
| Leach's Storm-Petrel | 100 | (DeGange, Lester & Stewart, 1980, L, III) | 42 |
| Brandt's Cormorant | 18 | (Lester, Nelson & SOWls, 6/7/80, BL, II) | 42 |
| Pelagic Cormorant | 400 | (Lester, Nelson, SOWls & Stewart, 1980, B, II) | 42 |
| Black Oystercatcher | 4 | (Lester & Rodstrom, 5/31/79, BL, III) | 42 |
| Western Gull | 350 | (Lester & Rodstrom, 5/31/79, BL, III) | 42 |
| Pigeon Guillemot | 250 | (Nelson, SOWls & Stewart, 6/7/80, B, III) | 42 |
| Rhinoceros Auklet | 14 | (Nelson, SOWls & Stewart, 6/7/80, B, III) | 42 |
| Tufted Puffin | 4 | (DeGange, Lester & Nelson, 6/7/80, BL, II) | 42 |
| Total | 1,130 | | |
| Brandt's Cormorant | 30 | (Lester & Rodstrom, 5/31/79, BL, III) | 42 |
| Pelagic Cormorant | 200 | (Osborne, 8/27/69, B) | 36 |
| Pelagic Cormorant | 200 | (Lester & Rodstrom, 5/31/79, BL, III) | 42 |
| Black Oystercatcher | 2 | (DeGange, Lester & Nelson, 6/7/80, BL, III) | 42 |
| Western Gull | 100 | (Osborne, 8/27/69, B) | 36 |
| Pigeon Guillemot | 6 | (Osborne, 8/27/69, B) | 36 |



Pelagic Cormorant, Fish Rocks

Photo by Bill Rodstrom



004 Gualala Point Island 38°45'04"N, 123°31'42"W

| | | | |
|--------------------|-------|--|----|
| Brandt's Cormorant | 1,240 | (Lester & SOWls, 7/23/80, A, II) | 42 |
| Western Gull | 40 | (DeGange, 6/11/80, M, III) | 42 |
| Pigeon Guillemot | 40 | (Lester, SOWls & Stewart, 7/13/80, B, III) | 42 |
| Total | 1,320 | | |
| Brandt's Cormorant | 500 | (Osborne, 8/27/69, M) | 36 |
| Brandt's Cormorant | 1,840 | (Lester & Rodstrom, 8/2/79, A, III) | 42 |
| Western Gull | 40 | (Lester & Rodstrom, 6/24/79, B, III) | 42 |





Gualala Point Island

Photo by Gary Lester

005 "Russian River Rocks" 38°27'14"N, 123°08'34"W

| | | | |
|--------------------------|-----|--------------------------------------|----|
| Brandt's Cormorant | 124 | (Lester & Rodstrom, 6/25/79, B, II) | 42 |
| Double-crested Cormorant | 32 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Pelagic Cormorant | 88 | (Lester & Rodstrom, 6/25/79, B, II) | 42 |
| Western Gull | 64 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Pigeon Guillemot | 40 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Total | 348 | | |
| Pelagic Cormorant | 200 | (Osborne, 8/23/69, M) | 36 |



006 Arched Rock 38°25'53"N, 123°07'32"W

| | | | |
|---------------------|-----|--------------------------------------|----|
| Brandt's Cormorant | 0 | (Lester & SOWls, 7/23/80, A, I) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Western Gull | 60 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Pigeon Guillemot | 20 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Tufted Puffin | 2 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Total | 84 | | |
| Brandt's Cormorant | 150 | (Osborne, 8/23/69, M) | 36 |
| Brandt's Cormorant | 400 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Western Gull | 6 | (Osborne, 8/23/69, M) | 36 |

007 Salmon Creek was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).



008 Bodega Rock 38°17'48"N, 123°02'50"W

| | | | |
|---------------------|-------|--------------------------------------|----|
| Brandt's Cormorant | 1,350 | (Nelson & SOWls, 6/24/80, A, II) | 42 |
| Black Oystercatcher | 2 | (Osborne, 8/23/69, L) | 36 |
| Western Gull | 50 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Total | 1,402 | | |
| Brandt's Cormorant | 800 | (Osborne, 8/23/69, L) | 36 |
| Brandt's Cormorant | 1,350 | (Jurek, 6/15/72, A, II) | 12 |
| Brandt's Cormorant | 1,714 | (Lester & Rodstrom, 7/11/79, A, II) | 42 |




Bodega Rock

Photo by Jay Nelson



009 "Dillon Beach Rocks" 38°16'26"N, 122°59'11"W

| | | | |
|---------------------|-----|--------------------------------------|----|
| Brandt's Cormorant | 190 | (Lester & Sows, 7/23/80, A, II) | 42 |
| Pelagic Cormorant | 186 | (Lester & Rodstrom, 6/26/79, B, II) | 42 |
| Black Oystercatcher | 6 | (Lester & Rodstrom, 6/26/79, B, III) | 42 |
| Western Gull | 12 | (Lester & Rodstrom, 6/26/79, B, III) | 42 |
| Pigeon Guillemot | 40 | (Lester & Rodstrom, 6/26/79, B, III) | 42 |
| Total | 434 | | |
| Pelagic Cormorant | 250 | (Osborne, 8/23/69, M) | 36 |
| Brandt's Cormorant | 168 | (Lester & Rodstrom, 6/26/79, B, II) | 42 |



010 Bird Rock 38°13'49"N, 122°59'35"W


| | | | |
|---------------------|-----|-------------------------------------|----|
| Ashy Storm-Petrel | 14 | (Lester & Rodstrom, 7/1/79, L, II) | 42 |
| Pelagic Cormorant | 8 | (Lester & Rodstrom, 7/1/79, L, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 7/1/79, L, III) | 42 |
| Western Gull | 228 | (Lester & Rodstrom, 7/1/79, L, III) | 42 |
| Pigeon Guillemot | 30 | (Lester & Rodstrom, 7/1/79, L, III) | 42 |
| Total | 282 | | |
| Ashy Storm-Petrel | 10 | (Ainley & Osborne, 7/3/72, L) | 3 |
| Pelagic Cormorant | 2 | (Osborne, 8/23/69, B) | 36 |
| Black Oystercatcher | 6 | (Ainley & Osborne, 7/3/72, L) | 3 |
| Western Gull | 60 | (Ainley & Osborne, 7/3/72, L) | 3 |
| Pigeon Guillemot | 24 | (Ainley & Osborne, 7/3/72, L) | 3 |

011 Tomales Point 38°12'13"N, 122°57'39"W

| | | | |
|-------------------|-----|-------------------------------------|----|
| Pelagic Cormorant | 134 | (Lester & Rodstrom, 7/1/79, B, III) | 42 |
| Western Gull | 2 | (Lester & Rodstrom, 7/1/79, B, III) | 42 |
| Pigeon Guillemot | 8 | (Ainley & Whitt, 7/3/72, B) | 3 |
| Total | 144 | | |
| Pelagic Cormorant | 172 | (Ainley & Whitt, 7/3/72, B) | 3 |

012 Point Reyes Beach was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).

013 Limantour Estero was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).



014 Napa River was previously assigned a catalog number because of Double-crested Cormorant, California Clapper Rail, and Caspian Tern nesting. We have not included information on this site because it is not coastal. See Varoujean (1979).

015 Petaluma River was previously assigned a catalog number because of California Clapper Rail nesting. We have not included information on this species in this report. See Gould (1973).

016 Gallinas Creek was previously assigned a catalog number because of California Clapper Rail nesting. We have not included information on this species in this report. See Gould (1973).

017 Point Arena 38°57'20"N, 123°44'30"W



| | | | |
|---------------------|----|---------------------------|----|
| Pelagic Cormorant | 28 | (Lester, 5/23/79, M, II) | 42 |
| Black Oystercatcher | 2 | (Lester, 5/23/79, M, III) | 42 |
| Pigeon Guillemot | 60 | (Lester, 5/23/79, M, III) | 42 |
| Total | 90 | | |

018 "Moat Cove" 38°53'10"N, 123°41'W

| | | | |
|-------------------|----|--------------------------------------|----|
| Pelagic Cormorant | 40 | (Lester & Rodstrom, 5/31/79, B, III) | 42 |
|-------------------|----|--------------------------------------|----|

019 "Section 30 Cove" 38°52'39"N, 123°40'10"W

| | | | |
|------------------|----|--------------------------------------|----|
| Pigeon Guillemot | 30 | (Lester & Rodstrom, 5/31/79, B, III) | 42 |
|------------------|----|--------------------------------------|----|



020 Saunders Landing 38°51'13"N, 123°39'05"W

| | | | |
|-------------------|------------|---------------------------------------|----|
| Pelagic Cormorant | 174 | (Lester, Sows & Stewart, 7/13/80, II) | 42 |
| Pigeon Guillemot | 2 | (Lester & Rodstrom, 5/31/79, B, III) | 42 |
| Total | <u>176</u> | | |
| Pelagic Cormorant | 48 | (Lester & Rodstrom, 5/31/79, B, III) | 42 |

021 Triplett Gulch 38°49'N, 123°36'15"W

| | | | |
|---------------------|------------|--|----|
| Pelagic Cormorant | 390 | (Lester, Sows & Stewart, 6/6/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester, Sows & Stewart, 6/6/80, B, III) | 42 |
| Pigeon Guillemot | 200 | (Lester, Sows & Stewart, 6/6/80, B, III) | 42 |
| Total | <u>592</u> | | |
| Pelagic Cormorant | 294 | (Lester & Rodstrom, 5/31/79, B, III) | 42 |

022 "Fish Rock Cove" 38°47'45"N, 123°35'20"W



| | | | |
|--------------------|-----------|--|----|
| Brandt's Cormorant | 18 | (Lester, Sows & Stewart, 7/13/80, B, II) | 42 |
| Pelagic Cormorant | 54 | (Lester, Sows & Stewart, 7/13/80, B, II) | 42 |
| Total | <u>72</u> | | |
| Pelagic Cormorant | 36 | (Lester & Rodstrom, 5/31/79, B, II) | 42 |


023 Collins Landing to Gualala River 38°46'N, 123°32'40"W

| | | | |
|---------------------|-----|--|----|
| Pelagic Cormorant | 368 | (Lester, SOWls & Stewart, 7/13/80, B, II) | 42 |
| Black Oystercatcher | 6 | (Lester, SOWls & Stewart, 7/13/80, B, III) | 42 |
| Western Gull | 2 | (Lester, SOWls & Stewart, 7/13/80, B, III) | 42 |
| Pigeon Guillemot | 30 | (Lester, SOWls & Stewart, 7/13/80, B, III) | 42 |
| Total | 406 | | |
| Pelagic Cormorant | 154 | (Lester & Rodstrom, 6/24/79, B, III) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/24/79, B, III) | 42 |

024 Del Mar Point 38°15'N, 123°31'W

| | | | |
|-------------------|----|--------------------------------------|----|
| Pelagic Cormorant | 12 | (Lester & Rodstrom, 6/24/79, B, III) | 42 |
|-------------------|----|--------------------------------------|----|






025 Sea Ranch 38°42'N, 123°27'30"W

| | | | |
|---------------------|------------|---|----|
| Pelagic Cormorant | 164 | (Lester & Rodstrom, 6/1/79, M, & 6/24/79, B, III) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/1/79, M, II) | 42 |
| Western Gull | 20 | (Lester & Rodstrom, 6/24/79, B, III) | 42 |
| Pigeon Guillemot | 8 | (Lester & Rodstrom, 6/24/79, B, III) | 42 |
| Total | <u>194</u> | | |






②②⑥ Black Point to Stewarts Point 38°40'N, 123°25'15"W

| | | | |
|-------------------|----------|-----------------------------------|----|
| Pelagic Cormorant | 54 | (Lester & Rodstrom,6/24/79,B,III) | 42 |
| Pigeon Guillemot | <u>2</u> | (Lester & Rodstrom,6/24/79,B,III) | 42 |
| Total | 56 | | |

②②⑦ Stewarts Point to Rocky Point 38°39'N, 123°38'45"W

| | | | |
|-------------------|----------|-----------------------------------|----|
| Pelagic Cormorant | 76 | (Lester & Rodstrom,6/24/79,B,II) | 42 |
| Western Gull | 8 | (Lester & Rodstrom,6/24/79,B,II) | 42 |
| Pigeon Guillemot | <u>6</u> | (Lester & Rodstrom,6/24/79,B,III) | 42 |
| Total | 90 | | |




028 Horseshoe Cove 38°36'30"N, 123°22'10"W

| | | | |
|-------------------|-----------|--------------------------------------|----|
| Pelagic Cormorant | 50 | (Lester & Rodstrom, 6/24/79, B, III) | 42 |
| Pigeon Guillemot | 14 | (Lester & Rodstrom, 6/24/79, B, III) | 42 |
| Total | <u>64</u> | | |

029 Cannon Gulch to Stump Beach 38°35'30"N, 123°20'30"W

| | | | |
|-------------------|------------|--------------------------------------|----|
| Pelagic Cormorant | 124 | (Lester & Rodstrom, 6/24/79, B, II) | 42 |
| Pigeon Guillemot | 4 | (Lester & Rodstrom, 6/24/79, B, III) | 42 |
| Total | <u>128</u> | | |



Section from U.S.G.S.
1:24,000 scale map:

Plantation, Calif.



Km
0 1/2 1

030 Gerstle Cove to Stillwater Cove 38°33'N, 123°18'45"W

| | | | |
|-------------------|------------|-----------------------------------|----|
| Pelagic Cormorant | 86 | (Lester & Rodstrom,6/25/79,B,I) | 42 |
| Western Gull | 6 | (Lester & Rodstrom,6/25/79,B,III) | 42 |
| Pigeon Guillemot | 18 | (Lester & Rodstrom,6/25/79,B,III) | 42 |
| Total | <u>110</u> | | |

031 Bench Mark 125 to Timber Cove 38°32'20"N, 123°17'W

| | | | |
|-------------------|-----------|---------------------------------|----|
| Pelagic Cormorant | 74 | (Lester & Rodstrom,6/25/79,B,I) | 42 |
| Western Gull | 2 | (Lester & Rodstrom,6/25/79,B,I) | 42 |
| Total | <u>76</u> | | |



032 "Northwest Cape Rocks" 38°30'40"N, 123°15'17"W



| | | | |
|-------------------|-----------|--------------------------------------|----|
| Pelagic Cormorant | 20 | (Lester & Rodstrom, 6/25/79, B, II) | 42 |
| Western Gull | 28 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Total | <u>48</u> | | |

033 "Russian Gulch" 38°28'N, 123°09'36"W

| | | | |
|---------------------|------------|--------------------------------------|----|
| Pelagic Cormorant | 336 | (Lester & Rodstrom, 6/25/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Western Gull | 10 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Pigeon Guillemot | 60 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Total | <u>408</u> | | |



Section from U.S.G.S.
1:24,000 scale map:

Plantation, Calif.



Section from U.S.G.S.
1:24,000 scale map:

Arched Rock, Calif.



(034) "Peaked Hill" 38°25'45"N, 123°07'10"W


| | | | |
|---------------------|------------|--------------------------------------|----|
| Pelagic Cormorant | 156 | (Lester & Rodstrom, 6/25/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/25/79, B, II) | 42 |
| Western Gull | 20 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Pigeon Guillemot | 80 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Total | <u>258</u> | | |

(035) Gull Rock 38°25'30"N, 123°07'10"W

| | | | |
|--------------------|------------|--------------------------------------|----|
| Brandt's Cormorant | 650 | (Lester & Sows, 7/23/80, A, II) | 42 |
| Pelagic Cormorant | 16 | (Lester & Rodstrom, 6/25/79, B, II) | 42 |
| Western Gull | 28 | (DeGange, 6/10/80, M, III) | 42 |
| Pigeon Guillemot | 40 | (DeGange, 6/10/80, M, III) | 42 |
| Total | <u>734</u> | | |
| Brandt's Cormorant | 300 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Western Gull | 20 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |

(036) Shell-Wright Beach Rocks 38°25'N, 123°06"W


| | | | |
|---------------------|------------|--------------------------------------|----|
| Pelagic Cormorant | 112 | (Lester & Rodstrom, 6/25/79, B, I) | 42 |
| Black Oystercatcher | 6 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Western Gull | 80 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Pigeon Guillemot | 8 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Total | <u>206</u> | | |




037

Duncan Point to Arched Rock 38°22'30"N, 123°05"W

| | | | |
|---------------------|-----------|-----------------------------------|----|
| Pelagic Cormorant | 70 | (Lester & Rodstrom,6/25/79,B,II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom,6/25/79,B,III) | 42 |
| Western Gull | 16 | (Lester & Rodstrom,6/25/79,B,III) | 42 |
| Pigeon Guillemot | 4 | (Lester & Rodstrom,6/25/79,B,III) | 42 |
| Total | <u>92</u> | | |



Section from U.S.G.S.
1:24,000 scale map:
Duncan Mills &
Bodega Head, Calif.
Km
0 1/2 1



038 Bodega Head 38°18'N, 123°03'45"W

| | | | |
|---------------------|------------|--------------------------------------|----|
| Pelagic Cormorant | 168 | (Lester & Rodstrom, 6/25/79, B, II) | 42 |
| Black Oystercatcher | 6 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Pigeon Guillemot | 60 | (Lester & Rodstrom, 6/25/79, B, III) | 42 |
| Total | <u>234</u> | | |

(039) Pinnacle Rock 38°18'20"N, 123°01'10"W

| | | | |
|---------------------|-----------|--------------------------------------|----|
| Pelagic Cormorant | 4 | (Lester & Rodstrom, 6/26/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 6/26/79, B, III) | 42 |
| Western Gull | 2 | (Lester & Rodstrom, 6/26/79, B, II) | 42 |
| Pigeon Guillemot | <u>30</u> | (Lester & Rodstrom, 6/26/79, B, III) | 42 |
| Total | 38 | | |

(040) "Sonoma-Marin County Line" 38°17'20"N, 123°00'20"W



| | | | |
|---------------------|-----------|--------------------------------------|----|
| Brandt's Cormorant | 12 | (Lester & Sows, 7/23/80, A, II) | 42 |
| Pelagic Cormorant | 134 | (Lester & Rodstrom, 6/26/79, B, II) | 42 |
| Black Oystercatcher | 4 | (Lester & Rodstrom, 6/26/79, B, III) | 42 |
| Western Gull | 16 | (Lester & Rodstrom, 6/26/79, B, III) | 42 |
| Pigeon Guillemot | <u>40</u> | (Lester & Rodstrom, 6/26/79, B, III) | 42 |
| Total | 206 | | |

(041) "Elephant Rock Complex" 38°11'N, 122°58'W

| | | | |
|-------------------|-----------|-------------------------------------|----|
| Pelagic Cormorant | 16 | (Lester & Rodstrom, 7/1/79, B, III) | 42 |
| Pigeon Guillemot | <u>12</u> | (Lester & Rodstrom, 7/1/79, B, III) | 42 |
| Total | 28 | | |



Section from U.S.G.S.
1:24,000 scale map:

Bodega Head, Calif.





Section from U.S.G.S.
1:24,000 scale map:

Valley Ford, Calif.



Section from U.S.G.S.
1:24,000 scale map:

Tomales, Calif.





429

San Francisco

The map on the facing page is an index to the locations of colonies within map 545, San Francisco. Note that all colonies on the map are not numbered consecutively from north to south, since many previously unreported colonies have been added since initial colony numbers were assigned by Varoujean (1979). On the pages following this map, all colonies are listed sequentially and a detailed map of each is provided.


Numbers of breeding seabirds will vary from year to year. Below are the approximate numbers of breeding seabirds within this region. Most of these birds are at the Farallon Islands (429 012).


| | |
|------------------------------------|---------|
| Leach's Storm-Petrel | 1,400 |
| Ashy Storm-Petrel | 4,000 |
| Brandt's Cormorant | 31,000 |
| Double-crested Cormorant | 2,000* |
| Pelagic Cormorant | 4,000 |
| Black Oystercatcher | 100 |
| Western Gull | 34,000 |
| Common Murre | 100,000 |
| Pigeon Guillemot | 4,500 |
| Marbled Murrelet | X |
| Cassin's Auklet | 105,000 |
| Rhinoceros Auklet | 100 |
| Tufted Puffin | 100 |

*coastal population only.

X = present

429 San Francisco






(001) Point Reyes 37°59'26"N, 123°59'24"W

| | | | |
|---------------------|---------------|--|----|
| Brandt's Cormorant | 2,400 | (Lester & Rodstrom, 7/1/79, B, 7/11/79, AM, III) | 42 |
| Pelagic Cormorant | 808 | (Lester & Rodstrom, 7/1/79, B, 7/11/79, M, III) | 42 |
| Black Oystercatcher | 10 | (Lester & Rodstrom, 7/1/79, B, 7/11/79, M, III) | 42 |
| Western Gull | 62 | (Lester & Rodstrom, 7/1/79, B, 7/11/79, M, III) | 42 |
| Common Murre | 16,500 | △ (Lester & Rodstrom, 7/1/79, B, 7/11/79, AM, III) | 42 |
| Pigeon Guillemot | 120 | (Lester & Rodstrom, 7/1/79, B, 7/11/79, M, III) | 42 |
| Tufted Puffin | 6 | (LeValley, 1975-80, L) | 32 |
| Total | 19,906 | | |
| Brandt's Cormorant | 960 | (Ainley & Whitt, 7/3/72, B) | 3 |
| Pelagic Cormorant | 528 | (Ainley & Whitt, 7/3/72, B) | 3 |
| Black Oystercatcher | 6 | (Ainley & Whitt, 7/3/72, B) | 3 |
| Western Gull | 26 | (Ainley & Whitt, 7/3/72, B) | 3 |
| Common Murre | 7,640 | (Ainley & Whitt, 7/3/72, B) | 3 |
| Pigeon Guillemot | 48 | (Ainley & Whitt, 7/3/72, B) | 3 |

△ Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/2/80 aerial survey (also times 1.67) is 22,000.



(002) Millers Point Rocks 37°58'53"N, 122°48'35"W

| | | | |
|--------------------|-----|---|----|
| Brandt's Cormorant | 194 | (Nelson & SOWls, 6/24/80, A, III) | 42 |
| Pelagic Cormorant | 60 | (Lester & Rodstrom, 7/2/79, B, II) | 42 |
| Western Gull | 34 | (Lester & Rodstrom, 7/2/79, B, III) | 42 |
| Pigeon Guillemot | 10 | (Lester & Rodstrom, 7/2/79, B, III) | 42 |
| Total | 298 | | |
| Brandt's Cormorant | 120 | (Lester & Rodstrom, 7/2/79, B, 7/11/79, A, III) | 42 |
| Brandt's Cormorant | 30 | (Osborne, 1970, M) | 36 |
| Pelagic Cormorant | 10 | (Osborne, 1970, M) | 36 |

(003) Double Point Rocks 37°56'51"N, 122°47'08"W

| | | | |
|---------------------|----------------------|---|----|
| Brandt's Cormorant | 258 | (Lester & Rodstrom, 7/2/79, B, 7/11/79, A, III) | 42 |
| Pelagic Cormorant | 16 | (Lester & Rodstrom, 7/2/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Osborne, 1970, M) | 36 |
| Western Gull | 24 | (Lester & Rodstrom, 7/2/79, B, III) | 42 |
| Common Murre | 13,000 ^{Δ1} | (Nelson & SOWls, 6/24/80, A, III) | 42 |
| Pigeon Guillemot | 40 | (Lester & Rodstrom, 7/2/79, B, III) | 42 |
| Total | 13,340 | | |
| Brandt's Cormorant | 340 | (Osborne, 1970, M) | 36 |
| Western Gull | 100 | (Osborne, 1970, M) | 36 |
| Common Murre | 1,400 | (Osborne, 1970, M) | 36 |

^{Δ1} Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/1/80 aerial survey (also times 1.67) is 13,900.

(004) Bolinas Lagoon was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).

(005) San Pablo Creek was previously assigned a catalog number because of California Clapper Rail nesting. We have not included information on this species in this report. See Gould (1973).

(006) Corte Madera Marsh was previously assigned a catalog number because of California Clapper Rail nesting. We have not included information on this species in this report. See Gould (1973).

AREA 429, San Francisco (cont'd.)

(007) Bird Island 37°49'27"N, 122°32'09"W

| | | | |
|--------------------|----------|-------------------------------------|----|
| Brandt's Cormorant | 0 | (Lester & Rodstrom, 7/3/79, B, I) | 42 |
| Western Gull | 2 | (Lester & Rodstrom, 7/3/79, B, II) | 42 |
| Pigeon Guillemot | 4 | (Lester & Rodstrom, 7/3/79, B, III) | 42 |
| Total | <u>6</u> | | |
| Brandt's Cormorant | 75 | (Osborne, 8/19/69, M) | 36 |
| Pigeon Guillemot | 2 | (Osborne, 8/19/69, M) | 36 |

(008) Point Bonita 37°48'55"N, 122°31'40"W

| | | | |
|-------------------|-----------|------------------------------------|----|
| Pelagic Cormorant | 60 | (Lester & Rodstrom, 7/3/79, B, II) | 42 |
| Western Gull | 4 | (Lester & Rodstrom, 7/3/79, B, II) | 42 |
| Pigeon Guillemot | X | (Lester & Rodstrom, 7/3/79, B) | 42 |
| Total | <u>64</u> | | |
| Pelagic Cormorant | 50 | (Reynolds, 8/19/69, M) | 36 |

X = present

(009) Seal Rocks 37°46'42"N, 122°30'53"W


The Seal Rocks colony is an excellent location to see seabirds, particularly Brown Pelicans, even though there are few nesting birds here. California Sea lions can also be observed. See appendix B.

| | | | |
|---------------------|-----------|---|----|
| Brandt's Cormorant | 0 | (Nelson & Sows, 6/24/80, A, I) | 42 |
| Black Oystercatcher | 2 | (Nelson & Nelson, 5/25/79, M, 7/1/79, B, II) | 42 |
| Western Gull | 44 | (Nelson & Nelson, 5/25/79, M, 7/1/79, B, III) | 42 |
| Pigeon Guillemot | 6 | (Nelson & Nelson, 5/25/79, M, 7/1/79, B, III) | 42 |
| Total | <u>52</u> | | |
| Brandt's Cormorant | 76 | (Nelson & Nelson, 5/25/79, M, 7/1/79, B, III) | 42 |
| Western Gull | 24 | (Reynolds, 7/21/70, M) | 36 |

(010) Alameda Naval Air Station 37°47'12"N, 122°19'49"W

No map is provided for this site in San Francisco Bay. For the most current information contact the California Department of Fish and Game. Least Terns are an endangered species. Populations of Least Terns are surveyed annually.

| | | | |
|------------|-----|----------------------------|----|
| Least Tern | 80 | (, 1979, L) | 12 |
| Least Tern | 160 | (Erickson, 1978, L) | 12 |
| Least Tern | 90 | (Atwood et al., 5/6/77, L) | 12 |



011 Oakland International Airport 37°43'21"N, 122°13'46"

No map is provided for this site in San Francisco Bay. For the most current information contact the California Department of Fish and Game. Least Terns are an endangered species. Populations of Least Terns are surveyed annually.

| | | |
|------------|-----------------------|----|
| Least Tern | 0 (Erickson, 1978, L) | 12 |
| Least Tern | 14 (Atwood, 1977, L) | 12 |

012 Farallon Islands 37°41'53"N, 123°00'05"W

The Farallon Islands constitute the most important area for nesting seabirds on the California coast. Together they contain the largest breeding populations of Ashy Storm-Petrels, Brandt's Cormorants, and Western Gulls in the world and a large percentage of many other California breeding seabirds (Figure 4). The importance of these islands to marine birds and mammals cannot be overemphasized.


Uncontrolled exploitation in the past of marine mammals and seabirds on the Farallon Islands led to drastic population declines. Russian and American sealers exterminated the Farallon populations of elephant seals (*Mirounga angustirostris*), fur seals (*Arctocephalus philippi*), and sea otters (*Enhydra lutris*). Seabird eggs were collected commercially during the gold rush and were sold as food. Well over 14 million murre eggs alone were taken over a 45-year period and murre numbers declined from about 400,000 in 1860 to less than 5,000 in 1924 (Ainley and Lewis, 1974). For a thorough review of this history read Ainley and Lewis, 1974.

Today the Farallon Islands are protected as a National Wildlife Refuge and all waters within one mile of the islands make up a state refuge. Most marine mammal and seabird populations are increasing dramatically in numbers and eventual full recovery seems possible. Longterm scientific research on marine mammals and seabirds is being conducted by Point Reyes Bird Observatory (PRBO). Only through such studies can we hope to understand and protect these magnificent resources.

| | | | |
|--------------------------|---------|------------------------|----|
| Leach's Storm-Petrel | 1,400 | (Ainley & Lewis, 1972) | 2 |
| Ashy Storm-Petrel | 4,000 | (Ainley & Lewis, 1972) | 2 |
| Brandt's Cormorant | 28,000 | (PRBO Staff, 1979) | 1 |
| Double-crested Cormorant | 180 | (PRBO Staff, 1979) | 1 |
| Pelagic Cormorant | 2,000 | (Ainley & Lewis, 1972) | 2 |
| Black Oystercatcher | 40 | (Ainley & Lewis, 1972) | 2 |
| Western Gull | 32,000 | (PRBO Staff, 1979) | 1 |
| Common Murre | 60,000 | △ (PRBO Staff, 1979) | 1 |
| Pigeon Guillemot | 3,000 | (PRBO Staff, 1979) | 1 |
| Cassin's Auklet | 105,000 | (Manuwal, 1971) | 33 |
| Rhinoceros Auklet | 100 | (PRBO Staff, 1979) | 2 |
| Tufted Puffin | 100 | (PRBO Staff, 1979) | 2 |
| Total | 236,320 | | |

For a thorough review of historical data see Ainley and Lewis, 1974.

△ Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/2/80 aerial survey (also times 1.67) is 138,500. PRBO estimates do not include North Farallon.





Southeast Farallon Island

U.S.F.W.S. photo



Southeast Farallon Island

Photo by Bill Parsons

(013) San Pedro Rock 37°35'43"N, 122°31'20"W

| | | | |
|---------------------|----|--|----|
| Brandt's Cormorant | 0 | (Nelson, Sows & Stuart, 6/9/79, BL, I) | 42 |
| Pelagic Cormorant | 8 | (Nelson, Sows & Stuart, 6/9/79, BL, I) | 42 |
| Black Oystercatcher | 2 | (Nelson, Sows & Stuart, 6/9/79, BL, II) | 42 |
| Western Gull | 8 | (Nelson, Sows & Stuart, 6/9/79, BL, I) | 42 |
| Pigeon Guillemot | 40 | (Nelson, Sows & Stuart, 6/9/79, BL, III) | 42 |
| Total | 58 | | |
| Cormorant (unid.) | 50 | (Reynolds, 7/21/70, A) | 36 |

(014) Devil's Slide Rock 37°34'28"N, 122°31'39"W

| | | | |
|---------------------|-------|---|----|
| Brandt's Cormorant | 22 | (Nelson, Sows & Stuart, 6/9/79, B, 6/30/79, M, II) | 42 |
| Pelagic Cormorant | 180 | (Nelson, Sows & Stuart, 6/9/79, B, 6/30/79, M, III) | 42 |
| Black Oystercatcher | 4 | (Nelson, Sows & Stuart, 6/9/79, B, 6/30/79, M, II) | 42 |
| Western Gull | 2 | (Nelson, Sows & Stuart, 6/9/79, B, 6/30/79, M, II) | 42 |
| Common Murre | 2,300 | (Nelson & Sows, 6/30/79, M, 7/6/79, A, III) | 42 |
| Pigeon Guillemot | 120 | (Nelson, Sows & Stuart, 6/9/79, B, 6/30/79, M, III) | 42 |
| Total | 2,628 | | |
| Common Murre | 700 | (Reynolds, 7/21/70, M) | 36 |
| Pigeon Guillemot | 2 | (Reynolds, 7/21/70, M) | 36 |

△ Estimate is number of birds present times 1.67, see page 10. Briggs et al.'s estimate for 7/1/80 aerial survey (also times 1.67) is 2,900!

(015) Alameda Creek 37°36'59"N, 122°07'20"W

No map is provided for this site in San Francisco Bay.

| | | | |
|----------------|-----|-------------------|----|
| Forster's Tern | 200 | (Sibley, 5/28/48) | 43 |
|----------------|-----|-------------------|----|

(016) Bair Island 37°31'43"N, 122°13'05"W


No map is provided for this site in San Francisco Bay. For the most current information contact the California Department of Fish and Game. Least Terns are an endangered species. Populations of Least Terns are surveyed annually.

| | | | |
|------------|---|-------------------------|----|
| Least Tern | 8 | (Erickson, 1979, L) | 12 |
| Least Tern | 2 | (Atwood et al., 5-6/77) | 12 |

(017) Coyote Hills 37°32'48"N, 122°07'28"W

No map is provided for this site in San Francisco Bay. For the most current information contact the California Department of Fish and Game. Least Terns are an endangered species. Populations of Least Terns are surveyed annually.

| | | | |
|----------------|-----|----------------|----|
| Forster's Tern | 614 | (Gill, 4-8/71) | 43 |
| Least Tern | 80 | (Gill, 4-8/71) | 43 |
| Total | 694 | | |



(018) Greco Island was previously assigned a catalog number because of California Clapper Rail and Snowy Plover nesting. We have not included data on these species in this report. See Gill (1972) and Page Stenzel (1979).

(019) Coyote Creek 37°28'41"N, 122°02'51"W

No map is provided for this site in San Francisco Bay. For further information see Gill (1972).

| | | | |
|--------------|-----|----------------|----|
| Caspian Tern | 400 | (Gill, 4-8/71) | 43 |
|--------------|-----|----------------|----|

(020) Guadalupe Slough 37°28'12"N, 122°04'52"W

No map is provided for this site in San Francisco Bay. For further information see Gill (1972).

| | | | |
|----------------|-------|----------------|----|
| Forster's Tern | 1,256 | (Gill, 4-8/71) | 43 |
|----------------|-------|----------------|----|

(021) Pescadero Creek was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).

(022) Punta del Año Nuevo 37°07'07"N, 122°20'09"W

| | | | |
|-------------------|------------|------------------------------------|----|
| Pelagic Cormorant | 210 | (Lester & Nelson, 6/13/80, B, II) | 42 |
| Pigeon Guillemot | 70 | (Lester & Nelson, 6/13/80, B, III) | 42 |
| Total | <u>280</u> | | |
| Pelagic Cormorant | 200 | (Nelson & Lester, 7/5/79, B, II) | 42 |


(023) Año Nuevo Island 37°06'30"N, 122°20'09"W

| | | | |
|---------------------|------------|-------------------|----|
| Pelagic Cormorant | 10 | (Briggs, 1976, L) | 43 |
| Black Oystercatcher | 24 | (Briggs, 1976, L) | 43 |
| Western Gull | 240 | (Briggs, 1976, L) | 43 |
| Pigeon Guillemot | 64 | (Briggs, 1976, L) | 43 |
| Total | <u>338</u> | | |



Pelagic Cormorants, Punta del Año Nuevo

Photo by Art SOWLS



024 Point Resistance 37°59'55"N, 122°49'40"W

| | | | |
|---------------------|--------------|-------------------------------------|----|
| Brandt's Cormorant | 150 | (Rodstrom, 7/11/79, A, III) | 42 |
| Pelagic Cormorant | 104 | (Lester & Rodstrom, 7/2/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 7/2/79, B, III) | 42 |
| Western Gull | 20 | (Lester & Rodstrom, 7/2/79, B, III) | 42 |
| Common Murre | 7,500 | △ (Nelson & Sows, 6/24/80, A, III) | 42 |
| Pigeon Guillemot | 60 | (Lester & Rodstrom, 7/2/79, B, III) | 42 |
| Total | <u>7,836</u> | | |
| Common Murre | 400 | (Osborne, 1970, M) | 36 |

△ Estimate is number of birds present times 1.67, see page 20. Briggs et al.'s estimate for 7/1/80 aerial survey (also times 1.67) is 6,800.





Point Resistance Rock

Photo by Jay Nelson

025 Gull Rock Area 37°52'35"N, 122°37'W

| | | | |
|---------------------|-----------|-------------------------------------|----|
| Pelagic Cormorant | 28 | (Lester & Rodstrom, 7/3/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 7/3/79, B, III) | 42 |
| Western Gull | 4 | (Lester & Rodstrom, 7/3/79, B, III) | 42 |
| Pigeon Guillemot | 2 | (Lester & Rodstrom, 7/3/79, B, III) | 42 |
| Total | <u>36</u> | | |





026 Muir Beach Headlands to Tennessee Cove 37°51'00"N, 122°33'45"W

| | | | |
|---------------------|-----------|------------------------------------|----|
| Pelagic Cormorant | 34 | (Lester & Rodstrom, 7/3/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Rodstrom, 7/3/79, B, II) | 42 |
| Pigeon Guillemot | X | (Lester & Rodstrom, 7/3/79, B, II) | 42 |
| Total | <u>36</u> | | |

027 Bonita Cove 37°49'30"N, 122°31'W

| | | | |
|-------------------|-----------|------------------------------------|----|
| Pelagic Cormorant | 20 | (Lester & Rodstrom, 7/3/79, B, II) | 42 |
| Western Gull | 2 | (Lester & Rodstrom, 7/3/79, B, I) | 42 |
| Pigeon Guillemot | X | (Lester & Rodstrom, 7/3/79, B) | 42 |
| Total | <u>22</u> | | |

X = present



(028) Point Diablo Bluffs and Needles 37°49'30"N, 122°29'W

| | | | |
|-------------------|-----------|------------------------------------|----|
| Pelagic Cormorant | 64 | (Lester & Rodstrom, 7/3/79, B, II) | 42 |
| Western Gull | 16 | (Lester & Rodstrom, 7/3/79, B, II) | 42 |
| Pigeon Guillemot | X | (Lester & Rodstrom, 7/3/79, B) | 42 |
| Total | <u>80</u> | | |

X = present


(029) Lobos Rock and Lands End 37°47'15"N, 122°30'20"W

| | | | |
|--------------------|------------|-----------------------------------|----|
| Brandt's Cormorant | 80 | (Nelson & Sows, 6/24/80, A, II) | 42 |
| Western Gull | 12 | (Nelson & Nelson, 7/1/79, B, III) | 42 |
| Pigeon Guillemot | 68 | (Nelson & Nelson, 7/1/79, B, III) | 42 |
| Total | <u>160</u> | | 42 |
| Brandt's Cormorant | 0 | (Nelson & Nelson, 7/1/79, B, I) | 42 |




Lobos Rock

Photo by Jay Nelson




Section from U.S.G.S.
 1:24,000 scale map:
 San Francisco North
 & Pt. Bonita, Calif.





030 Pillar Point 37°23'N, 122°29'55"W

| | | | |
|-------------------|-----------|---|----|
| Pelagic Cormorant | 16 | (Nelson, Sows & Stuart, 6/9/79, B, II) | 42 |
| Pigeon Guillemot | 6 | (Nelson, Sows & Stuart, 6/9/79, B, III) | 42 |
| Total | <u>22</u> | | |
| Pelagic Cormorant | 0 | (Reynolds, 1970) | 36 |



Section from U.S.G.S.
 1:24,000 scale map:
**Half Moon Bay &
 Montara Mt., Calif.**

Km
 0 1/2 1

031 Eel Rock Cliffs 37°24'15"N, 122°25'30"W

| | | | |
|-------------------|-----------|---|----|
| Pelagic Cormorant | 12 | (Lester & Nelson, 6/13/80, B, I) | 42 |
| Pigeon Guillemot | P | (Nelson, SOWls & Stuart, 6/9/79, B) | 42 |
| Total | <u>12</u> | | |
| Pelagic Cormorant | 14 | (Nelson, SOWls & Stuart, 6/9/79, B, II) | 42 |


032 Seal Rock Cliffs 37°23'N, 122°25'W

| | | | |
|---------------------|------------|--|----|
| Brandt's Cormorant | 50 | (Lester & Nelson, 6/13/80, B, II) | 42 |
| Pelagic Cormorant | 108 | (Lester & Nelson, 6/13/80, B, II) | 42 |
| Black Oystercatcher | 4 | (Lester & Nelson, 6/13/80, B, III) | 42 |
| Pigeon Guillemot | 10 | (Lester & Nelson, 6/13/80, B, II) | 42 |
| Total | <u>172</u> | | |
| Pelagic Cormorant | 168 | (Nelson, SOWls & Stuart, 6/9/79, B, II) | 42 |
| Black Oystercatcher | P | (Nelson, SOWls & Stuart, 6/9/79, B) | 42 |
| Pigeon Guillemot | 10 | (Nelson, SOWls & Stuart, 6/9/79, B, III) | 42 |

P = probably present


033 Martins Beach 37°22'N, 122°24'30"W

| | | | |
|---------------------|------------|------------------------------------|----|
| Brandt's Cormorant | 40 | (Lester & Nelson, 6/13/80, B, II) | 42 |
| Pelagic Cormorant | 100 | (Lester & Nelson, 6/13/80, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Nelson, 6/13/80, B, III) | 42 |
| Pigeon Guillemot | 120 | (Lester & Nelson, 6/13/80, B, III) | 42 |
| Total | <u>262</u> | | |
| Pelagic Cormorant | 152 | (Nelson & Lester, 7/5/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Nelson & Lester, 7/5/79, B, III) | 42 |



Section from U.S.G.S.
1:24,000 scale map:

Half Moon Bay &
San Gregorio, Calif.



$37^{\circ}22'30''$ +
 $122^{\circ}25'$

034 Pigeon Point 37°10'55"N, 122°23'20"W


| | | | |
|---------------------|----------|------------------------------------|----|
| Black Oystercatcher | 2 | (Lester & Nelson, 7/5/79, BM, I) | 42 |
| Pigeon Guillemot | 6 | (Lester & Nelson, 7/5/79, BM, III) | 42 |
| Total | <u>8</u> | | |

035 Greyhound Rock 37°04'40"N, 122°16'W to
Davenport 37°00'30"N 122°11'30"W


No map is provided for this site as it extends along a lengthy stretch of coastline.

| | | | |
|---------------------|------------|-----------------------------------|----|
| Brandt's Cormorant | 236 | △ (Nelson, 7/14/80, M, II) | 42 |
| Pelagic Cormorant | 50 | (Lester & Nelson, 7/5/79, B, II) | 42 |
| Black Oystercatcher | 6 | (Lester & Nelson, 7/5/79, B, IV) | 42 |
| Pigeon Guillemot | 400 | (Lester & Nelson, 7/5/79, B, III) | 42 |
| Total | <u>682</u> | | |

△ all on pier at Davenport.



Section from U.S.G.S.
1:24,000 scale map:
Pigeon Point, Calif.



$37^{\circ}12'30''$
 $122^{\circ}25'$

034

(036) Alcatraz Island 37°49'34"N, 122°25'20"W

| | | | |
|-----------------|---|-----------------|----|
| Western Gull | X | (Abbore, 1980) | 15 |
| Heermann's Gull | 2 | (Binford, 1980) | 8 |



(037) Pier 45 37°48'34"N, 122°25'W

| | | | |
|--------------|---|-------------------|----|
| Western Gull | X | (Danielson, 1973) | 15 |
|--------------|---|-------------------|----|

(038) Yerba Buena Island 37°48'34"N, 122°22'15"W

| | | | |
|--------------|----|---------------------|----|
| Western Gull | 80 | (Cogswell, 7/28/74) | 15 |
| Western Gull | X | (Cogswell, 1967) | 15 |

X = present



039 Red Rock 37°55'45"N, 122°25'50"W

| | | | |
|--------------|-----|--|----|
| Western Gull | 92+ | (Cogswell, 5/20/70, L) | 15 |
| Western Gull | X | (Cogswell, 1960, 1969, 1971, 1976, 1978) | 15 |



040 The Brothers 37°57'47"N, 122°26'W

| | | | |
|--------------|----|------------------------------------|----|
| Western Gull | 80 | (Cogswell, 6/22/67, M) | 15 |
| Western Gull | X | (Cogswell, 1968-71, 1973, 1975-76) | 15 |

X = present

041 The Sisters 37°59'22" N, 122°26'25"

| | | | |
|--------------|-----|---------------------|----|
| Western Gull | 40+ | (Cogswell, 6/13/75) | 15 |
|--------------|-----|---------------------|----|





454

Monterey


The map on the facing page is an index to the locations of colonies within map 454, Monterey. Note that all colonies on the map are not numbered consecutively from north to south, since many previously unreported colonies have been added since initial colony numbers were assigned by Varoujean (1979). On the pages following this map, all colonies are listed sequentially and a detailed map of each is provided.


Numbers of breeding seabirds will vary from year to year. Below are the approximate numbers of breeding seabirds within this region.

| | |
|------------------------------------|-------|
| Brandt's Cormorant | 8,000 |
| Double-crested Cormorant | X |
| Pelagic Cormorant | 800 |
| Black Oystercatcher | .60 |
| Western Gull | 900 |
| Common Murre | 6,000 |
| Pigeon Guillemot | 2,600 |
| Marbled Murrelet | P |
| Tufted Puffin | 2 |

P = probably present

454 Monterey





001 Wilder Creek was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).


002 Pajaro River was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).

003 Elkhorn Slough 36°49'04"N, 121°46'30"W

| | | | |
|----------------|---------|---------------------------------|----|
| Western Gull | 122 | (Harvey, 1980, L) | 26 |
| Forster's Tern | 95 | (Harvey, 1980, L) | 26 |
| Caspian Tern | 180 | (Harvey, 1980, L) | 26 |
| Total | 397 | | |
| Western Gull | 74 | (Varoujean et al., 5-8/1972, L) | 43 |
| Western Gull | 110 | (Harvey, 1978, L) | 26 |
| Western Gull | 102 | (Harvey, 1979, L) | 26 |
| Forster's Tern | 165 | (Harvey, 1978, L) | 26 |
| Forster's Tern | 550-600 | (Harvey, 5/25/79, L) | 26 |
| Caspian Tern | 170 | (Harvey, 1978, L) | 26 |
| Caspian Tern | 160-180 | (Harvey, 1979, L) | 26 |

004 Salinas River Beach was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).

005 Marina Beach was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).



(006) Bird Rock 36°35'31"N, 121°57'59"W

Bird Rock offers excellent viewing opportunities for seabirds, sea lions and harbor seals. See appendix B.

| | | | |
|---------------------|--------------|--------------------------------|----|
| Brandt's Cormorant | 1,340 | (Nelson & SOWls,6/23/80,A,II) | 42 |
| Black Oystercatcher | 2 | (Nelson & SOWls,6/10/79,M,II) | 42 |
| Western Gull | 10 | (Nelson & SOWls,6/10/79,M,III) | 42 |
| Total | <u>1,352</u> | | |
| Brandt's Cormorant | 2,000 | (Nelson & SOWls,7/6/79,A,III) | 42 |
| Brandt's Cormorant | 600 | (Reynolds,7/15/70,A) | 36 |





Bird Rock

Photo by Art SOWls

(007) Pinnacle Point Area 36°31'25"N, 121°57'14"W

| | | | |
|---------------------|------------|--|----|
| Brandt's Cormorant | 200 | (Nelson & SOWls,6/11/79,B,7/31&8/3/79,L,III) | 42 |
| Pelagic Cormorant | 22 | (Nelson & SOWls,6/11/79,B,7/31&8/3/79,L,II) | 42 |
| Black Oystercatcher | P | (Nelson & SOWls,6/11/79,B,7/31&8/3/79,L,II) | 42 |
| Western Gull | 14 | (Nelson & SOWls,6/11/7/13&8/3/79,B,L,III) | 42 |
| Pigeon Guillemot | 100 | (Nelson & SOWls,6/11/79,B,7/31&8/3/79,L,III) | 42 |
| Total | <u>336</u> | | |
| Brandt's Cormorant | 125 | (Varoujean & Briggs,4/25&7/14/72,M) | 43 |
| Brandt's Cormorant | 30 | (Reynolds,5/6/70,M) | 36 |
| Pelagic Cormorant | 30 | (Reynolds,5/6/70,M) | 36 |
| Black Oystercatcher | 2 | (Reynolds,5/6/70,M) | 36 |
| Western Gull | 25 | (Reynolds,5/6/70,M) | 36 |
| Pigeon Guillemot | 2 | (Reynolds,5/6/70,M) | 36 |

P = probably present



008 Sand Hill Cove 36°31'01"N, 121°57'01"W


| | | | |
|---------------------|----|---------------------------------------|----|
| Pelagic Cormorant | 36 | (Nelson & Sows, 8/2/79, L, I) | 42 |
| Black Oystercatcher | 2 | (Nelson & Sows, 8/2/79, L, III) | 42 |
| Western Gull | 2 | (Nelson & Sows, 6/24/80, L, II) | 42 |
| Pigeon Guillemot | 20 | (Nelson & Sows, 6/24/80, L, III) | 42 |
| Total | 58 | | |
| Pelagic Cormorant | 36 | (Briggs & Varoujean, 4/25&7/14/72, L) | 43 |
| Pelagic Cormorant | 26 | (Nelson & Sows, 6/24/80, L, II) | 42 |
| Pigeon Guillemot | 12 | (Briggs & Veroujean, 4/25&7/14/72, L) | 43 |

009 Bird Island 36°30'25"N, 121°56'33"W

Bird Island is the second largest Brandt's Cormorant colony in California, after the Farallon Islands (429 012). It is also the most northern site for nesting Brown Pelicans ever recorded, although no nesting pelicans have been observed here since 1963 (Baldrige, 1973). If recovery of the Brown Pelican continues, this site may be recolonized. Bird Island offers excellent viewing opportunities (see appendix B).

| | | | |
|---------------------|-------|--|----|
| Brandt's Cormorant | 4,200 | (Nelson & Sows, 6/23/80, A, II) | 42 |
| Pelagic Cormorant | 16 | (Nelson & Sows, 8/2/79, L, III) | 42 |
| Black Oystercatcher | 4 | (Nelson & Sows, 6/11/79, B, 6/12/79, L, III) | 42 |
| Western Gull | 46 | (Nelson & Sows, 6/11/79, B, III) | 42 |
| Pigeon Guillemot | 4 | (Nelson & Sows, 6/24/80, M, III) | 42 |
| Total | 4,270 | | |
| Brown Pelican | 0-110 | (1927-1963; see Baldrige 1973) | 7 |
| Brandt's Cormorant | 800 | (Reynolds, 5/6/69, M) | 36 |
| Brandt's Cormorant | 1,568 | (Briggs & Varoujean, 4/25&7/14/72, M) | 43 |
| Brandt's Cormorant | 6,000 | (Nelson & Sows, 7/6/79, A, III) | 42 |
| Black Oystercatcher | 2 | (Briggs & Varoujean, 4/25&7/14/72, M) | 43 |
| Western Gull | X | (Briggs & Varoujean, 4/25&7/14/72, M) | 43 |
| Pigeon Guillemot | X | (Briggs & Varoujean, 4/25&7/14/72, M) | 43 |

X = present



Bird Island

Photo by Jay Nelson

010 Castle Rocks & Mainland 36°22'35"N, 121°54'25"W



| | | | |
|---------------------|-------|--|----|
| Brandt's Cormorant | 18 | (Lester, Nelson & SOWls,6/12/80,B,II) | 42 |
| Pelagic Cormorant | 96 | (Lester, Nelson & SOWls,6/12/80,B,II) | 42 |
| Black Oystercatcher | 6 | (Lester, Nelson & SOWls,6/12/80,B,III) | 42 |
| Western Gull | 78 | (Lester, Nelson & SOWls,6/12/80,B,III) | 42 |
| Common Murre | 3,500 | (Lester, Nelson & SOWls,6/12/80,B,III) | 42 |
| Pigeon Guillemot | 88 | (Nelson & SOWls,7/14/79,M,6/20&8/1/79,B,III) | 42 |
| Total | 3,780 | | |
| Brandt's Cormorant | 534 | (Nelson & SOWls,7/14/79,M,6/20&8/1/79,B,II) | 42 |
| Brandt's Cormorant | 300 | (Reynolds,5/6/70,M) | 36 |
| Pelagic Cormorant | 62 | (Nelson & SOWls,6/20&8/1/79,B,II) | 42 |
| Black Oystercatcher | 6 | (Nelson & SOWls,6/20/79,B,II) | 42 |
| Black Oystercatcher | 2 | (Reynolds,5/6/70,M) | 36 |
| Western Gull | 50 | (Nelson & SOWls,6/20&8/1/79,B,II) | 42 |
| Western Gull | 20 | (Reynolds,5/6/70,M) | 36 |
| Common Murre | 200 | (Reynolds,5/6/70,M) | 36 |
| Pigeon Guillemot | 2 | (Reynolds,5/6/70,M) | 36 |

011 Hurricane Point Rocks 36°21'40"N, 121°54'25"W

| | | | |
|---------------------|-------|---|----|
| Brandt's Cormorant | 444 | (Lester, Nelson & SOWls,6/12/80,B,III) | 42 |
| Pelagic Cormorant | 50 | (Lester, Nelson & SOWls,6/12/80,B,II) | 42 |
| Black Oystercatcher | 10 | (Lester, Nelson & SOWls,6/12/80,B,III) | 42 |
| Western Gull | 72 | (Lester, Nelson & SOWls,6/12/80,B,III) | 42 |
| Common Murre | 2,300 | (Lester, Nelson & SOWls,6/12/80,B,III) | 42 |
| Pigeon Guillemot | 80 | (Lester, Nelson & SOWls,6/12/80,B,III) | 42 |
| Tufted Puffin | 2 | (Lester, Nelson & SOWls,6/12/80,B,II) | 42 |
| Total | 2,958 | | |
| Brandt's Cormorant | 582 | (Nelson & SOWls,7/14/79,M,8/1/79,B,III) | 42 |
| Pelagic Cormorant | 10 | (Nelson & SOWls,7/14/79,M,8/1/79,B,II) | 42 |
| Western Gull | 50 | (Nelson & SOWls,7/14/79,M,8/1/79,B,III) | 42 |
| Common Murre | 400 | (Reynolds,5/6/70,M) | 36 |
| Pigeon Guillemot | 4 | (Nelson & SOWls,7/14/79,M,8/1/79,B,III) | 42 |

012 Point Sur 36°18'22"N, 121°53'39"W

| | | | |
|---------------------|----|--|----|
| Pelagic Cormorant | 54 | (Lester, Nelson & SOWls,6/12/80,B,II) | 42 |
| Black Oystercatcher | 2 | (Lester, Nelson & SOWls,6/12/80,B,III) | 42 |
| Western Gull | 6 | (Lester, Nelson & SOWls,6/12/80,B,III) | 42 |
| Pigeon Guillemot | 4 | (Nelson & SOWls,8/1/79,B,III) | 42 |
| Total | 66 | | |



013 "Torre Canyon Rocks" 36°11'25"N, 121°42'46"W


| | | | |
|---------------------|-----------|----------------------------------|----|
| Brandt's Cormorant | 0 | (Nelson & Sows, 6/22/79, B, I) | 42 |
| Pelagic Cormorant | 22 | (Nelson & Sows, 6/22/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Nelson & Sows, 6/22/79, B, III) | 42 |
| Total | <u>24</u> | | |
| Brandt's Cormorant | 125 | (Reynolds, 6/14/70, M) | 36 |

014 "Partington Ridge North" 36°10'06"N, 121°41'14"W

| | | | |
|--------------------------|--------------|--|----|
| Double-crested Cormorant | 6 | (Baldrige, 1980, M) | 6 |
| Brandt's Cormorant | 910 | (Nelson & Sows, 6/23/79, B, 7/13/79, M, III) | 42 |
| Pelagic Cormorant | 26 | (Nelson & Sows, 6/23/79, B, II) | 42 |
| Black Oystercatcher | 4 | (Nelson & Sows, 6/23/79, B, III) | 42 |
| Western Gull | 30 | (Nelson & Sows, 6/23/79, B, III) | 42 |
| Pigeon Guillemot | 80 | (Nelson & Sows, 6/23/79, B, III) | 42 |
| Total | <u>1,050</u> | | |
| Double-crested Cormorant | 0-10 | (Baldrige, 1963-79, M) | 6 |
| Brandt's Cormorant | 125 | (Reynolds, 5/14/70, M) | 36 |

015 McWay Rocks 36°09'46"N, 121°40'44"W

| | | | |
|---------------------|------------|----------------------------------|----|
| Brandt's Cormorant | 20 | (Nelson & Sows, 6/23/79, B, I) | 42 |
| Black Oystercatcher | 2 | (Nelson & Sows, 6/23/79, B, III) | 42 |
| Western Gull | 8 | (Nelson & Sows, 6/23/79, B, III) | 42 |
| Pigeon Guillemot | 100 | (Nelson & Sows, 6/23/79, B, III) | 42 |
| Total | <u>130</u> | | |
| Brandt's Cormorant | 80 | (Reynolds, 7/22/70, M) | 36 |



(016) "Anderson Canyon Rock" 36°06'58"N, 121°36'58"W

| | | | |
|--------------------|-----|---------------------------------|----|
| Brandt's Cormorant | 0 | (Nelson & Sows, 6/23/79, B, I) | 42 |
| Pelagic Cormorant | 82 | (Nelson & Sows, 6/23/79, B, II) | 42 |
| Total | 82 | | |
| Brandt's Cormorant | 284 | (Reynolds, 7/22/70, M) | 36 |

(017) "Burns Creek Rocks" 36°08'29"N, 121°39'28"W



| | | | |
|--------------------|-----|--|----|
| Cormorant (Unid.) | 2 | (Nelson & Sows, 6/23/79, B, 7/13/79, M) | 42 |
| Brandt's Cormorant | 348 | (Nelson & Sows, 6/23/79, B, 7/13/79, M, III) | 42 |
| Western Gull | 4 | (Nelson & Sows, 7/13/79, M, III) | 42 |
| Pigeon Guillemot | 24 | (Nelson & Sows, 7/13/79, M, III) | 42 |
| Total | 378 | | |
| Brandt's Cormorant | 60 | (Reynolds, 7/22/70, M) | 36 |

(018) Dolan Rock 36°05'06"N, 121°37'02"W

| | | | |
|--------------------|-----|---|----|
| Brandt's Cormorant | 0 | (Nelson & Sows, 7/23/79, B, 8/2/79, A, I) | 42 |
| Brandt's Cormorant | 100 | (Reynolds, 7/15/70, A) | 36 |

(019) Square Black Rock 36°04'21"N, 121°36'35"W

| | | | |
|--------------------|-------|---|----|
| Brandt's Cormorant | 0 | (Nelson & Sows, 6/23/80, A, I) | 42 |
| Brandt's Cormorant | 0 | (Nelson & Sows, 7/23/79, B, 8/2/79, A, I) | 42 |
| Brandt's Cormorant | 20-40 | (Reynolds, 7/15/70, A) | 36 |



②②① Lopez Rock 36°01'34"N, 121°34'46"W

| | | | |
|--------------------|-----|---|----|
| Brandt's Cormorant | 0 | (Nelson & Sows, 6/23/80, A, I) | 42 |
| Brandt's Cormorant | 0 | (Nelson & Sows, 7/23/79, B, 8/2/79, A, I) | 42 |
| Brandt's Cormorant | 100 | (Reynolds, 7/23/70, M) | 36 |

②②① Davenport 37°00'30"N, 122°11'30"W to
Pt. Santa Cruz 37°57'10"N, 122°01'15"

No map is provided for this site as it extends along a lengthy stretch of coastline. See page 213 .

| | | | |
|---------------------|-------|----------------------------------|----|
| Pelagic Cormorant | 28 | (Nelson & Sows, 7/15/79, B, I) | 42 |
| Black Oystercatcher | P | (Nelson & Sows, 7/15/79, B, I) | 42 |
| Western Gull | 2 | (Nelson & Sows, 7/15/79, B, II) | 42 |
| Pigeon Guillemot | 1,200 | (Nelson & Sows, 7/15/79, B, III) | 42 |
| Total | 1,230 | | |

P = probably present

②②② Pescadero Rock 36°33'43"N, 121°56'33"W

| | | | |
|---------------------|----|-----------------------------------|----|
| Black Oystercatcher | 2 | (Nelson & Sows, 6/11/79, BL, III) | 42 |
| Western Gull | 20 | (Nelson & Sows, 6/11/79, BL, I) | 42 |
| Total | 22 | | |


②②③ "Guillemot Island Area" 36°31'25"N, 121°56'47"W

| | | | |
|---------------------|-----|--|----|
| Pelagic Cormorant | 14 | (Nelson & Sows, 6/11/79, BL, 8/3/79, M, II) | 42 |
| Black Oystercatcher | 4 | (Nelson & Sows, 6/11/79, BL, II) | 42 |
| Western Gull | 60 | (Nelson & Sows, 6/11/79, BL, 8/3/79, M, II) | 42 |
| Pigeon Guillemot | 40 | (Nelson & Sows, 6/11/79, BL, 8/3/79, M, III) | 42 |
| Total | 118 | | |

Section from U.S.G.S.
1:24,000 scale map:

Lopez Pt., Calif.

Km
0 1/2 1



Section from U.S.G.S.
1:24,000 scale map:


Monterey, Calif.

Km
0 1/2 1

Section from U.S.G.S.
1:24,000 scale map:

Monterey, Calif.

Km
0 1/2 1



024 Yankee Point 36°29'29"N, 121°56'41"W

| | | | |
|------------------|----------|----------------------------------|----|
| Western Gull | 8 | (Nelson & Sows, 6/11/79, B, II) | 42 |
| Pigeon Guillemot | X | (Nelson & Sows, 6/11/79, B, III) | 42 |
| Total | <u>8</u> | | |

X = present,

025 Lobos Rocks 36°27'18"N, 121°56'10"W

| | | | |
|--------------|----|---------------------------------|----|
| Western Gull | 12 | (Nelson & Sows, 6/11/79, B, II) | 42 |
|--------------|----|---------------------------------|----|




Lobos Rocks

Photo by Art Sows

026 "Soberanes Creek Rocks" 36°27'18"N, 121°55'35"W

| | | | |
|-------------------|-----------|----------------------------------|----|
| Pelagic Cormorant | 30 | (Nelson & Sows, 6/11/79, B, I) | 42 |
| Western Gull | 4 | (Nelson & Sows, 7/17/79, M, II) | 42 |
| Pigeon Guillemot | 40 | (Nelson & Sows, 6/11/79, B, III) | 42 |
| Total | <u>74</u> | | |



(027) "Soberanes Point South" 36°26'47"N, 121°55'35"W



| | | | |
|---------------------|-----------|----------------------------------|----|
| Pelagic Cormorant | 2 | (Nelson & Sows, 6/11/79, B, I) | 42 |
| Black Oystercatcher | 4 | (Nelson & Sows, 6/11/79, B, III) | 42 |
| Western Gull | 6 | (Nelson & Sows, 6/11/79, B, III) | 42 |
| Total | <u>12</u> | | |

(028) Rocky Point 36°24'06"N, 121°54'40"W

| | | | |
|---------------------|-----------|----------------------------------|----|
| Pelagic Cormorant | 6 | (Nelson & Sows, 6/11/79, B, I) | 42 |
| Black Oystercatcher | 4 | (Nelson & Sows, 6/11/79, B, III) | 42 |
| Western Gull | 20 | (Nelson & Sows, 6/11/79, B, III) | 42 |
| Pigeon Guillemot | 40 | (Nelson & Sows, 6/11/79, B, III) | 42 |
| Total | <u>70</u> | | |

(029) "Bench Mark-227x" 36°23'21"N, 121°54'13"W

| | | | |
|---------------------|------------|---|----|
| Pelagic Cormorant | 68 | (Nelson & Sows, 6/11/79, B, 6/12/79, BM, II) | 42 |
| Black Oystercatcher | 2 | (Nelson & Sows, 6/11/79, B, 6/12/79, BM, III) | 42 |
| Western Gull | 300 | (Nelson & Sows, 6/11/79, B, 6/12/79, BM, III) | 42 |
| Pigeon Guillemot | <u>160</u> | (Nelson & Sows, 6/11/79, B, 6/12/79, BM, III) | 42 |
| Total | <u>530</u> | | |



(030) "Molera Rock" 36°16'45"N, 121°51'30"W

| | | | |
|-------------------|-----------|----------------------------------|----|
| Pelagic Cormorant | 26 | (Nelson & Sows, 6/22/79, BM, I) | 42 |
| Western Gull | 8 | (Nelson & Sows, 6/22/79, BM, II) | 42 |
| Pigeon Guillemot | P | (Nelson & Sows, 6/22/79, BM, II) | 42 |
| Total | <u>34</u> | | |

P = probably present

(031) Cooper Point and Islands 36°14'55"N, 121°50'10"W

| | | | |
|--------------------|------------|----------------------------------|----|
| Brandt's Cormorant | 72 | (Nelson & Sows, 6/22/79, B, II) | 42 |
| Pelagic Cormorant | 20 | (Nelson & Sows, 6/22/79, B, II) | 42 |
| Pigeon Guillemot | 40 | (Nelson & Sows, 6/22/79, B, III) | 42 |
| Total | <u>132</u> | | |

No nesting birds (Reynolds, 7/15/70, A) 36

(032) Pfeiffer Point 36°35'18"N, 121°47'35"W




| | | | |
|--------------------|-----------|----------------------------------|----|
| Cormorant (Unid.) | 2 | (Nelson & Sows, 6/22/79, B, II) | 42 |
| Brandt's Cormorant | 6 | (Nelson & Sows, 6/22/79, B, I) | 42 |
| Pelagic Cormorant | 4 | (Nelson & Sows, 6/22/79, B, I) | 42 |
| Pigeon Guillemot | 8 | (Nelson & Sows, 6/22/79, B, III) | 42 |
| Total | <u>20</u> | | |

(033) Grimes Point 36°12'20"N, 121°44'15"W

| | | | |
|---------------------|-----------|----------------------------------|----|
| Brandt's Cormorant | 16 | (Nelson & Sows, 6/22/79, B, II) | 42 |
| Pelagic Cormorant | 20 | (Nelson & Sows, 6/22/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Nelson & Sows, 6/22/79, B, III) | 42 |
| Pigeon Guillemot | 40 | (Nelson & Sows, 6/22/79, B, III) | 42 |
| Total | <u>78</u> | | |

(034) Lafler Rock and Mainland 36°12'N, 121°43'36"W

| | | | |
|--------------------|-----------|----------------------------------|----|
| Brandt's Cormorant | 12 | (Nelson & Sows, 6/22/79, B, I) | 42 |
| Pelagic Cormorant | 6 | (Nelson & Sows, 6/22/79, B, I) | 42 |
| Pigeon Guillemot | 20 | (Nelson & Sows, 6/22/79, B, III) | 42 |
| Total | <u>38</u> | | |



035 "Partington Ridge South" 36°00'N, 121°40'40"W




| | | | |
|-------------------|-----|--|----|
| Pelagic Cormorant | 20 | (Nelson & Sowls, 6/23/79, B, I) | 42 |
| Western Gull | 30 | (Nelson & Sowls, 6/23&7/13/79, B, III) | 42 |
| Pigeon Guillemot | 416 | (Nelson & Sowls, 6/23&7/13/79, B, III) | 42 |
| Total | 466 | | |

036 "Bench Mark 247" 36°02'N, 121°34'45"W

| | | | |
|-------------------|---|---------------------------------|----|
| Pelagic Cormorant | 6 | (Nelson & Sowls, 6/23/79, B, I) | 42 |
|-------------------|---|---------------------------------|----|

037 "Rockland Landing North" 36°00'57"N, 121°32'30"W

| | | | |
|--------------------|-------|----------------------------------|----|
| Brandt's Cormorant | 16 | (Nelson & Sowls, 6/23/79, B, II) | 42 |
| Pelagic Cormorant | 64 | (Nelson & Sowls, 6/23/79, B, II) | 42 |
| Total | 80 | | |
| Pelagic Cormorant | 20-40 | (Reynolds, 7/23/70, M) | 36 |





477


San Luis Obispo


The map on the facing page is an index to the locations of colonies within map 477, San Luis Obispo. Note that all colonies on the map are not numbered consecutively from north to south, since many previously unreported colonies have been added since initial colony numbers were assigned by Varoujean (1979). On the pages following this map, all colonies are listed sequentially and a detailed map of each is provided.

Numbers of breeding seabirds will vary from year to year. Below are the approximate numbers of breeding seabirds within this region.

| | |
|-------------------------------|-------|
| Brandt's Cormorant. | 3,000 |
| Pelagic Cormorant | 700 |
| Black Oystercatcher | .80 |
| Western Gull. | 1,100 |
| Pigeon Guillemot. | 1,200 |
| Tufted Puffin | 0-2 |

477 San Luis Obispo






(001) Small rocks and mainland north and east of Plaskett Rock
35°55'16"N, 121°28'22"W

| | | | |
|---------------------|-----|--|----|
| Pelagic Cormorant | 42 | (Nelson & Sows, 6/25/79, B, I) | 42 |
| Black Oystercatcher | 6 | (Nelson & Sows, 6/25/79, B, II) | 42 |
| Western Gull | 64 | (Nelson & Sows, 6/25/79, B, 7/13/79, M, III) | 42 |
| Pigeon Guillemot | 30 | (Nelson & Sows, 6/25/79, B, III) | 42 |
| Total | 142 | | |
| Western Gull | 40 | (Reynolds, 5/4/70, M) | 36 |

(002) Plaskett Rock 35°55'14"N, 121°28'41"W

| | | | |
|---------------------|-----|---|----|
| Brandt's Cormorant | 0 | (Nelson & Sows, 6/23/80, A, II) | 42 |
| Pelagic Cormorant | 10 | (Nelson & Sows, 6/25/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Nelson & Sows, 6/25/79, B, III) | 42 |
| Western Gull | 60 | (Nelson & Sows, 6/25/79, B, III) | 42 |
| Pigeon Guillemot | 20 | (Nelson & Sows, 6/25/79, B, III) | 42 |
| Total | 92 | | |
| Brandt's Cormorant | 200 | (Reynolds, 5/4/70, M) | 36 |
| Brandt's Cormorant | 0 | (Nelson & Sows, 6/25/79, B, 8/2/79, A, I) | 42 |
| Pigeon Guillemot | 2 | (Reynolds, 5/4/70, M) | 36 |



Section from U.S.G.S.
1:24,000 scale map:
Cape San Martin,
Calif.



Plaskett Rock


Photo by Jay Nelson

003 Cape San Martin 35°53'17"N, 121°27'55"W

| | | | |
|---------------------|-------|--|----|
| Brandt's Cormorant | 680 | (Nelson & Sows, 6/23/80, A, II) | 42 |
| Pelagic Cormorant | 26 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, II) | 42 |
| Black Oystercatcher | 4 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, III) | 42 |
| Western Gull | 474 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, III) | 42 |
| Pigeon Guillemot | 8 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, III) | 42 |
| Total | 1,192 | | |
| Brandt's Cormorant | 400 | (Reynolds, 5/4/70, M) | 36 |
| Brandt's Cormorant | 1,228 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, 8/2/79, A, II) | 42 |
| Western Gull | 140 | (Reynolds, 5/4/70, M) | 36 |
| Pigeon Guillemot | 2 | (Reynolds, 5/4/70, M) | 36 |

004 Unnamed Rock 35°53'05"N, 121°27'46"W

| | | | |
|---------------------|-----|--|----|
| Pelagic Cormorant | 2 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, III) | 42 |
| Western Gull | 12 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, III) | 42 |
| Total | 16 | | |
| Brandt's Cormorant | 150 | (Reynolds, 5/4/70, M) | 36 |



Cape San Martin

Photo by Jay Nelson

005 "Redwood Gulch Rock" 35°49'32"N, 121°23'29"W

| | | | |
|--------------------|-----|--|----|
| Brandt's Cormorant | 478 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, II) | 42 |
| Pigeon Guillemot | 2 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, III) | 42 |
| Total | 480 | | |
| Brandt's Cormorant | 600 | (Reynolds, 7/21/70, M) | 36 |

006 La Cruz Rock 35°42'23"N, 121°18'45"W

| | | | |
|---------------------|----|------------------------------------|----|
| Cormorant (unid.) | 0 | (DeGange & Nelson, 7/15/80, L, I) | 42 |
| Black Oystercatcher | 2 | (DeGange & Nelson, 7/15/80, L, I) | 42 |
| Western Gull | 10 | (DeGange & Nelson, 7/15/80, L, II) | 42 |
| Total | 12 | | |
| Cormorant (unid.) | 4 | (Nelson & Sows, 6/25/79, BL, I) | 42 |
| Black Oystercatcher | 2 | (Reynolds, 7/19/70, M) | 36 |
| Black Oystercatcher | 2 | (Nelson & Sows, 6/25/79, BL, I) | 42 |
| Western Gull | 20 | (Nelson & Sows, 6/25/79, BL, III) | 42 |




007 Piedras Blancas 35°39'52"N, 121°17'18"W

| | | | |
|---------------------|-------|----------------------------------|----|
| Brandt's Cormorant | 1,200 | (Nelson & Sows, 6/23/80, A, II) | 42 |
| Black Oystercatcher | 2 | (Sorensen, 1980, M, III) | 30 |
| Western Gull | 56 | (Nelson & Sows, 6/26/79, B, III) | 42 |
| Pigeon Guillemot | 50 | (Nelson & Sows, 6/26/79, B, III) | 42 |
| Tufted Puffin | 0 | (Jameson, 1980, M) | 30 |
| Total | 1,308 | | |
| Brandt's Cormorant | 200 | (Reynolds, 7/15-19/70, AM) | 36 |
| Brandt's Cormorant | 1,360 | (Nelson & Sows, 8/2/79, A, II) | 42 |
| Western Gull | 8 | (Reynolds, 7/15-19/70, AM) | 36 |
| Pigeon Guillemot | 2 | (Reynolds, 7/15-19/70, AM) | 36 |
| Tufted Puffin | 2 | (Reynolds, 7/15-19/70, AM) | 36 |
| Tufted Puffin | 2 | (Nelson & Sows, 6/26/79, B, III) | 42 |

008 Morro Bay was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979). For information on Morro Rock see 026.

009 Point Buchon 35°15'20"N, 121°53'58"W

| | | | |
|---------------------|----|---|----|
| Pelagic Cormorant | 4 | (Chambers, Rodstrom & Sows, 7/6/79, B, II) | 42 |
| Black Oystercatcher | 6 | (Chambers, Rodstrom & Sows, 7/6/79, B, III) | 42 |
| Pigeon Guillemot | 20 | (Chambers, Rodstrom & Sows, 7/6/79, B, III) | 42 |
| Total | 30 | | |
| Pelagic Cormorant | 46 | (Frame, 1972, M) | 19 |



010 Unnamed Rocks 35°14'40"N, 120°53'39"W

| | | | |
|---------------------|-----|--|----|
| Pelagic Cormorant | 64 | (Lester, Nelson & Sows, 6/10/80, B, II) | 42 |
| Black Oystercatcher | 10 | (Chambers, Rodstrom & Sows, 7/6/79, B, III) | 42 |
| Western Gull | 22 | (Lester, Nelson & Sows, 6/10/80, B, III) | 42 |
| Pigeon Guillemot | 200 | (Chambers, Rodstrom & Sows, 7/16/79, B, III) | 42 |
| Total | 296 | | |
| Pelagic Cormorant | 50 | (Frame, 1972, M) | 19 |
| Pelagic Cormorant | 62 | (Chambers, Rodstrom & Sows, 7/6/79, B, II) | 42 |
| Black Oystercatcher | 4 | (Lester, Nelson & Sows, 6/10/80, B, III) | 42 |
| Western Gull | 54 | (Chambers, Rodstrom & Sows, 7/6/79, B, III) | 42 |



011 Lion Rock 35°31'01"N, 120°52'15"W

While Lion Rock is not an important nesting island, it is a critical roost rock. In the fall, up to 5,000 cormorants, hundreds of Brown Pelicans, and lesser numbers of Western and Heermann's Gulls roost here. California Sea lions haul out here in large numbers.

| | | | |
|---------------------|------|---|--|
| Brandt's Cormorant | 0 | (Nelson & Sows, 6/23/80, A, I) | |
| Pelagic Cormorant | 0 | (Lester, Nelson & Sows, 6/10/80, B, II) | |
| Black Oystercatcher | 2 | (Lester, Nelson & Sows, 6/10/80, B, II) | |
| Western Gull | 34 | (Lester, Nelson & Sows, 6/10/80, B, III) | |
| Pigeon Guillemot | 30 | (Chambers, Rodstrom & Sows, 7/6/79, BL, III) | |
| Total | 66 | | |
| Brandt's Cormorant | 700 | (Reynolds, 7/15/70, A) | |
| Brandt's Cormorant | 200+ | (Frame, 1972, L) | |
| Brandt's Cormorant | 100 | (Chambers, 1978, BL) | |
| Brandt's Cormorant | 0 | (Chambers, Rodstrom & Sows, 7/6/79, B, L, 8/2/79, A, I) | |
| Pelagic Cormorant | 30 | (Frame, 1972, L) | |
| Black Oystercatcher | 4 | (Chambers, Rodstrom & Sows, 7/6/79, BL, III) | |
| Western Gull | 20 | (Chambers, Rodstrom & Sows, 7/6/79, BL, III) | |

012 Unnamed Rock 35°12'06"N, 120°50'28"W

This site was reported by Reynolds in 1970. Exact location of this site is uncertain. Data has been combined with number 030.



013 "36 North" 35°58'36"N,121°29'15"W

| | | | |
|-------------------|---|-----------------------------|----|
| Pelagic Cormorant | 6 | (Nelson & Sows,6/25/79,B,I) | 42 |
|-------------------|---|-----------------------------|----|

014 "Larus Rock" 35°57'44"N,121°29'01"W

| | | | |
|---------------------|-----------|--|----|
| Pelagic Cormorant | 2 | (Nelson & Sows,6/24/79,M,6/25/79,B,I) | 42 |
| Black Oystercatcher | 2 | (Nelson & Sows,6/24/79,M,6/25/79,B,I) | 42 |
| Western Gull | 20 | (Nelson & Sows,6/24/79,M,6/25/79,B,II) | 42 |
| Total | <u>24</u> | | |

015 Unnamed Point 35°57'00"N,121°28'51"W


| | | | |
|---------------------|-----------|-------------------------------|----|
| Pelagic Cormorant | 6 | (Nelson & Sows,6/25/79,B,I) | 42 |
| Black Oystercatcher | 2 | (Nelson & Sows,6/25/79,B,III) | 42 |
| Western Gull | 4 | (Nelson & Sows,6/25/79,B,III) | 42 |
| Total | <u>12</u> | | |

016 Mainland point across from Bird Rock 35°52'37"N,121°26'59"W

| | | | |
|---------------------|-----------|-------------------------------|----|
| Pelagic Cormorant | 38 | (Nelson & Sows,6/25/79,B,I) | 42 |
| Black Oystercatcher | 2 | (Nelson & Sows,6/25/79,B,III) | 42 |
| Total | <u>40</u> | | |



017 Point north of Redwood Gulch 35°50'20"N,121°24'04"W

| | | | |
|-------------------|----|-----------------------------|----|
| Pelagic Cormorant | 26 | (Nelson & Sows,6/25/79,B,I) | 42 |
|-------------------|----|-----------------------------|----|



Section from U.S.G.S.
1:24,000 scale map:
Cape San Martin,
Calif.

Km
0 1/2 1



Section from U.S.G.S.
1:24,000 scale map:
Villa Creek, Calif.

Km
0 1/2 1

(018) Seastack south of Redwood Gulch 35°49'30"N,121°23'22"W

| | | | |
|---------------------|-----------|-----------------------------|----|
| Pelagic Cormorant | 16 | (Nelson & Sows,6/25/79,B,I) | 42 |
| Black Oystercatcher | P | (Nelson & Sows,6/25/79,B) | 42 |
| Western Gull | 6 | (Nelson & Sows,6/25/79,B,I) | 42 |
| Total | <u>22</u> | | |

P = probably present

(019) "Unmapped Island" 35°48'20"N,121°22'26"W



| | | | |
|-------------------|-----------|-------------------------------|----|
| Pelagic Cormorant | 56 | (Nelson & Sows,6/25/79,B,II) | 42 |
| Pigeon Guillemot | 12 | (Nelson & Sows,6/25/79,B,III) | 42 |
| Total | <u>68</u> | | |

(020) "Salmon Creek" 35°48'31"N,121°21'47"W

| | | | |
|-------------------|----|-----------------------------|----|
| Pelagic Cormorant | 12 | (Nelson & Sows,6/25/79,B,I) | 42 |
|-------------------|----|-----------------------------|----|

(021) Arched peninsula South of Salmon Creek 35°48'05"N,121°21'14"W

| | | | |
|-------------------|-----------|-------------------------------|----|
| Pelagic Cormorant | 8 | (Nelson & Sows,6/25/79,B,I) | 42 |
| Pigeon Guillemot | 80 | (Nelson & Sows,6/25/79,B,III) | 42 |
| Total | <u>88</u> | | |



022 "Ragged Point Lodge Colony" 35°46'53"N, 121°19'56"W

| | | | |
|---------------------|-----------|--|----|
| Pelagic Cormorant | 46 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, I) | 42 |
| Black Oystercatcher | 2 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, III) | 42 |
| Western Gull | 14 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, II) | 42 |
| Pigeon Guillemot | 20 | (Nelson & Sows, 6/24/79, M, 6/25/79, B, III) | 42 |
| Total | <u>82</u> | | |

023 "3 Rocks" 35°45'06"N, 121°19'07"W

| | | | |
|-------------------|-----------|---------------------------------|----|
| Pelagic Cormorant | 38 | (Nelson & Sows, 6/25/79, B, I) | 42 |
| Western Gull | 2 | (Nelson & Sows, 6/25/79, B, II) | 42 |
| Total | <u>40</u> | | |

024 Two rocks south of Point Piedras Blancas 35°39'30"N, 121°16'02"W


| | | | |
|------------------|-----------|----------------------------------|----|
| Western Gull | 48 | (Nelson & Sows, 6/26/79, B, II) | 42 |
| Pigeon Guillemot | 20 | (Nelson & Sows, 6/26/79, B, III) | 42 |
| Total | <u>68</u> | | |

025 Island south of Cayucos Point 35°26'45"N, 120°55'51"W

| | | | |
|---------------------|---|---------------------------------|----|
| Black Oystercatcher | 2 | (Nelson & Sows, 6/26/79, BL, I) | 42 |
|---------------------|---|---------------------------------|----|



Section from U.S.G.S.
1:24,000 scale map:
Burro Mountain, Calif.

Km
0 1/2 1




Section from U.S.G.S.
1:24,000 scale map:
Burro Mountain, Calif.

Km
0 1/2 1



Section from U.S.G.S.
1:24,000 scale map:
Piedras Blancas, Calif.

Km
0 1/2 1



Section from U.S.G.S.
1:24,000 scale map:
Cayucos, Calif.

Km
0 1/2 1

(026) Morro Rock and Pillar Rock 35°22'13"N, 120°52'08"W

| | | | |
|---------------------|------------|-----------------------------------|----|
| Pelagic Cormorant | 40 | (Lester & Nelson, 7/7/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Lester & Nelson, 7/7/79, B, II) | 42 |
| Western Gull | 120 | (Lester & Nelson, 7/7/79, B, III) | 42 |
| Pigeon Guillemot | 40 | (Lester & Nelson, 7/7/79, B, III) | 42 |
| Total | <u>202</u> | | |



Morro Rock



Photo by Jay Nelson

(027) Spooner's Cove 35°16'21"N, 120°53'57"W

| | | | |
|------------------|------------|---------------------------|----|
| Western Gull | 2 | (Nelson, 6/11/80, M, I) | 42 |
| Pigeon Guillemot | 100 | (Nelson, 6/11/80, M, III) | 42 |
| Total | <u>102</u> | | |



Section from U.S.G.S.
1:24,000 scale map:

Morro Bay South, Calif.



Section from U.S.G.S.
1:24,000 scale map:

Morro Bay South, Calif.



028 "Pup Rock and Adjacent Mainland" 35°13'00N, 120°52'11"W


| | | | |
|---------------------|----|---|----|
| Black Oystercatcher | 2 | (Lester, Nelson, & Sows, 6/10/80, B, III) | 42 |
| Western Gull | 54 | (Lester, Nelson & Sows, 6/10/80, L, II) | 42 |
| Total | 56 | | |
| Western Gull | 40 | (Chambers, Rodstrom & Sows, 7/6/79, BL, II) | 42 |

029 Diablo Rock and Adjacent Mainland 35°12'36"N, 120°51'38"W

| | | | |
|---------------------|-----|---|----|
| Brandt's Cormorant | 212 | (Lester, Nelson & Sows, 6/10/80, B, II) | 42 |
| Pelagic Cormorant | 16 | (Lester, Nelson & Sows, 6/10/80, B, II) | 42 |
| Western Gull | 4 | (Lester, Nelson & Sows, 6/10, 80, B, II) | 42 |
| Pigeon Guillemot | 60 | (Lester, Nelson, & Sows, 6/10/80, B, II) | 42 |
| Total | 292 | | |
| Brandt's Cormorant | 360 | (Nelson & Sows, 8/2/79, A, II) | 42 |
| Pelagic Cormorant | 22 | (Chambers, Rodstrom & Sows, 7/6/79, B, II) | 42 |
| Black Oystercatcher | 2 | (Chambers, Rodstrom & Sows, 7/6/79, B, III) | 42 |
| Western Gull | 4 | (Chambers, Rodstrom & Sows, 7/6/79, B, III) | 42 |
| Pigeon Guillemot | 30 | (Chambers, Rodstrom & Sows, 7/6/79, B, III) | 42 |

030 Diablo Canyon Nuclear Power Plant South 35°12'07"N, 120°50'39"W

| | | | |
|---------------------|-----|---|----|
| Brandt's Cormorant | 100 | (Lester, Nelson & Sows, 6/10/80, B, III) | 42 |
| Pelagic Cormorant | 82 | (Lester, Nelson & Sows, 6/10/80, B, II) | 42 |
| Black Oystercatcher | 4 | (Chambers, Rodstrom & Sows, 7/6/79, B, III) | 42 |
| Western Gull | 10 | (Lester, Nelson & Sows, 6/10/80, B, II) | 42 |
| Pigeon Guillemot | 132 | (Chambers, Rodstrom & Sows, 7/6/79, B, III) | 42 |
| Total | 328 | | |
| Cormorant (unid.) | 16 | (Chambers, Rodstrom & Sows, 7/6/79, B, I) | 42 |
| Brandt's Cormorant | 200 | (Reynolds, 7/15/70, A) | 36 |
| Brandt's Cormorant | 16 | (Chambers, Rodstrom & Sows, 7/6/79, B, I) | 42 |
| Pelagic Cormorant | 18 | (Chambers, Rodstrom & Sows, 7/6/79, B, II) | 42 |
| Western Gull | 4 | (Chambers, Rodstrom & Sows, 7/6/79, B, III) | 42 |



Diablo Rock off of Diablo Canyon Nuclear Power Plant

Photo by Art Sowls

(031) "Double Rock Region" 35°11'39"N, 120°50'29"W

| | | | |
|-------------------|----|---|----|
| Pelagic Cormorant | 16 | (Nelson, Sows & Watson, 6/28/79, B, II) | 42 |
|-------------------|----|---|----|

(032) Pecho Rock 35°10'45"N, 120°49'00"W

| | | | |
|--------------------|------------|---|----|
| Brandt's Cormorant | 148 | (Nelson & Sows, 6/23/80, A, II) | 42 |
| Western Gull | 4 | (Lester, Nelson & Sows, 6/10/80, B, II) | 42 |
| Total | <u>152</u> | | |
| Brandt's Cormorant | none | (Reynolds, 7/15/70, A) | 36 |
| Brandt's Cormorant | 140 | (Nelson & Sows, 8/2/79, A, II) | 42 |



Pecho Rock




Photo by Art Sows

(033) Smith and Whaler Islands 35°09'00"N, 120°45'15"W

| | | | |
|---------------------|-----------|---|----|
| Black Oystercatcher | 4 | (Nelson, Sows & Watson, 6/28/79, BL, III) | 42 |
| Western Gull | 2 | (Nelson, Sows & Watson, 6/28/79, BL, I) | 42 |
| Pigeon Guillemot | 20 | (Nelson, Sows & Watson, 6/28/79, BL, III) | 42 |
| Total | <u>26</u> | | |

(034) Fossil Point 35°10'26"N, 120°43'26"W

| | | | |
|---------------------|------------|-----------------------------------|----|
| Pelagic Cormorant | 44 | (Rodstrom & Sows, 7/7/79, B, I) | 42 |
| Black Oystercatcher | 6 | (Rodstrom & Sows, 7/7/79, B, III) | 42 |
| Western Gull | 6 | (Rodstrom & Sows, 7/7/79, B, II) | 42 |
| Pigeon Guillemot | 110 | (Rodstrom & Sows, 7/7/79, B, III) | 42 |
| Total | <u>166</u> | | |



035 "Shell Beach Rocks" 35°09'06"N, 120°40'11"W

| | | | |
|---------------------|----------------|------------------------------------|----|
| Pelagic Cormorant | 4 | (Rodstrom & Sowls, 7/7/79, B, I) | 42 |
| Black Oystercatcher | 6 | (Sowls, 6/11/80, M, II) | 42 |
| Western Gull | 14 | (DeGange, 5/26/80, M, II) | 42 |
| Heermann's Gull | X ¹ | (DeGange, 5/26/80, M, II) | 42 |
| Pigeon Guillemot | 100 | (Sowls, 6/11/80, M, III) | 42 |
| Total | 124 | | |
| Black Oystercatcher | 6 | (Rodstrom & Sowls, 7/7/79, B, III) | 42 |

¹ Before 1980, Heermann's Gulls were known to breed only in the Gulf of California and along the west coast of Baja California, Mexico. Two pairs attempted to nest at Shell Beach in 1980. These represent 2 of 3 known nesting attempts by Heermann's Gulls in the state of California in 1980; the other being at Alcatraz in San Francisco Bay (Binford 1980). All 3 nesting attempts were unsuccessful. See Appendix B.

X = present

036 "North Pismo Beach Rocks" 35°08'57"N, 120°39'23"W

| | | | |
|---------------------|----|------------------------------------|----|
| Pelagic Cormorant | 18 | (Rodstrom & Sowls, 7/7/79, B, II) | 42 |
| Black Oystercatcher | 4 | (Rodstrom & Sowls, 7/7/79, B, III) | 42 |
| Western Gull | 8 | (Rodstrom & Sowls, 7/7/79, B, II) | 42 |
| Pigeon Guillemot | 60 | (Nelson & Sowls, 5/29/79, M, III) | 42 |
| Total | 90 | | |




037 Oso Flaco Lake 35°01'42"N, 120°37'40"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|-------------------------|----|
| Least Tern | 12-20 | (Goldwasser, 4-8/80, L) | 12 |
|------------|-------|-------------------------|----|

038 Point San Simeon 35°38'N, 121°12'W

| | | | |
|------------------|----|-----------------------------------|----|
| Pigeon Guillemot | 40 | (Nelson & Sowls, 6/26/79, B, III) | 42 |
|------------------|----|-----------------------------------|----|





501

Santa Maria


The maps on the facing page and following page are indexes to the locations of colonies within map 501, Santa Maria. Note that all colonies on the map are not numbered consecutively from north to south, since many previously unreported colonies have been added since initial colony numbers were assigned by Varoujean (1979). On the pages following these two maps, all colonies are listed sequentially and a detailed map of each is provided.


Numbers of breeding seabirds will vary from year to year. Below are the approximate numbers of breeding seabirds within this region.

| | |
|-----------------------------------|--------|
| Leach's Storm-Petrel. | X |
| Ashy Storm-Petrel | 400 |
| Brandt's Cormorant. | 5,000 |
| Double-crested Cormorant. | 150* |
| Pelagic Cormorant | 400 |
| Black Oystercatcher | 130 |
| Western Gull. | 1,200 |
| Pigeon Guillemot. | 1,400 |
| Xantus' Murrelet. | 150 |
| Cassin's Auklet | 22,000 |
| Rhinoceros Auklet | 30 |

X = present

* coastal population only.






(001) Santa Maria River 34°58'09"N, 120°38'51"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.


| | | | |
|------------|-------|-------------------------|----|
| Least Tern | 40 | (Goldwasser, 4-8/80, L) | 12 |
| Least Tern | 34-40 | (Atwood, 4-8/ , L) | 12 |
| Least Tern | 36-46 | (Atwood, 4-8/79, L) | 12 |

(002) Santa Ynez River was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).



Section from U.S.G.S.
1:24,000 scale map:


Point Sal, Calif.



003 San Antonio Creek and Purisima Point 34°47' 120°38'

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|-------------------------|----|
| Least Tern | 54-64 | (Goldwasser, 4-8/80, L) | 12 |
| Least Tern | 26-30 | (Atwood, 4-8/80, L) | 12 |
| Least Tern | 58-68 | (Atwood, 4-8/79, L) | 12 |



(004) Prince Island 34°03'29"N, 120°20'00"W For map see page 281.

| | | | | | |
|--------------------------|--------|---|----------|-------------|----|
| Leach's Storm-Petrel | 4+ | (| Δ | ,1976-77,L) | 29 |
| Ashy Storm-Petrel | 600 | (| | ,1976-77) | 29 |
| Brown Pelican | 0 | (| | ,1976-77) | 29 |
| Brandt's Cormorant | 1,814 | (| | ,6/21/77) | 29 |
| Double-crested Cormorant | 150 | (| | ,1976-77) | 29 |
| Pelagic Cormorant | 40 | (| | ,1977) | 29 |
| Black Oystercatcher | 6 | (| | ,1977) | 29 |
| Western Gull | 960 | (| | ,1977) | 29 |
| Common Murre | 0 | (| | ,1975-77) | 29 |
| Pigeon Guillemot | 300 | (| | ,1975-77) | 29 |
| Xantus' Murrelet | 150 | (| | ,1975-77) | 29 |
| Cassin's Auklet | 20,000 | (| | ,1975-77) | 29 |
| Tufted Puffin | 0 | (| | ,1975-77) | 29 |
| Total | 23,420 | | | | |

| | | | |
|--------------------------|-------------|--|----|
| Ashy Storm-Petrel | X | (Blietz,7/50+7/61) | 29 |
| Ashy Storm-Petrel | 800 | (Craig & Sheppard,7/65) | 29 |
| Ashy Storm-Petrel | 50-100 | (Huber,1968) | 29 |
| Brown Pelican | X | (Willet,1910; Everman,1919; Degoot,1927; Stevens,1930) | 29 |
| Brown Pelican | 400 | (Summer,5/18/39) | 29 |
| Brandt's Cormorant | X | (Willet,1910; Pemberton,1922+1928; Stevens,1929) | 29 |
| Brandt's Cormorant | 3,000 | (Craig & Sheppard,7/65) | 29 |
| Brandt's Cormorant | 2,000 | (Anderson,4/27/72) | 29 |
| Brandt's Cormorant | 1,720 | (Δ ,1975) | 29 |
| Brandt's Cormorant | 1,180 | (Δ ,1976) | 29 |
| Double-crested Cormorant | 200 | (Appleton,6/6/06) | 29 |
| Double-crested Cormorant | X | (Willet,1910) | 29 |
| Double-crested Cormorant | 60 | (Crossin & Borwnell,5/15/68) | 29 |
| Double-crested Cormorant | 40 | (Huber,1968) | 29 |
| Pelagic Cormorant | X | (Streator,1886) | 29 |
| Pelagic Cormorant | 24 | (Appleton,6/6/06) | 29 |
| Pelagic Cormorant | 10 | (Huber,1968) | 29 |
| Pelagic Cormorant | 20 | (Δ ,1976) | 29 |
| Western Gull | X | (Willet,6/10) | 29 |
| Western Gull | 1,000-2,000 | (Wright & Snyder,5/25/29) | 29 |
| Western Gull | 4,000 | (Craig & Sheppard,7/65) | 29 |
| Western Gull | 480-500 | (Huber,1968) | 29 |
| Western Gull | 1,000 | (Δ ,1976) | 29 |
| Common Murre | X | (Bradbury,1885; Burt,1905; Hedrick & Appleton,1906) | 29 |
| Common Murre | 200 | (Willet,6/15/10) | 29 |
| Common Murre | X | (Wright & Snyder,7/12/12) | 29 |
| Pigeon Guillemot | X | (Willet,6/15/10) | 29 |
| Pigeon Guillemot | 400 | (Craig & Sheppard,1965) | 29 |
| Pigeon Guillemot | 100 | (Huber,1968) | 29 |

X = present

004 Prince Islands (Cont'd.)

| | | | |
|------------------|--------|--|----|
| Xantus' Murrelet | X | (Huber, 1968) | 29 |
| Cassin's Auklets | X | (Streator, 1886; Wright & Snyder, 1912) | 29 |
| Cassin's Auklets | 2,000+ | (Burt & Appleton, 6/6/06) | 29 |
| Cassin's Auklets | 200 | (Van Denburgh, 5/19/19) | 29 |
| Cassin's Auklets | 100 | (Pemberton & DeGoot, 3/31/27) | 29 |
| Cassin's Auklets | 6,000 | (Craig & Sheppard, 7/4/65) | 29 |
| Cassin's Auklets | 10,000 | (Crossin & Brownell, 5/68) | 29 |
| Cassin's Auklets | 3,000 | (Huber, 1968) | 29 |
| Tufted Puffin | X | (Burt, 1905; Burt & Appleton, 1906; Willet, 1910; Wright & Snyder, 1912) | 29 |
| Tufted Puffin | none | (Craig & Sheppard, 1965; POBSP personnel, 1968) | 29 |

X = present

△ Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.



Prince Island


Photo by George Hunt

(005) Castle Rock 34°03'17"N, 120°26'17"W


| | | | | | |
|---------------------|---------|---|---|-------------------------------|----|
| Ashy Storm-Petrel | 200 | (| △ | ,1976-77) | 29 |
| Brandt's Cormorant | 1,832 | (| | ,1977) | 29 |
| Pelagic Cormorant | 50 | (| | ,1977) | 29 |
| Black Oystercatcher | 6 | (| | ,6/8/76) | 29 |
| Western Gulls | 100 | (| | ,6/8/79) | 29 |
| Pigeon Guillemot | 200 | (| | ,1976-77) | 29 |
| Xantus' Murrelet | P | (| | ,1975-77) | 29 |
| Cassin's Auklet | 2,000 | (| | ,1977) | 29 |
| Total | 4,488 | | | | |
| Ashy Storm-Petrel | X | (| | (Crossin & Brownell, 5/15/68) | 29 |
| Brandt's Cormorant | X | (| | (Crossin & Brownell, 5/15/68) | 29 |
| Brandt's Cormorant | 1,100 | (| | (Anderson, 4/27/72) | 29 |
| Brandt's Cormorant | 432 | (| △ | ,1975) | 29 |
| Brandt's Cormorant | 726 | (| △ | ,6/8/76) | 29 |
| Pelagic Cormorant | 50 | (| | (Huber, 1968) | 29 |
| Pelagic Cormorant | 68 | (| △ | ,1976) | 29 |
| Western Gull | 200-300 | (| | (Huber, 1968) | 29 |
| Pigeon Guillemot | X | (| | (Crossin & Brownell, 5/15/68) | 29 |
| Xantus' Murrelet | X | (| | (Crossin & Brownell, 5/14/68) | 29 |
| Cassin's Auklet | X | (| | (Willet, Ca. 1912) | 29 |
| Cassin's Auklet | 5,000 | (| | (Crossin & Brownell, 5/15/68) | 29 |

X = present, P = probably present

△ Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.



Section from U.S.G.S.
1:24,000 scale map:
San Miguel Island West





006 San Miguel Island 34°02'32"N, 120°22'30"W

Data has been reorganized so that data for San Miguel Island is now under numbers 014, 015 and 016.


007 Santa Rosa Is., Sandy Pt. to Carrington Pt.

| | | | | | |
|-------------------------|--------------|------------|---------------------|-----------|-----------|
| Brandt's Cormorant | 1,400 | (| <u>1</u> | ,1977) | 29 |
| Pelagic Cormorant | 72 | (| | ,1977) | 29 |
| Black Oystercatcher | 40 | (<u>2</u> | | ,1976-77) | 29 |
| Western Gull | 30 | (<u>2</u> | | ,1976-77) | 29 |
| Pigeon Guillemot | 250 | (| | ,1976-77) | 29 |
| Total | <u>1,792</u> | | | | |
| Pigeon Guillemot | X | (| Willet,1910) | | 29 |

X = present

1 Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.

2 Population estimate is for all of Santa Rosa Island.



008 Lion Rock at Point Sal 34°53'55"N, 120°39'50"W



| | | |
|------------------|---------------------------------|----|
| No nesting birds | (Nelson & Sows, 7/12/79, B, I) | 42 |
| No nesting birds | (Nelson & Sows, 6/23/80, A, II) | 42 |
| No nesting birds | (Reynolds, 1970, A) | 36 |

009 Destroyer Rock 34°36'10"N, 120°38'40"W

| | | |
|------------------|--------------------------------------|----|
| Pigeon Guillemot | 100 (Nelson & Sows, 7/10/79, B, III) | 42 |
|------------------|--------------------------------------|----|

010 Mainland and rocks east of Destroyer Rock 34°36'N, 120°38'26"W

| | | |
|------------------|-------------------------------------|----|
| Pigeon Guillemot | 80 (Nelson & Sows, 7/10/79, B, III) | 42 |
|------------------|-------------------------------------|----|



(011) Point Arguello 34°38'N, 120°38'49"W

| | | | |
|---------------------|------------|---|--|
| Pelagic Cormorant | 30 | (Lester, 6/11/80, M, II) | |
| Western Gull | 4 | (Nelson & SOWls, 7/10/79, B, II) | |
| Black Oystercatcher | 2 | (DeGange & Nelson, 7/18/80, M, III) | |
| Pigeon Guillemot | 700 | (Lester, 6/11/80, M; Nelson & SOWls, 7/10/79, B, III) | |
| Rhinoceros Auklets | 30 | (Lester, 6/11/80, M; DeGange & Nelson, 7/18/80, M, III) | |
| Total | <u>766</u> | | |
| Pelagic Cormorant | 20 | (Nelson & SOWls, 7/10/79, B, II) | |
| Western Gull | 4 | (DeGange & Nelson, 7/18/80, M, III) | |



△ See text, page 50.

(012) Rocky Point 34°33'45"N, 120 38'11"W

| | | | |
|---------------------|------------|-----------------------------------|----|
| Black Oystercatcher | 2 | (Nelson & SOWls, 7/10/79, B, III) | 42 |
| Pigeon Guillemot | 100 | (Nelson & SOWls, 7/10/79, B, III) | 42 |
| Total | <u>102</u> | | |

(013) Point Conception 34°26'54"N, 120 28'13"W

| | | | |
|-------------------|-----------|-----------------------------------|----|
| Pelagic Cormorant | 6 | (Nelson & SOWls, 7/10/79, B, III) | 42 |
| Pigeon Guillemot | 30 | (Nelson & SOWls, 7/10/79, B, III) | 42 |
| Total | <u>36</u> | | |




014 Point Bennett, San Miguel Island 34°2'N, 120°3'30"W

| | | | | | | |
|---------------------|-----|-------------------------|---|-----------|--------|----|
| Brandt's Cormorant | 54 | (| 1 | ,7/20/77) | 29 | |
| Pelagic Cormorant | 24 | (| 1 | ,1977) | 29 | |
| Black Oystercatcher | P | 2 | (| 1 | ,1977) | 29 |
| Western Gull | 40 | (Collins,5/19/77) | | | 29 | |
| Cassin's Auklet | 20 | (Collins & Newman,1977) | | | 29 | |
| Total | 138 | | | | | |

P = probably present

1. Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.

2. The estimate for entire San Miguel Island is 48 birds.



Section from U.S.G.S.
1:24,000 scale map:
San Miguel Island West

Km
0 1/2 1

Judith Rock
34°01'30" +
120°25'


015 Harris Pt. to Cuyler Harbor 34°04'N, 120°22'W

| | | | | | |
|---------------------|-----------------|---|----|-----------|----|
| Ashy Storm-Petrel | X | (| ∠1 | ,6/25/76) | 29 |
| Brandt's Cormorant | 10 | (| | ,1976) | 29 |
| Pelagic Cormorant | 124 | (| | ,1977) | 29 |
| Black Oystercatcher | X ^{∠2} | (| | ,1977) | 29 |
| Western Gull | 28 | (| | ,1976) | 29 |
| Pigeon Guillemot | 140 | (| | ,1975-76) | 29 |
| Xantus' Murrelet | P | (| | ,1975-76) | 29 |
| Total | <u>302</u> | | | | |

X = present, P = probably present


∠1 Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.

∠2 The estimate is for entire San Miguel Island is 48 birds.



Section from U.S.G.S.
1:24,000 scale map:

San Miguel Island East





(016) Bay Point Area 34°02'N, 120°19'W

| | | | | | |
|---------------------|----------------|---|----------|-----------|----|
| Pelagic Cormorant | 52 | (| <u>1</u> | ,1977) | 29 |
| Black Oystercatcher | P ² | (| | ,1975-77) | 29 |
| Pigeon Guillemot | 120 | (| | ,1975-77) | 29 |
| | <u>172</u> | | | | |


P = probably present

¹ Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.

² Estimate for the entire San Miguel Island is 48 birds.



Section from U.S.G.S.
1:24,000 scale map:
San Miguel Island East





502

Los Angeles

The map on the facing page is an index to the locations of colonies within map 502, Los Angeles. Note that all colonies on the map are not numbered consecutively from north to south, since many previously unreported colonies have been added since initial colony numbers were assigned by Varoujean (1979). On the pages following this map, all colonies are listed sequentially and a detailed map of each is provided.


Numbers of breeding seabirds will vary from year to year. Below are the approximate numbers of breeding seabirds within this region.

| | |
|------------------------------------|-------|
| Ashy Storm-Petrel. | 80 |
| Brown Pelican. | 2,500 |
| Brandt's Cormorant | .100 |
| Double-crested Cormorant | .150* |
| Pelagic Cormorant. | 60 |
| Black Oystercatcher. | .130 |
| Western Gull | 6,700 |
| Pigeon Guillemot | .500 |
| Cassin's Auklet. | .120 |

* coastal population only.

502 Los Angeles





001 Goleta Slough was previously assigned a catalog number because of Light-footed Clapper Rail nesting. We have not included information on this species in this report. See Wilbur (1974).

002 El Estero was previously assigned a catalog number because of Light-footed Clapper Rail nesting. We have not included information on this species in this report. See Wilbur (1974).

003 Santa Clara River 34°14'08"N, 119°15'51"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|-------------------------|----|
| Least Tern | 34-30 | (Goldwasser, 4-8/80, L) | 12 |
| Least Tern | 20-30 | (Atwood, 4-18/78, L) | 12 |
| Least Tern | 30-40 | (Atwood, 4-18/79, L) | 12 |

004 McGrath Lake was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).

005 Ormond Beach 34°08'13"N, 119°10'56"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.



| | | | |
|------------|-------|-------------------------|----|
| Least Tern | 0 | (Goldwasser, 4-8/80, L) | 12 |
| Least Tern | 0 | (Atwood, 4-8/80, L) | 12 |
| Least Tern | 12-16 | (Atwood, 4-8/79, L) | 12 |

006 Mugu Lagoon 34°06'08"N, 119°06'04"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|-------------------------|----|
| Least Tern | 24 | (Goldwasser, 4-8/80, L) | 12 |
| Least Tern | 20-24 | (Atwood, 4-8/80, L) | 12 |
| Least Tern | X | (Atwood, 4-8/79, L) | 12 |

X = present



007

Anacapa Island - West 34°00'54"N, 119°21'57"W

Anacapa Island - West is the most important breeding site for Brown Pelicans in California.


| | | | |
|--------------------------|-----------------|--------------------------|------|
| Brown Pelican | 2,516 | (Anderson & Gress, 1979) | 4,20 |
| Brandt's Cormorant | 0 | (<u>1</u> , 1976) | 29 |
| Double-crested Cormorant | 132 | (Anderson & Gress, 1979) | 4,20 |
| Pelagic Cormorant | 0 | (<u>1</u> , 1976-77) | 29 |
| Black Oystercatcher | X ² | (<u>1</u> , 1976-77) | 29 |
| Western Gull | X | (<u>1</u> , 1976-77) | 29 |
| Pigeon Guillemot | 10 ³ | (<u>1</u> , 6/23/77) | 29 |
| Total | 2,758 | | |

| | | |
|--------------------------|-------|---|
| Brown Pelican | X | (Ashworth, 1929; Stevens, 1935; Bond, 1940) |
| Brown Pelican | 400 | (Ashworth & Thompson, 5/9/30) |
| Brown Pelican | 4,000 | (Bond, 1935) |
| Brown Pelican | 4,000 | (Stevens & Harrison, 3/1/36) |
| Brown Pelican | 4,000 | (Bond & Sumner, 4/16/39) |
| Brown Pelican | X | (Jensen, 1962; Ranks, 1963-64; Schreiber & DeLong, 1967-68) |
| Brown Pelican | 2,544 | (Risebough, 1969) |
| Brown Pelican | 1,104 | (Gress, 1970) |
| Brown Pelican | 1,080 | (Anderson & Anderson, 1971) |
| Brown Pelican | 522 | (Anderson & Anderson, 1972) |
| Brown Pelican | 494 | (Anderson & Anderson, 1973) |
| Brown Pelican | 832 | (Anderson & Anderson, 1974) |
| Brown Pelican | 424 | (Anderson & Anderson, 1975) |
| Brown Pelican | 834 | (Anderson & Anderson, 1976) |
| Brown Pelican | 152 | (Anderson & Anderson, 1977) |
| Brown Pelican | 420 | (Anderson, 1978) |
| Brandt's Cormorant | X | (Ashworth & Thompson, 1928 & 31) |
| Brandt's Cormorant | 100 | (Bond, 5/34) |
| Brandt's Cormorant | X | (Crossin & Brownell, 5/68) |
| Brandt's Cormorant | 2 | (<u>1</u> , 1975) |
| Double-crested Cormorant | 30 | (<u>1</u> , 1977) |
| Double-crested Cormorant | 68 | (Anderson & Gress, 1978) |
| Pelagic Cormorant | 2 | (<u>1</u> , 1975) |
| Pigeon Guillemot | X | (Wright & Snyder, 7/6/12/ Badger, Peyton & Hanna, 5/27/17) |

¹ Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.

² 20+ estimated for entire Anacapa Island.

³ Estimate is for entire Anacapa, but birds are most likely from West Anacapa.



Brown Pelicans, Anacapa Island

Photo by Frank Gress

008 Anacapa Island - Middle 34°00'19"N, 119°23'43"W

| | | | | | |
|---------------------|--------------|----|----|-----------|----|
| Brandt's Cormorant | 4 | (| ∠1 | ,6/23/77) | 29 |
| Pelagic Cormorant | 4 | ∠2 | (| ,1977) | 29 |
| Black Oystercatcher | X | ∠3 | (| ,1976-77) | 29 |
| Western Gull | 5,000 | ∠4 | (| ,1976-77) | 29 |
| Pigeon Guillemot | P | ∠4 | (| , .) | 29 |
| Total | <u>5,008</u> | | | | |

009 Anacapa Island - East 34°00'41"N, 119°25'26"W

| | | | | |
|---------------------|------------|----|---------------------|----|
| Brown Pelican | 0 | ∠2 | (Anderson, 1976-77) | 4 |
| Black Oystercatcher | X | (| ∠1 ,1976-77) | 29 |
| Western Gull | 200 | ∠4 | (,1977) | 29 |
| Pigeon Guillemot | P | (| ,1977) | 29 |
| Xantus' Murrelet | X | (| ,1976-77) | 29 |
| Total | <u>200</u> | | | |

| | | | |
|---------------|--------|-------------------|----|
| Brown Pelican | X | (Holder, 1898) | 29 |
| Brown Pelican | 1,000 | (Willet, 6/5/10) | 29 |
| Brown Pelican | 400 | (Peyton, 3/12/11) | 29 |
| Brown Pelican | 2,000+ | (Peyton, 1914) | 29 |
| Brown Pelican | 3,000 | (Peyton, 1916) | 29 |
| Brown Pelican | 4,000 | (Peyton, 1917) | 29 |
| Brown Pelican | 10,000 | (Peyton, 1920) | 29 |
| Brown Pelican | 1,000 | (DeGoot, 3/5/28) | 29 |



∠1 Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.

∠2 20+ estimated from entire island.

∠3 Estimate includes birds from West Anacapa.

∠4 Estimate of 10 birds is for entire Anacapa. Birds most likely from West Anacapa.

X = present, P = probably present




010 Scorpion Rock 34°02'50"N, 119°32'47"W

| | | | | | |
|--------------------------|-----|---|----|---------------------------------------|----|
| Ashy Storm-Petrel | 40 | (| ∠1 | , 1976-77) | 29 |
| Brown Pelican | 0 | (| | , 1976-77) | 29 |
| Double-crested Cormorant | 0 | (| | , 1976-77) | 29 |
| Black Oystercatcher | 2 | (| | , 1977) | 29 |
| Western Gull | 300 | (| | , 1977) | 28 |
| Pigeon Guillemot | 8 | (| | , 1975-77) | 29 |
| Xantus' Murrelet | P | (| | , 1975-77) | 29 |
| Cassin's Auklet | 100 | (| | , 6/22/76) | 29 |
| Total | 400 | | | | |
| Ashy Storm-Petrel | X | (| | (Stevens, 1937-41) | 29 |
| Brown Pelican | X | (| | (Anderson & Anderson, 1972) | 29 |
| Brown Pelican | 160 | (| | (Anderson et al., 1975) | 29 |
| Brown Pelican | 210 | (| | (Anderson, et al., 1974) | 29 |
| Double-crested Cormorant | X | (| | (Beck, 1895) | 29 |
| Pelagic Cormorant | X | (| | (Beck, 1895) | 29 |
| Western Gull | X | (| | (Beck, 1895) | 29 |
| Xantus' Murrelet | X | (| | (Badger, 1928-29) | 29 |
| Xantus' Murrelet | X | (| | (Stevens, Harrison & Badger, 1936+38) | 29 |
| Cassin's Auklet | X | (| | (Beck, 1895; Badger, 1919+29) | 29 |

X = present

∠1 Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.



011 Santa Cruz Island


Data has been reorganized so that data for Santa Cruz Island is now under 012, 013 & 014.

012 Coche Point to Cavern Pt. 34°2'N, 119°36'50"W to 34°3'20"N, 119°33'45"W


| | | | | | |
|------------------|----|---|----------|--------|----|
| Western Gull | 92 | (| <u>1</u> | ,1977) | 29 |
| Pigeon Guillemot | X | (| <u>1</u> | ,1977) | 29 |

X = present

¹ Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.




Section from U.S.G.S.
 1:24,000 scale map:
Santa Cruz Island
 C & D



013 "Sppit Rock" 34°02'45"N, 119°43'30"W



| | | | | | |
|---------------------|-----|---|---|-----------|----|
| Ashy Storm Petrel | 16+ | (| △ | ,7/15/76) | 29 |
| Black Oystercatcher | 6 | (| | ,1977) | 29 |
| Cassin's Auklet | 20 | (| | ,6/22/77) | 29 |
| Total | 42+ | | | | |

△ Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.



Section from U.S.G.S.
1:24,000 scale map:

Santa Cruz Island C



014 Santa Cruz Is. - Kinton Pt. 34°0'30"N, 119°53'W to
Diablo Pt. 34°3'N, 119°45'W

| | | | | | |
|---------------------|----------------|---|----|-------------------------------------|----|
| Ashy Storm-Petrel | 20 | (| △1 | ,7/15/76) | 29 |
| Brandt's Cormorant | 84 | (| | ,1977) | 29 |
| Pelagic Cormorant | 50 | (| | ,1976) | 29 |
| Black Oystercatcher | X ² | (| | ,1977) | 29 |
| Western Gull | 80 | (| | ,1977) | 29 |
| Pigeon Guillemot | X ³ | (| | ,1977) | 29 |
| Cassin's Auklet | ? | (| | ,1977) | 29 |
| Total | 234 | | | | |
| Ashy Storm-Petrel | X | (| | (Wright & Snyder,1912; Dickey,1913) | 29 |
| Pelagic Cormorant | X | (| | (Dawson,1923) | 29 |
| Pigeon Guillemot | X | (| | (Wright & Snyder,1912) | 29 |
| Tufted Puffin | ? | (| | (Wright & Snyder,1912) | 29 |

X = present

△1 Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.


△2 100 estimated for entire Santa Cruz Island, including Gull Island (524 001), Scorpion Rock (502 010) and "Sppit" (502 013).

△3 400 estimated for entire Santa Cruz Island.

Section from
U.S.G.S. map:
Santa Cruz Island
A & B



014





524

Long Beach

The map on the facing page is an index to the locations of colonies within map 524, Long Beach. Note that all colonies on the map are not numbered consecutively from north to south, since many previously unreported colonies have been added since initial colony numbers were assigned by Varoujean (1979). On the pages following this map, all colonies are listed sequentially and a detailed map of each is provided.


Numbers of breeding seabirds will vary from year to year. Below are the approximate numbers of breeding seabirds within this region.


| | |
|------------------------------------|-------|
| Ashy Storm-Petrel | .300 |
| Black Storm-Petrel | .150 |
| Brown Pelican | .X |
| Brandt's Cormorant | .730 |
| Double-crested Cormorant | .150* |
| Pelagic Cormorant | 10 |
| Black Oystercatcher | 30 |
| Western Gull | 4,700 |
| Pigeon Guillemot | .120 |
| Xantus's Murrelet | 3,200 |
| Cassin's Auklet | .400 |

X = present

* coastal population only.

524 Long Beach






(001) Gull Island 33°57'01"N, 119°49'28"W

| | | | | | |
|---------------------|-----|---|---|-----------|----|
| Ashy Storm-Petrel | 2 | (| ∟ | ,4/12/77) | 29 |
| Brandt's Cormorant | 134 | (| | ,1977) | 29 |
| Pelagic Cormorant | 0 | (| | ,1976-77) | 29 |
| Black Oystercatcher | 8 | (| | ,1977) | 29 |
| Western Gull | 170 | (| | ,1977) | 29 |
| Xantus' Murrelet | 2 | (| | ,1976-77) | 29 |
| Cassin's Auklet | 150 | (| | ,1975-77) | 29 |
| Total | 466 | | | | |
| Brandt's Cormorant | 46+ | (| ∟ | ,1975) | 29 |
| Brandt's Cormorant | 110 | (| | ,1976) | 29 |
| Pelagic Cormorant | 8 | (| | ,1975) | 29 |

∟ Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.



002 Venice Beach and Playa del Rey 33°57'30"N, 118°27'30"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|---------|---------------------|----|
| Least Tern | 300-330 | (Atwood, 4-8/80, L) | 12 |
| Least Tern | 170-210 | (Atwood, 4-8/78, L) | 12 |
| Least Tern | 196-240 | (Atwood, 4-8/79, L) | 12 |



003 Terminal Island 33°57'30"N, 118°27'30"W

Least Terns no longer use this site for nesting.

004 Anaheim Bay and Surfside Beach 33°44'05"N, 118°05'34"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|---------------------|----|
| Least Tern | 80-96 | (Atwood, 4-8/80, L) | 12 |
| Least Tern | 12 | (Atwood, 4-8/79, L) | 12 |



005 San Gabriel River 33°45'12"N, 118°06'15"W



Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|---------|---------------------|----|
| Least Tern | 24-30 | (Atwood, 4-8/80, L) | 12 |
| Least Tern | 120-130 | (Atwood, 4-8/78, L) | 12 |
| Least Tern | 100-110 | (Atwood, 4-8/79, L) | 12 |

006 Bolsa Chica Beach 33°42'05"N, 118°03'05"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|---------------------|----|
| Least Tern | 40-52 | (Atwood, 4-8/80, L) | 12 |
| Least Tern | 0 | (Atwood, 4-8/78, L) | 12 |
| Least Tern | 68-92 | (Atwood, 4-8/79, L) | 12 |



(007) Shag Rock 33°29'15"N, 119°02'05"W

| | | | | |
|------------------|----|---|---------------|--------|
| Western Gull | 20 | (| $\frac{1}{1}$ | ,1976) |
| Xantus' Murrelet | 30 | (| 1 | ,1977) |
| Total | 50 | | | |


(008) Santa Barbara Island 33°28'37"N, 119°02'03"W

| | | | | | |
|--------------------------|---------|--------------|---------------|-----------|----|
| Black Storm-Petrel | 120-130 | (| $\frac{1}{1}$ | ,1976-77) | 29 |
| Ashy Storm-Petrel | 250 | (| 1 | ,1976-77) | 29 |
| Brown Pelican | 174 | (Gress,1980) | | | 20 |
| Brandt's Cormorant | 102 | (| $\frac{1}{1}$ | ,1977) | 29 |
| Double-crested Cormorant | 14 | (| | ,1977) | 29 |
| Pelagic Cormorant | 4 | (| | ,1977) | 29 |
| Black Oystercatcher | 12 | (| | ,1977) | 29 |
| Western Gull | 2,300 | (| | ,1975-78) | 29 |
| Pigeon Guillemot | 90 | (| | ,1976) | 29 |
| Xantus' Murrelet | 2-4,000 | (| | ,1977) | 29 |
| Cassin's Auklet | 150 | (| | ,1977) | 29 |
| Total | 6,220 | | | | |

| | | | | |
|--------------------------|---------|--|---------------|-----------|
| Brown Pelican | none | (Grinnel,1897) | | |
| Brown Pelican | 50 | {Willet,6/14/11} | | |
| Brown Pelican | 300-400 | (Wright & Snyder,7/2/12) | | |
| Brown Pelican | X | (Peyton,5/7/14; Schreiber & Delong,1967) | | |
| Brown Pelican | none | (| $\frac{1}{1}$ | ,1975-77) |
| Brown Pelican | none | (Gress,1978-1979) | | |
| Brandt's Cormorant | X | (Grinnell,1897; Howell,1908) | | |
| Brandt's Cormorant | 92 | (Jehl,7/11/74) | | |
| Brandt's Cormorant | 52 | (| $\frac{1}{1}$ | ,1975) |
| Brandt's Cormorant | 146 | (| 1 | ,1976) |
| Double-crested Cormorant | X | (Cooper,1863; Grinnel,1897; Peyton,1914; Wyman,1920+27; Sumner,1939) | | |
| Double-crested Cormorant | none | (Crossin & Brownell,5/68) | | |
| Double-crested Cormorant | 132 | (Hunt & Hunt,7/2/72) | | |
| Double-crested Cormorant | 20 | (| $\frac{1}{1}$ | ,1976) |
| Pelagic Cormorant | X | (Grinnell,1897; Pemberton,1927) | | |
| Pelagic Cormorant | 2 | (| $\frac{1}{1}$ | ,1975) |
| Pelagic Cormorant | none | (| 1 | ,1976) |
| Western Gull | X | (Grinnell,1897) | | |
| Western Gull | 1,000 | (Chambers,1889) | | |
| Western Gull | 3,000 | (Hunt & Hunt,7/7/72) | | |
| Western Gull | 2,324 | (| $\frac{1}{1}$ | ,1975) |
| Western Gull | 2,230 | (| | ,1976) |
| Western Gull | 1,622 | (| | ,1977) |
| Western Gull | 850 | (| | ,1978) |
| Pigeon Guillemots | X | (Grinnell,1897; Sumner,1939; Small,1960) | | |
| Xantus' Murrelet | X | (Wright & Snyder,7/3/12) | | |
| Cassin's Auklet | X | (Cooper,1863; Grinnel,1897) | | |
| Cassin's Auklet | none | (Howell,1908; Willet,1911; Wright & Snyder,1912) | | |
| Cassin's Auklet | none | (Sumner & Bond,1939; Hunt & Hunt,1972) | | |
| Tufted Puffin | ? | (Grinnel,1897) | | |

X = present


+ 33°30'
119°02'30"



+ 33°27'30"
119°02'30"

P A C I F I C

Section from U.S.G.S.
1:24,000 scale map:
Channel Islands Nat.
Monument, Calif.



009 Sutil Island 33°28'50"N, 119°02'50"W

| | | | | | |
|--------------------------|-------|-----------------------|---|---------------|----|
| Black Storm-Petrel | 20-30 | (| 1 | , 1976-77) | 29 |
| Ashy Storm-Petrel | 40-50 | (| | , 1976-77) | 29 |
| Brandt's Cormorant | 152 | (| | , 1977) | 29 |
| Double-crested Cormorant | 120 | (| | , 1977) | 29 |
| Pelagic Cormorant | 4 | (| | , 1977) | 29 |
| Black Oystercatcher | 4 | (| | , 1977) | 29 |
| Western Gull | 150 | (| | , 1976) | 29 |
| Pigeon Guillemot | 30 | (| | , 1976) | 29 |
| Xantus' Murrelet | 150 | (| | , 1977) | 29 |
| Cassin's Auklet | 70 | (| | , 6/27/76, L) | 29 |
| Total | 750 | | | | |
| Brandt's Cormorant | 80 | (Jeh1, 7/11/74) | | | 29 |
| Brandt's Cormorant | 186 | (| 1 | , 1975) | 29 |
| Brandt's Cormorant | 140 | (| 1 | , 1976) | 29 |
| Double-crested Cormorant | 60 | (| 1 | , 1976) | 29 |
| Cassin's Auklet | 200 | (Willett, 6/14/11, L) | | | 29 |


1 Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.



Sutil Island

Photo by George Hunt


+ 33°30'
119°02'30"



+ 33°27'30"
119°02'30"

P A C I F I C

Section from U.S.G.S.
1:24,000 scale map:
**Channel Islands Nat.
Monument, Calif.**




010 Bird Rock 33°27'04"N, 118°29'04"W

| | | | | | |
|--------------------|-----------|---|------------------|-----------|----|
| Brandt's Cormorant | 0 | (| 1 | ,1975-76) | 29 |
| Western Gull | 52 | (| | ,1976) | 29 |
| Xantus' Murrelet | 0 | (| | ,1976-77) | 29 |
| Total | <u>52</u> | | | | |
| Brandt's Cormorant | X | (| Willet, 4/11/04) | | 29 |
| Brandt's Cormorant | none | (| Jehl, 7/9/74) | | 29 |
| Western Gull | X | (| Grinnell, 1897) | | 29 |
| Western Gull | 48 | (| Harper, 1965) | | 29 |
| Western Gull | 50 | (| Harper, 1966) | | 29 |
| Western Gull | 20 | (| Jehl, 7/1974) | | 29 |
| Western Gull | 58 | (| Hand, 1974) | | 29 |
| Western Gull | 50-60 | (| 1, 1975) | | 29 |
| Xantus' Murrelet | X | (| Bleitz, 1967) | | 29 |

X = present

1 Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.



Section from U.S.G.S.
1:24,000 scale map:
Santa Catalina West
&
Santa Catalina North
Km



011 San Nicolas Island 33°14'30"N, 119°30'30"W

| | | | | | |
|---------------------|-------|---|-----------------------|-----------|----|
| Brandt's Cormorant | 290 | (| ∟ | ,1977) | 29 |
| Black Oystercatcher | 2 | (| | ,1977) | 29 |
| Western Gull | 1,800 | (| | ,1975-77) | 29 |
| Total | 2,092 | | | | |
| Brandt's Cormorant | X | (| Gaylord,1897) | | 29 |
| Brandt's Cormorant | 1,200 | (| Schreiber,6/17/68) | | 29 |
| Brandt's Cormorant | 1,200 | (| Anderson,6/14/72) | | 29 |
| Brandt's Cormorant | 970 | (| Anderson,1973) | | 29 |
| Brandt's Cormorant | 1,230 | (| Hunt & Leach,5/22/74) | | 29 |
| Brandt's Cormorant | 266 | (| ∟,1975) | | 29 |
| Brandt's Cormorant | 340 | (| ∟,1976) | | 29 |
| Western Gull | 6,000 | (| DeTong,7/29/67) | | 29 |
| Western Gull | 1,200 | (| Schreiber,1968) | | 29 |

X = present

∟ Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.



Section from U.S.G.S.


**San Nicolas
Island**

012 Bird Rock and N.W. San Clemente Is. 33°02'N, 118°35'W

| | | | | | |
|---------------------|-----------|---|-------------------------|--------|----|
| Brandt's Cormorant | 10 | (| ∟ | ,1976) | 29 |
| Black Oystercatcher | 2 | (| | ,1977) | 29 |
| Western Gull | 56 | (| | ,1976) | 29 |
| Total | <u>68</u> | | | | |
| Brandt's Cormorant | X | (| Linton,1907; Jehl,1973) | | 29 |
| Western Gull | X | (| Jehl,1973) | | 29 |
| Western Gull | 62 | (| ∟ | ,1975) | 29 |

X = present

∟ Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.



Section from U.S.C.G.S.
 1:24,000 scale map:
San Clemente Island
 North




013 Seal Cove to Lost Point 32°52'N, 118°31'W to 32°54'10"N,
118°32'20"W


| | | | | | |
|---------------------|----|--|---|-----------|----|
| Brandt's Cormorant | 30 | (| △ | ,1976) | 29 |
| Black Oystercatcher | 2 | (| | ,1976-77) | 29 |
| Western Gull | 56 | (| | ,1976-77) | 29 |
| Xantus' Murrelet | X | (| | ,1976) | 29 |
| Total | 88 | | | | |
| Brandt's Cormorant | X | (Leatherwood & Coulombe,1972; Jones & Jehl,1973) | | | 29 |
| Western Gull | X | (Jehl,1973) | | | 29 |

X = present

△ Investigators are some or all of the following: Hunt, Pitman, Naughton, Winnett, Newman, Kelly, Briggs and Speich. Only the most significant historical data has been summarized here from intensive studies conducted in the Channel Islands, see Hunt et al. 1979 for further information.



Section from U.S.G.S.
1:24,000 scale map:
San Clemente Island
Central







525

Santa Ana

The map on the facing page is an index to the locations of colonies within map 525, Santa Ana. Note that all colonies on the map are not numbered consecutively from north to south, since many previously unreported colonies have been added since initial colony numbers were assigned by Varoujean (1979). On the pages following this map, all colonies are listed sequentially and a detailed map of each is provided.

525 Santa Ana





001 Huntington Beach 33°38'43"N, 117°59'02"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|---------|---------------------|----|
| Least Tern | 140-180 | (Atwood, 4-8/80, L) | 12 |
| Least Tern | 150-180 | (Atwood, 4-8/78, L) | 12 |
| Least Tern | 160-190 | (Atwood, 4-8/79, L) | 12 |

002 Newport Bay 33°38'46"N, 117°53'08"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|---------------------|----|
| Least Tern | 4-10 | (Atwood, 4-8/80, L) | 12 |
| Least Tern | 16-20 | (Atwood, 4-8/78, L) | 12 |
| Least Tern | 12-14 | (Atwood, 4-8/79, L) | 12 |

003 Santa Margarita River 33°13'57"N, 117°24'37"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|------------------------------------|----|
| Least Tern | 80 | (Copper and Belluomini, 4-8/80, L) | 12 |
| Least Tern | 60-80 | (Unitt, 4-8/78, L) | 12 |
| Least Tern | 64-80 | (Unitt, 4-8/78, L) | 12 |

004 Agua Hedionda 33°08'45"N, 117°19'30"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|---------------------|----|
| Least Tern | 16-20 | (Copper, 4-8/80, L) | 12 |
| Least Tern | 22-30 | (Unitt, 4-8/78, L) | 12 |
| Least Tern | 46-56 | (Copper, 4-8/78, L) | 12 |

005 Batiquitos Lagoon 33°05'25"N, 117°17'30"W




Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|---------------------|----|
| Least Tern | 50-60 | (Copper, 4-8/80, L) | 12 |
| Least Tern | 44-54 | (Unitt, 4-8/78, L) | 12 |
| Least Tern | 76-80 | (Copper, 4-8/79, L) | 12 |

006 San Elijo Lagoon 33°00'58"N, 117°16'52"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|----|---------------------|----|
| Least Tern | 34 | (Copper, 4-8/80, L) | 12 |
| Least Tern | 18 | (Unitt, 4-8/78, L) | 12 |
| Least Tern | 24 | (Copper, 4-8/79, L) | 12 |



007 Aliso Creek 33°30'35"N, 117°45'12"W



Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-----|---------------------|----|
| Least Tern | 100 | (Copper, 4-8/80, L) | 12 |
| Least Tern | 30 | (Copper, 4-8/79, L) | 12 |

008 Buena Vista Lagoon 33°10'30"N, 117°21'15"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|---|---------------------|----|
| Least Tern | 2 | (Copper, 4-8/80, L) | 12 |
|------------|---|---------------------|----|







545 San Diego

The map on the facing page is an index to the locations of colonies within map 545, San Diego. Note that all colonies on the map are not numbered consecutively from north to south, since many previously unreported colonies have been added since initial colony numbers were assigned by Varoujean (1979). On the pages following this map, all colonies are listed sequentially and a detailed map of each is provided.

545 San Diego





(001) Los Penasquitos Lagoon 32°55'49"N, 117°14'54"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|---------------------|----|
| Least Tern | 30 | (Copper, 4-8/80, L) | 12 |
| Least Tern | 36-50 | (Unitt, 4-8/78, L) | 12 |
| Least Tern | 32 | (Copper, 4-8/79, L) | 12 |

002 Mission Bay 32°46'42"N, 117°13'46"W


Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|---------|---------------------|----|
| Least Tern | 262-266 | (Copper, 4-8/80, L) | 12 |
| Least Tern | 246-328 | (Unitt, 4-8/78, L) | 12 |
| Least Tern | 222 | (Copper, 4-8/79, L) | 12 |



Least Terns

Photo by Bill Beebe, Santa Monica Evening Look



003 North San Diego Bay 32°44'N, 117°12'W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|--------------|------------|---------------------------------|----|
| Least Tern | 342 | (Copper, 4-8/80, L) | 12 |
| Western Gull | 20 | (Copper & Jorgensen, 4-8/80, L) | 16 |
| Total | <u>362</u> | | |
| Least Tern | 182-190 | (Unitt, 4-8/78, L) | 12 |
| Least Tern | 386-400 | (Copper, 4-8/79, L) | 12 |

004 Silver Strand Beach was previously assigned a catalog number because of Snowy Plover nesting. We have not included information on this species in this report. See Page & Stenzel (1979).




Section from U.S.G.S.
 1:24,000 scale map:
 Point Loma, Calif.


005 South San Diego Bay 32°36'N, 117°07'W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|----------------|---------|-----------------------------|--------|
| Least Tern | 130 | (Copper & Evans, 4-8/80, L) | 12 |
| Forster's Tern | 2,000 | (Copper & Evans, 4-8/80, L) | 12, 16 |
| Elegant Tern | 900 | (Copper & Evans, 4-8/80, L) | 12, 16 |
| Caspian Tern | 900 | (Copper & Evans, 4-8/80, L) | 12, 16 |
| Black Skimmer | 70-80 | (Copper & Evans, 4-8/80, L) | 12, 16 |
| Total | 4,010 | | |
| Least Tern | 74-78 | (Unitt, 4-8/80, L) | 12 |
| Least Tern | 122-140 | (Copper, 4-8/79, L) | 12 |
| Black Skimmer | 2 | (Evans, 1976, L) | 12, 16 |
| Black Skimmer | 6 | (Evans, 4-8/77, L) | 12, 16 |



Caspian Terns



006 Tijuana River Mouth 32°33'25"N, 117°07'48"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|---------------------|----|
| Least Tern | 50 | (Copper, 4-8/80, L) | 12 |
| Least Tern | 16-24 | (Unitt, 4-8/78, L) | 12 |
| Least Tern | 50-60 | (Copper, 4-8/79, L) | 12 |

007 Del Mar 32°58'10"N, 117°14'45"W



Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|----|-------------------|----|
| Least Tern | 10 | (Denson, 1980, L) | 12 |
|------------|----|-------------------|----|

008 Sweetwater River 32°38'30"N, 117°06'35"W

Least Terns are an endangered species. Populations of Least Terns are surveyed annually. For the most current information contact the California Department of Fish and Game.

| | | | |
|------------|-------|---------------------|----|
| Least Tern | 24-30 | (Copper, 4-8/80, L) | 12 |
| Least Tern | 94 | (Unitt, 4-8/78, L) | 12 |
| Least Tern | 48-56 | (Copper, 4-8/79, L) | 12 |



(009) La Jolla 32°51'N, 117°15'55"W

| | | | |
|--------------------|-----------|--------------------|----|
| Brandt's Cormorant | 6 | (Everett, 1980, L) | 16 |
| Western Gull | 4 | (Everett, 1980, L) | 16 |
| Total | <u>10</u> | | |



ARD 79

REFERENCES

Italicized numbers in the margin (1, 2, etc.) correspond to italicized numbers in the maps and tables and in the breeding chronology figures in the species accounts.

- Ainley, D.G. , pers. comm. Point Reyes Bird Observatory, 4990 Shoreline Highway, Stinson Beach, CA 94970.
- Ainley, D.G., 1976. The occurrence of seabirds in the coastal region of California. *Western Birds* 7:33-68.
- 1 Ainley, D.G., R.J. Boekelheide, T.J. Lewis, H. R. Huber, C.S. Strong, and S. H. Morrell. Unpubl. data on Farallon Islands, 1971-1980. Point Reyes Bird Observatory, 4990 Shoreline Highway, Stinson Beach, CA 94970.
- Ainley, D.G., C.R. Grau, S.H. Morrell, T.E. Roudebush, R.R. LeValley, H.R. Huber, C.S. Strong, and T.A. Wooton. 1979. Influence of petroleum on egg formation and embryonic development in seabirds. Final Report. NOAA, Juneau, Alaska.
- 2 Ainley, D.G., and T.J. Lewis. 1974. The history of Farallon Island marine bird population, 1854-1972. *Condor* 76:432-446.
- Ainley, D.G., T.J. Lewis and S. Morrell. 1976. Molt in Leach's and Ashy Storm-Petrels. *Wilson Bull.* 88:76-95.
- Ainley, D.G., S. Morrell, and T.J. Lewis. 1974. Patterns in the life histories of storm petrels on the Farallon Islands. *Living Bird* 13:295-312.
- Ainley, D.G., and T.O. Osborne. 1972. A Marin County, California, breeding site for Ashy Petrels. *Calif. Birds* 3:71.
- Ainley, D.G., and G.A. Sanger. 1979. Trophic relations of seabirds in the northeastern Pacific Ocean and Bering Sea. In J.C. Bartonek and D.N. Nettleship (eds.), *Conservation of marine birds of northern North America*. U.S. Dept. of Interior, Fish and Wildl. Serv., Wildl. Res. Rep. 11.
- 3 Ainley, D.G., and M.C. Whitt. 1974. Number of marine birds breeding in Northern California. *Western Birds* 4:65-70.
- Ainslie, J.A., and R. Atkinson. 1937. On the breeding habits of Leach's Fork-tailed Petrel. *Brit. Birds* 30:234-238.
- Albers, P.H., and R.C. Szaro. 1978. Effects of Number 2 fuel oil on Common Eider eggs. *Mar. Poll. Bull.* 9:138-139.
- Aldrich, E.C. 1938. A recent oil-pollution and its effects on the waterbirds of the San Francisco Bay area. *Bird Lore* 40:110-114.
- 4 Anderson, D.W., pers. comm. Wildlife-Fisheries, Univ. of Cal., Davis, CA 95616.
- Anderson, D.W., and I.T. Anderson. 1976. Distribution and status of Brown Pelicans in the California Current. *Amer. Birds* 30:3-12.
- Anderson, D. W., F. Gress, K.F. Mais, and P.R. Kelly. 1980. Brown Pelicans as anchovy stock indicators and their relationships to commercial fishing. *CALCOFI Reps.* XXI : 54-61.
- Anderson, D.W., J.R. Jehl, Jr., R.W. Riseborough, L.A. Woods, Jr., L.R. DeWeese, and W.G. Edgecomb. 1975. Brown Pelicans: improved reproduction off the southern California coast. *Science* 190:806-808.
- Anderson, D.W., and J.O. Keith. 1980. The human influence on seabird nesting success: conservation implications. *Biol. Conserv.* 18:65-80.
- Anthony, A.W. 1898. Petrels of Southern California. *Auk* 40:140-144.
- Ashmole, N.P. 1971. Sea bird ecology and the marine environment. In D.S. Farner, J.R. King, and K.C. Parker (eds.), *Avian biology*. Vol I. Academic Press, New York.
- 5 Ayers, D. 1975. Reproductive performance of the Double-crested Cormorant in Humboldt Bay, California. M.S. thesis, Humboldt State Univ., Arcata, CA .

- 6 Baldridge, A. pers. comm. Hopkins Marine Station, Pacific Grove, CA 93950.
- 7 Baldridge, A. 1973. The status of the Brown Pelican in the Monterey region of California: past and present. *Western Birds* 4:93-100.
- Baltz, D.M., and G.V. Morejohn. 1976. Evidence from seabirds of plastic and particle pollution off central California. *Western Birds* 7:111-112.
- Baltz, D.M., and G.V. Morejohn. 1977. Food habits and niche overlap of seabirds wintering on Monterey Bay. *Auk* 94:526-543.
- Bang, B.G. 1966. The olfactory apparatus of the tube-nosed birds (Procellariiformes). *Acta Anat.* 65:391-415.
- Bartholomew, G.A., Jr., and W.R. Dawson. 1954. Temperature regulation in young pelicans, herons, and gulls. *Ecology* 35:466-477.
- Bent, A.C. 1922. Life histories of North American petrels and pelicans and their allies. U.S. Natl. Mus. Bull. 121.
- Bent, A.C. 1946. Life histories of North American diving birds. U.S. Natl. Mus. Bull. 107.
- Benz, C., and R. Garrett. 1978. Colony development and nesting behavior of Double-crested and Pelagic Cormorants. Abstract. P.S.G. Bull. 5-82.
- Bergstrom, E.A. 1952. Extreme old age in terns. *Bird-Banding* 23:72-73.
- Berkner, A.B., pers. comm. Inter. Bird Rescue Resear. Center, Aquatic Park, Berkeley, CA 94710.
- 8 Binford, L.C. 1980. Heermann's Gull invades Alcatraz. P.R.B.O. newsletter 51.
- 9 Binford, L.C., B.G. Elliott, and S.W. Singer. 1975. Discovery of a nest and the downy young of the Marbled Murrelet. *Wilson Bull.* 87:303-319.
- Birkhead, T.R., and D.N. Nettleship. 1980. Census methods for murrens, *Uria* species: a unified approach. Occas. Pap. No. 43, Canad. Wildl. Serv., Ottawa.
- Boersma, P.D., and N.T. Wheelwright. 1979. The costs of egg neglect in the Procellariiformes: reproductive adaptations in the Fork-tailed Storm Petrel. *Condor* 81:157-165.
- 10 Boersma, P.D., N.T. Wheelwright, M.K. Nerini, and E.S. Wheelwright. 1980. The breeding biology of the Fork-tailed Storm Petrel (*Oceanodroma furcata*). *Auk* 97:268-282.
- Bolin, R.L., and D.P. Abbot. 1963. Studies on the marine climate and phytoplankton of the central coastal area of California, 1954-1960. Calif. Coop. Ocean. Fish. Invest. Rept. 9:23-45.
- Bourne, W.R.P. 1968. Oil pollution and bird populations. In J.D. Carthy and D.R. Arthur (eds.), *The biological effects of oil pollution on natural communities*. Field studies Suppl. No. 2.
- Bourne, W.R.P. 1970. Oil pollution and bird conservation. *Biol. Conserv.* 2:300-302.
- Bourne, W.R.P. 1972. Threats to seabirds. *Intl. Council Bird Pres. Bull.* 11:200-218.
- 11 Briggs, K.T., pers. comm. Center for Coastal Marine Studies, University of California, Santa Cruz, CA 95064
- Brown, R.G.B. 1970. Fulmar distribution: a Canadian perspective. *Ibis* 112:44-51.
- Brown, R.G.B., D.N. Nettleship, P. Germain, C.E. Tull, and T. Davis. 1975. Atlas of eastern Canadian seabirds. Canadian Wildl. Serv. Info. Canada. Ottawa.
- 12 California Dept. of Fish and Game, Wildlife Investigations, Sacramento, CA 95814.
- Campbell, R.W. 1977. Use of man-made structures as nest sites by Pigeon Guillemots. *Can. Field Nat.* 91:193-194.
- 13 Chambers, J.R., Jr. 1979. Notes on the bird life in the vicinity of Diablo Canyon. Unpubl. ms.
- Chatto, T. pers. comm. U.S. Fish and Wildlife Service. FAO, 791 8th Street, Suite S, Arcata, CA 95521
- Clapp, R.B., and C.D. Hackman. 1969. Longevity record for a breeding Great Frigatebird. *Bird-Banding* 40:47.

- Clapp, R.B., and F.C. Sibley. 1966. Longevity record for some central Pacific seabirds. *Bird-Banding* 37:193-197.
- Clark, R.B. 1969. Oil pollution and the conservation of seabirds. Pp. 76-112 in *Proc. Intl. Conf. Oil Poll.*
- Clark, R.B., and R.J. Kennedy. 1968. Rehabilitation of oiled seabirds. Report Adv. Comm. Oil Poll. Sea. Dept. Zool., Univ. Newcastle upon Tyne.
- Clay, C.I. 1911. Some diving notes on cormorants. *Condor* 13:138.
- 14 Clay, C.I. unpubl. field notes. Humboldt State Univ. Library, Arcata, CA.
- 15 Cogswell, H.W., pers. comm. 1548 East Avenue, Hayward, CA 94541
- 16 Copper, E., pers. comm. 920 First Street, Coronado, CA 92118
- Coon, C., P.H. Albers, and R.C. Szaro. 1979. Number 2 fuel oil decreases embryonic survival of Great Black-backed Gulls. *Bull. Envir. Contam. Toxicol.* 21:152-156.
- Coulter, M.C., and R.W. Riseborough. 1973. Shell-thinning in eggs of the Ashy Petrel (*Oceanodroma homochroa*) from the Farallon Islands. *Condor* 75:254-255.
- Crocker, A.D., J. Cronshaw, and W.N. Holmes. 1974. The effect of crude oil on intestinal absorption in ducklings (*Anas platyrhynchos*). *Environ. Pollut.* 7: 165-177.
- Croxall, J.P. 1975. The effect of oil on nature conservation, especially birds. In H.R. Cole (ed.), *Petroleum and the continental shelf of northwest Europe*. Vol. 2. Halsted Pres, United Kingdom.
- Dawson, W.L. 1911. Another fortnight on the Farallones. *Condor* 13:171-183.
- 17 Dawson, W.L. 1923. The birds of California. South Moulton Co., San Francisco.
- DeGange, A.R., pers. comm. U.S.F.W.S. 1011 E. Tudor Road, Anchorage, AK 99503.
- DeSante, D., and D.G. Ainley. 1980. The avifauna of the south Farallon Islands, California. *Studies in avian biology*, No. 4. Cooper Ornith. Soc.
- DeWeese, L.R., and D.W. Anderson. 1976. Distribution and breeding biology of Craveri's Murrelet. *San Diego Soc. Nat. Hist. Trans.* 18(9):155-168.
- 18 Drent, R.H. 1965. Breeding biology of the Pigeon Guillemot, *Cepphus columba*. *Ardea* 53:99-160.
- Drent, R., G.F. van Tets, F. Tompa, and K. Vermeer. 1964. The breeding birds of Mandarte Island, British Columbia. *Canad. Field-Nat.* 78:208-263.
- Drury, W.H. 1979. Population dynamics in northern marine birds. In J.C. Bartonek and D.N. Nettleship (eds.), *Conservation of marine birds of northern North America*. U.S. Dept. of Interior, Fish and Wildl. Serv., Wildl. Res. Rep. 11.
- Evans, W.E., J.E. Jehl, Jr., and C.F. Cooper (eds.). 1979. Potential impact of space shuttle sonic booms on the biota of the California Channel Islands: literature review and problem analysis. U.S. Air Force, Space and Missile System Org., Contract F 04701-78-C-0060.
- Follett, W.I., and D.G. Ainley. 1976. Fishes collected by Pigeon Guillemots. (*Cepphus columba Pallas*), nesting on southwest Farallon Islands, California. *Calif. Fish and Game* 62:28-31.
- 19 Frame, M.A. 1972. Cormorant nesting, San Luis Obispo County, California, 1972. Calif. Dept. Fish and Game, Spec. Wildl. Invest. Prog. Rept., Proj. W-54-R-4.
- Gill, R.E., Jr. 1972. South San Francisco Bay breeding bird survey, 1971. Calif. Dept. Fish and Game, Wildl. Mgmt. Branch, Admin. Rep. 72-6.
- Gould, G.I., 1973. California Clapper Rail survey, 1973. Calif. Dept. Fish and Game, Spec. Wildl. Invest., Project W-54-R, Job II-10, final rep.
- Graham, F. 1969. Ear pollution. *Audubon* 71(3):34-39.

- Graham, F.G., Jr. 1980. To kill an albatross. *Audubon* 82:8-12.
- Grau, C.R., T. Roudybush, J. Dobbs, and J. Wathen. 1977. Altered yolk structure and reduced hatchability of eggs from birds fed single doses of petroleum oils. *Science* 195:779-781.
- 20 Gress, F., pers. comm. Wildlife-Fisheries Dept., Univ. of Cal. Davis, Davis, CA 95616.
- 21 Gress, F. 1970. Reproductive status of the California Brown Pelican in 1970, with notes on breeding biology and natural history. Calif. Dept. of Fish and Game, Wildl. Mgmt. Branch, Admin. Rep. 70-6.
- Gress, F., P.R. Kelly, D.B. Lewis, and D.W. Anderson. In prep. Feeding activities and prey preference of Brown Pelicans breeding in the southern California Bight. Submitted to Calif. Fish and Game.
- Gress, F., R.W. Riseborough, D.W. Anderson, L.F. Kiff, and J.R. Jehl, Jr. 1973. Reproductive failures of Double-crested Cormorants in southern California and Baja California. *Wilson Bull* 85:197-208.
- Gress, F., R.W. Riseborough, and F.C. Sibley. 1971. Shell-thinning in eggs of the Common Murre (*Uria aalge*) from the Farallon Islands, California. *Condor* 73:368-369.
- Grinnell, J. 1897. Petrels of Sitka, Alaska. *Nidologist* 4:76-78.
- 22 Gross, W.A.O. 1935. The life history cycle of Leach's Petrel (*Oceanodroma leucorhoa leucorhoa*) on the outer sea islands of the Bay of Fundy. *Auk* 52:382-399.
- Grubb, T.C., Jr. 1973. Colony location by Leach's Storm Petrel. *Auk* 90:78-82.
- Grubb, T.C., Jr. 1974. Olfactory navigation to the nesting burrow in Leach's Storm Petrel (*Oceanodroma leucorhoa*). *Anim. Behav.* 22:192-202.
- 23 Harris, S.W., pers. comm. Dept. of Wildlife, Humboldt State Univ., Arcata, CA 95521.
- 24 Harris, S.W. 1974. Status, chronology, and ecology of nesting storm petrels in northwestern California. *Condor* 76:249-261.
- 25 Harrison, C. 1978. A field guide to the nests, eggs, and nestlings of North American birds. William Collins Sons and Co., Ltd., Glasgow.
- Hartung, R. 1965. Some effects of oiling on reproduction of ducks. *J. Wildl. Mgmt.* 29:872-874.
- Hartung, R. 1967. Energy metabolism in oil-covered ducks. *J. Wildl. Mgmt.* 31:798-804.
- Hartwick, E.B. 1974. Breeding ecology of the Black Oystercatcher (*Haematopus bachmani* Audubon). *Syesis* 7:83-92.
- Hartwick, E.B. 1976. Foraging strategy of the Black Oystercatcher, *Haematopus bachmani* Audubon. *Can. J. Zool.* 54:142-155.
- 26 Harvey, T., pers comm. 543 Crofton Ave., Oakland, CA 94610.
- Hatch, S.A., T.W. Peterson, and P.J. Gould. 1979. Reproductive ecology of seabirds at Middleton Island, Alaska. In Environmental assessment of the Alaskan continental shelf. Annual reports of principal investigators. Natl. Ocean. Atmos. Admin. Environ. Res. Lab., Boulder, CO.
- Hatler, D.F., R.W. Campbell, and A. Dorst. 1978. Birds of Pacific Rim National Park. British Columbia Provincial Museum. occ. paper no. 20.
- Hays, H., and R.W. Riseborough. 1972. Pollutant concentrations in abnormal young terns from Long Island Sound. *Auk* 89:19-35.
- Heath, H. 1915. Birds observed on Forrester Island, Alaska during the summer of 1913. *Condor* 17:20-41.
- 27 Helbing, G.L. 1977. Maintenance activities of the Black Oystercatcher, *Haematopus bachmani* Audubon, in northwestern California. M.S. thesis, Humboldt State Univ., Arcata, CA.

- Hoffman, W., J.A. Wiens, and J.M. Scott. 1978. Hybridization between gulls (*Larus glaucescens* and *L. occidentalis*) in the Pacific Northwest. *Auk* 95:441-458.
- Hubbs, C.L. 1948. Changes in the fish fauna of western North America correlated with changes in ocean temperatures. *J. Mar. Res.* 7:459-482.
- Hubbs, C.L., A.L. Kelly, and C. Limbaugh. 1970. Diversity in feeding by Brandt's Cormorants near San Diego. *Calif. Fish and Game* 53:156-165.
- Huber, L.N. 1968. Preliminary report of San Miguel Island and adjacent islets, Prince and Castle. Unpubl. ms. on file at U.S. Natl. Mus. Nat. Hist., Wash., DC.
- 28 Hunt, G.L., Jr., pers. comm. School of Biological Sciences, University of California, Irvine, Irvine, CA 92717.
- Hunt, G.L., Jr. 1972. Influence of food distribution and human disturbance on the reproductive success of Herring Gulls. *Ecology* 53:1051-1061.
- Hunt, G.L., Jr., and J.L. Butler. 1980. Reproductive ecology of Western Gulls and Xantus' Murrelets with respect to food resources in the southern California bight. *CalCOFI rep.*, Vol. XXI:62-67.
- Hunt, G.L., Jr., and M.W. Hunt. 1975. Reproductive ecology of the Western Gull: the importance of nest space. *Auk* 92:270-279.
- Hunt, G.L., Jr., and M.W. Hunt. 1977. Female-female pairing in Western Gulls (*Larus occidentalis*) in southern California. *Science* 196:1466-1467.
- 29 Hunt, G.L., Jr., R.L. Pitman, M. Naughton, K. Winnet, A. Newman, P.R. Kelly, and K.T. Briggs. 1979. Distribution, status, reproductive ecology, and foraging habits of breeding seabirds. In Summary of marine mammal and seabird surveys of the southern California Bight area, 1975-1978. U.S. Dept. of Interior, Bur. of Land Mgmt., Los Angeles.
- Huntington, C.A. 1963. Population dynamics of Leach's petrel, *Oceanodroma leucorhoa*. *Proc. Intl. Ornithol. Congr.* 13:701-705.
- 30 Jameson, R., pers. comm. U.S. Fish and Wildl. Service, P.O. Box 67, San Simeon, CA 93452.
- Jehl, J.R., Jr., pers. comm. 2022 Willow St., San Diego, CA 92106.
- Jehl, J.R., Jr. 1973. Studies of a declining population of Brown Pelicans in northwestern Baja California. *Condor* 75: 69-79.
- Jehl, J.R., Jr., and S.I. Bond. 1975. Morphological variation and species limits in murrelets of the genus *Endomychura*. *San Diego Soc. Nat. Hist. Trans.* 18:9-23.
- Johnson, R.A. 1941. Nesting behavior of the Atlantic Murre. *Auk* 58:153-163.
- Kadlec, J.A., and W.H. Drury. 1968. Structure of the New England Herring Gull population. *Ecology* 49: 644-676.
- Kelly, P., pers. comm. California Department of Fish and Game, 350 Goldenshore, Long Beach, CA 90802.
- 31 Kiff, L., pers. comm. Western Foundation of Vert-Zoology., 1100 Glendon Avenue, Los Angeles, CA 90024.
- Kiff, L., In press. Eggs of the Marbled Murrelet. *Wilson Bull.*
- King, J.G., and G.A. Sanger. 1978. Oil vulnerability index for marine-oriented birds. Pp. 227-239 in J.C. Bartonek and D.N. Nettleship (eds.), Conservation of marine birds in northern North America. U.S. Dept. of Interior, Fish and Wildl. Serv., Wildl. Res. Rep. 11.
- King, K.A., and C.A. Lefever. 1979. Effects of oil transferred from incubating gulls to their eggs. *Mar. Poll. Bull.* 10:319-320.
- Krasnow, L.D., G.A. Sanger, and D.W. Wiswar. 1978. Nearshore feeding ecology of marine birds in the Kodiak area, 1978. In C.J. Lensink, P.J. Gould, and G.A. Sanger (eds.), Population dynamics and trophic relationships of marine birds in the Gulf of Alaska. Environmental assessment of the Alaska continental shelf. Annual reports of principal investigators. Natl. Ocean. Atmos. Admin. Environ. Res. Lab., Boulder, CO.

- Kurland, L., S. Faro, and H. Siedler. 1960. Minamata disease. *World Neurology*, 1:370-391.
- Kury, C.R., and M. Gochfield. 1975. Human interference and gull predation in cormorant colonies. *Biol. Conserv.* 8:23-34.
- Kuzyakin, A.P. 1963. On the biology of the Long-billed Murrelet. *Ornitologia* 6:315-320 (Eng. trans. in Josselyn Van Tyne Memorial Library, Univ. Michigan, Ann Arbor).
- Lack, D. 1954. *The natural regulation of animal numbers.* Oxford Univ. Press, London.
- Lensink, C.J., P.J. Gould, C.S. Harrison and D. Forsell. 1978. Distribution and abundance of marine birds - south and east Kodiak Island waters. Pp. 614-710 in *Environmental assessment of the Alaskan continental shelf, Annual Rept. 2.* U.S. Dept. Commerce and U.S. Dept. Interior, Outer Continental Shelf Environmental Assessment Program.
- Leschner, L.L. 1976. *The breeding biology of the Rhinoceros Auklet on Destruction Island.* M.S. thesis, Univ. Washington, Seattle.
- 32 LeValley, R., pers. comm. 1876 Ocean Drive, McKinleyville, CA 95521.
- MacArthur, R.H., and E.O. Wilson. 1967. *The theory of island biogeography.* Monographs in Pop. Biol. 1. Princeton Univ. Press.
- MacCall, A.D. 1974. The mortality rate of *Engraulis mordax* in southern California. *Mar. Res. Comm., Calif. Coop. Ocean. Fish., Invest. Rept.* 17: 131-135.
- 33 Manuwal, D.A. 1974a. The natural history of Cassin's Auklet (*Ptychoramphus aleuticus*). *Condor* 76:421-431.
- Manuwal, D.A. 1974b. The incubation patches of Cassin's Auklet. *Condor* 76:481-484.
- Manuwal, D.A. 1978. Effect of man on marine birds: a review. *Proc. J.S. Wright Conf. 4th (Purdue Univ.)*, 140-160.
- McCaskie, G. 1980. Southern Pacific coast regional report. *Amer. Birds* 34(3).
- McGill, P.A., and M.E. Richmond. 1979. Hatching success of Great Black-backed Gull eggs treated with oil. *Bird-Banding* 50:108-113.
- Miller, D., pers. comm. California Dept. of Fish and Game, 2201 Garden Road., Monterey, CA 93940.
- Moffitt, J., and R.T. Orr. 1938. Recent disastrous effects of oil pollution on birds in the San Francisco Bay region. *Calif. Fish and Game* 24:239-244.
- Morse, D.H., and C.W. Buchheister. 1979. Nesting patterns of Leach's Storm-Petrels on Matinicus Rock, Maine. *Bird-Banding* 50:145-158.
- Murphy, R.C. 1936. *Oceanic birds of South America.* Vol. 2. Amer. Mus. Nat. Hist. New York.
- Nelson, E.W., and E.A. Goldman. 1931. Six new White-footed Mice (*Peromyscus maniculatus* group) from islands off the Pacific coast. *J. Wash. Acad. Sci.* 21:530-535.
- Nettleship, D.N. 1972. Breeding success of the Common Puffin (*Fratercula arctica* L.) on different habitats at Great Island, Newfoundland. *Ecol. Mono.* 42:239-268.
- Nettleship, D.N. 1976. Census techniques for seabirds of arctic and eastern Canada. *Occas. Pap. No. 25.* Canadian Wildl. Serv., Ottawa.
- Nettleship, D.N. 1977. Seabird resources of eastern Canada: status, problems, and prospects. In T. Mosquin and C. Suchal (eds.). *Proceedings of the Symposium on Canada's Threatened Species and Habitats.* Canadian Nature Fed., Ottawa.
- Nisbet, I.C.T. 1973. Terns in Massachusetts: present numbers and historical changes. *Bird-Banding* 44:27-55.
- Nysewander, D.R. 1977. *Reproductive success of the Black Oystercatcher in Washington State.* M.S. thesis, Univ. Washington, Seattle.

- Nysewander, D.R., and D.B. Barbour. 1979. The breeding biology of marine birds associated with Chiniak Bay, Kodiak Island. In Environmental assessment of the Alaskan continental shelf. Annual reports of principal investigators. Natl. Ocean. Atmos. Admin. Environ. Res. Lab., Boulder, CO.
- Ogi, H., and T. Tsujita. 1973. Preliminary examination of stomach contents of murrets (*Uria spp.*) from the eastern Bering Sea and Bristol Bay, June-August, 1970 and 1971. Jap. Jour. Ecol. 23: 201-209.
- Ogi, H., and T. Tsujita. 1977. Food and feeding habits of Common Murres and Thick-billed Murres in the Okhotsk Sea in summer, 1972 and 1973. Pp. 459-517 in Res. Inst. North Pac. Fish. Special Volume. Hokkaido Univ.
- 34 Osborne, T.O.. pers. comm. Alaska Dept. Fish and Game, Box 667, Petersburg, AK 99833.
- 35 Osborne, T.O. 1972. Ecology and avian use of the coastal rocks of Northern California. M.A. Thesis. Humboldt State Univ., Arcata, CA.
- 36 Osborne, T.O., and J.G. Reynolds. 1971. California seabird breeding ground survey. Calif. Dept. Fish and Game, Admin. Rep. 71-73.
- Page, G.W., and L.E. Stenzel (eds.). 1979. The status of breeding Snowy Plovers in California. Calif. Dept. Fish and Game, Nongame Wildl. Invest. Rep.
- 37 Palmer, R.S. (ed.). 1962. Handbook of North American birds. Vol. I, loons through flamingos. Yale Univ. Press, New Haven.
- Patten, S.M., and L.R. Patten. 1977. Effects of petroleum exposure on hatching success and incubation behavior of Glaucous-winged Gulls (*Larus glaucescens*) in the Northeast Gulf of Alaska. Pp. 418-445 in Environmental assessment of the Alaskan continental shelf. Annual reports of Principal Investigators Vol. III: Natl. Ocean. Atmos. Admin. Environ. Res. Lab., Boulder, CO.
- Peakall, D.B. 1970. Pesticides and the reproduction of birds. Sci. Amer. 222: 72-78.
- Peakall, D.B. 1975. Physiological effects of chlorinated hydrocarbons on avian species. Pp. 343-360 in R. Haque and V.H. Freed (eds.), Environmental dynamics of pesticides. Plenum Publ. Corp., New York.
- Pitman, R.L. and S.M. Speich. 1976. Black Storm-Petrel breeds in the United States. Western Birds 7:71.
- Portnoy, J.W. 1977. Nesting colonies of seabirds and wading birds--coastal Louisiana, Mississippi, and Alabama. U.S. Dept. of Interior, Fish and Wildl. Serv., Biol. Serv. Prog. FWS/OBS-77/07.
- Radovich, J. 1979. Managing pelagic schooling prey species. Pp. 365-375, in H. Clepper (ed.), Predator-prey systems in fisheries management. Sport. Fish. Inst., Wash., D.C.
- Rauzon, M., pers. comm. 627 N. Forest, Bellingham, WA 98225.
- 38 Richardson, F. 1961. Breeding biology of the Rhinoceros Auklet on Protection Island, WA. Condor 63:456-473.
- Richdale, L.E., and J. Warham. 1973. Survival, pair bond retention and nest site tenacity in Buller's Mollymawk. Ibis 115:257-263.
- Rijke, A.M. 1968. The water repellency and feather structure of cormorants, Phalacrocoracidae. J. Exp. Biol. 48:185-189.
- Riseborough, R.W., D.B. Menzel, D.J. Martin, and H.S. Olcott. 1967. DDT residues in Pacific seabirds: a persistent insecticide in marine food chains. Nature 216:589-591.
- Riseborough, R.W., F.C. Sibley, and M.N. Kirven. 1971. Reproductive failure of the Brown Pelican on Anacapa Island in 1969. Amer. Birds 25: 8-9.
- Robertson, I. 1971. The influence of brood size on reproductive success in two species of cormorant, *P. auritus* and *P. pelagicus*, and its relation to the problem of clutch size. M.S. thesis, U. British Columbia, Vancouver.
- 39 Robertson, I. 1974. The food of nesting Double-crested and Pelagic Cormorants at Mandarte Island, British Columbia, with notes on feeding ecology. Condor 76:346-348.

- Rothstein, S.I. 1973. Plastic particle pollution of the surface of the Atlantic Ocean: evidence from a seabird. *Condor* 75:344-346.
- Romero, P.D. 1971. Anaheim Bay study, July 1970 to 1971. Calif. Dept. Fish and Game, Spec. Wildl. Invest., Project W-54-R, Job III-12, final rep.
- Salomonsen, F. 1979. Marine birds in the Danish Monarchy and their conservation. In J.C. Bartonek and D.N. Nettleship (eds.), Conservation of marine birds in northern North America. U.S. Dept. of Interior, Fish and Wildl. Serv., Wildl. Res. Rept. 11.
- Sano, O. 1978. Seabirds entangled in salmon driftnets. *Enyo* 30: 1-4.
- Schaefer, M.B. 1970. Men, birds, and anchovies in the Peru Current - dynamic interactions. *Trans. Amer. Fish. Soc.* 99: 461-467.
- Schreiber, R.W., and R.L. DeLong. 1969. Brown Pelican status in California. *Audubon Field Notes* 23(1):57-59.
- Schreiber, R.W., and R.W. Riseborough. 1972. Studies of the Brown Pelican. No. 1: Status of Brown Pelican populations in the United States. *Wilson Bull.* 84:119-135.
- Schwartzlose, R. 1963. Nearshore currents of the western United States and Baja California as measured by drift bottles. *Calif. Coop. Fish. Invest. Repts.* 9:15-22.
- Scott, J.M. 1973. Resource allocation in four syntopic species of marine diving birds. Ph.D. diss. Oregon State Univ. Corvallis.
- Scott, J.M., W. Hoffman, D. Ainley, C.F. Zeillemaker. 1974. Range expansion and activity patterns in Rhinoceros Auklets. *Western Birds* 5:13-20.
- Sealy, S.G. 1974. Breeding phenology and clutch size in the Marbled Murrelet. *Auk* 91:10-23.
- 40 Sealy, S.G. 1975a. Aspects of the breeding biology of the Marbled Murrelet in British Columbia. *Bird-Banding* 46:141-154.
- Sealy, S.G. 1975b. Feeding ecology of the Ancient and Marbled Murrelets near Langara Island, British Columbia. *Can. J. Zool.* 53:418-433.
- Sibley, C.G. 1953. Forster's Terns breeding on San Francisco Bay, California. *Condor* 55:278-279.
- Simon, T.R. 1980. Discovery of a ground-nesting Marbled Murrelet. *Condor* 82:1-9.
- Singer, S.W., and D.R. Verardo. 1975. The Murrelet's nest discovered. *Pacific Discovery* 28:18-21.
- Smail, J., D.G. Ainley, and H. Strong. 1972. Notes on birds killed in the 1971 San Francisco oil spill. *Calif. Birds* 3:25-32.
- Sorenson, F., pers. comm. U.S. Fish and Wildlife Service, P.O. Box 67, San Simeon, CA 93452.
- Sowls, A.L., S.M. Hatch, and C.J. Lensink. 1978. Catalog of Alaskan Seabird Colonies. U.S. Dept. of Interior, Fish and Wildl. Ser., Biol. Ser. Prog. FWS/OBS-78/78.
- Speich, S., and D.A. Manuwal. 1974. Gular pouch development and population structure of Cassin's Auklet. *Auk* 91:291-306.
- Stager, K.E. 1967. Avian olfaction. *Am. Zool.* 7:415-419.
- Stahlecker, D.W. and A.W. Alldredge. 1976. The impact of an underground nuclear fracturing experiment on cliff nesting raptors. *Wilson Bull.* 88:151-154.
- Strachan, G.J., pers. comm. Prairie Creek Redwoods State Park, Orick, CA 95555.
- Straughan, D. 1970. Ecological effects of the Santa Barbara oil spill. Pp. 173-182 in R.W. Holmes and F.A. DeWitt (eds). Santa Barbara Oil Symposium, Dec. 16-18, 1970, at Univ. California, Santa Barbara.

- Straughan, D. 1971. Oil pollution and seabirds. Pp. 307-312 in Biological and oceanographic survey of the Santa Barbara Channel oil spill, 1969-1970. Vol. 1, Allan Hancock Foundation, Univ. Southern Calif.
- Sumner, L.E. 1939. An investigation of Santa Barbara, Anacapa, and San Miguel Islands. Unpubl. ms. on file Channel Island Natl. Monument.
- 41 Thoresen, A.C. 1964. The breeding behavior of the Cassin's Auklet. *Condor* 66:456-476.
- Thoresen, A.C., and E.S. Booth. 1958. Breeding activities of the Pigeon Guillemot, *Cephus columba columba Pallas*. Dept. Biol. Sci., Walla Walla College, Walla Walla, WA, Publ. 23.
- Threlfall, W. 1974. Foot injuries in Leach's Storm Petrels. *Wilson Bull.* 86:65-67.
- Tickell, W.L.N. 1968. The biology of the great albatrosses, *Diomedea exulans* and *Diomedea epomorpha*. *Antarctic Res. Ser.* 12:1-55.
- Tuck, L.M. 1960. The murre. Their distribution, populations, and biology: a study of the genus *Uria*. *Canad. Wildf. Serv., Monogr. Ser.* 1. Ottawa, Canada.
- Tull, C.E., P. Germain, and A.W. May. 1972. Mortality of Thick-billed Murres in the west Greenland salmon fishery. *Nature* 237: 42-44.
- U.S. Air Force. 1978. Final environmental impact statement, space shuttle program. Vandenberg Air Force Base, CA.
- 42 U.S. Fish and Wildlife Service. Field notes. See appendix A.
- Varoujean, D., pers. comm. Oregon Inst. Marine Biology, Charleston, OR 97420.
- 43 Varoujean, D.H. 1979. Seabird colony catalog: Washington, Oregon, and California. U.S. Dept. of Interior, Fish and Wildl. Serv.
- Varoujean, D.H. and R.L. Pitman. 1979. Oregon seabird colony survey, 1979. U.S. Dept. of Interior, Fish and Wildl. Service. 150 pp.
- Veirs, S.D., pers. comm. Research Scientist, Redwood Nat. Park, Box 55, Arcata, CA 95521.
- Vermeer, K. 1963. The breeding ecology of the Glaucous-winged Gull (*Larus glaucescens*) on Mandarte Island, British Columbia. *Occas. Pap. British Columbia Prov. Mus.* 13:1-104.
- Vermeer, K., and D.B. Peahall. 1977. Toxic chemicals in Canadian fish-eating birds. *Mar. Poll. Bull.* 8:205-210.
- Vermeer, R., and K. Vermeer. 1974. Oil pollution of birds: an abstracted bibliography. *Can. Wildl. Serv., Pesticide Sec., Manu. Rept. No.* 29.
- Webster, J.D. 1941. The breeding of the Black Oystercatcher. *Wilson Bull.* 53:141-156.
- Welty, J.C. 1962. The life of birds. W.B. Saunders Co. 546 p.
- Wiens, J.A., D. Heinemann, and W. Hoffman. 1978. Community structure, distribution and inter-relationships of marine birds in the Gulf of Alaska. U.S. Dept. Comm., U.S. Dept. Interior. Outer Continental Shelf Environmental Assessment Program. Final Rept. 3:1-178.
- Wilbur, H.M. 1969. The breeding biology of Leach's Petrel, *Oceanodroma leucorhoa*. *Auk* 86:433-442.
- Willett, G. 1910. A summer trip to the northern Santa Barbara Island. *Condor* 12:170-174.
- Willett, G. 1912. Birds of the Pacific slope of southern California. *Pacific Coast Avifauna* 7:1-122.
- Willett, G. 1915. Summer birds of Forrester Island. *Auk* 32:295-305.
- Willett, G. 1933. Birds of southwestern California- in part (Petrels, Pelecaniformes, and Alcidae). *Pacific Coast Avifauna*, 21.

- Williams, A.S., S.C. Brundage, J.M. Harris, and D.C. Smith. 1978. Saving oiled seabirds: a manual for cleaning and rehabilitating oiled waterfowl. Amer. Petroleum Inst., Wash. DC.
- Williams, L. 1927. California Brown Pelicans nesting at Point Lobos, Monterey County, California. Condor 33:66-69.
- Williams, L. 1931. Further notes on California Brown Pelicans at Point Lobos, California. Condor 33:66-69.
- Winnett, K.A., K.G. Murray, and J.C. Wingfield. 1979. Southern race of Xantus' Murrelet breeding on Santa Barbara Island, California. Western Birds 10:81-82.
- Yocom, C.F., and S.W. Harris. 1975. Birds of northwestern California. Humboldt State Univ., Arcata, CA.
- 44 Zerlang, L., and T. Fraser. 1940. A large set of the Black Oystercatcher. Condor 42:264.

APPENDIX A: DATA ARCHIVING

This catalog is a summary of data from many sources and more detailed information on many of these sites is available. This information may include more detailed maps, notes on reproductive success, vegetation, marine mammals, pelagic birds in the area, land ownership, access, management problems, and photographs. We have provided this section for those who may desire access to this information.

Field data collected by the U.S. Fish and Wildlife Service in 1979 and 1980 were recorded onto Colony Status Records (Figure 5) or into a field notebook arranged by species. Other data compiled in this catalog are referenced as to their sources. This catalog can serve as an index to the Colony Status Records since their numbering systems are identical. Copies of the Colony Status Records and our field notebook have been deposited at:

Bureau of Land Management
Pacific OCS Office
1340 W. 6th Street
Los Angeles, CA 90017

California Academy of Sciences
Golden Gate Park
San Francisco, CA 94118

California Dept. of Fish and Game
Wildlife Investigations
1416 Ninth Street
Sacramento, CA 95814

Patuxent Research Lab
U.S. Fish & Wildlife Service
Laurel, MD 20810

Colonial Bird Register
Laboratory of Ornithology
Cornell University
159 Sapsucker Woods Road
Ithaca, NY 14850

U.S. Fish & Wildlife Service
Lloyd 500 Building, Suite 1692
500 N.E. Multnomah Street
Portland, OR 97232

Photographs will be of great value in the future, particularly for evaluating changes in habitat and changes in populations of Brandt's Cormorants and Common Murres. Some black and white prints and some color slides are included with each set of Colony Status Records. Nearly all of these photographs were taken during our study. All remaining photographs and all black-and-white negatives taken during our study have been divided between the U.S. Fish and Wildlife Service office in Portland and the California Academy of Sciences in San Francisco. These were divided so that nearly identical photographs are at both locations. Important photographs from other sources have also been copied and included when possible or reference to their existence has been made on the Colony Status Records under the section "Photo Coverage".

More historical data probably exist than have been summarized in this study and future studies may obtain much new information. We consider this study a step toward a better understanding of marine birds and we welcome any comments, corrections, or additions to our files or to this report. Comments should be addressed to our Portland office.

 Colony Status Record
U.S. Fish & Wildlife Service

Area Number 477 007
to be assigned by office

Colony Name Piedras Blancas Rock Field No. _____ Observer(s) Nelson, Sowls
Map Piedras Blancas, Ca. Lat. 35°39'52" Long. 121°17'18" Time 2/26 9:40 Date { 6/26/79 - boat
8/2/79 - aerial
Weather 6/26 overcast, light breeze from NW, swells 6', waves 1'.

| Species | No. Nests <small>use codes below</small> | No. Birds <small>use codes below</small> | Remarks <small>(estimated minimum & maximum, egg & chick status, etc.)</small> |
|--------------------------|---|---|---|
| Fork-tailed Storm Petrel | _____ | _____ | _____ |
| Leach's Storm Petrel | _____ | _____ | _____ |
| Ashy Storm Petrel | _____ | _____ | _____ |
| Brown Pelican | _____ | <u>roost</u> | _____ |
| Cormorant (unid.) | _____ | <u>roost</u> | } <u>count made from aerial slide taken 8/2/79.</u> <u>most nests in a "bowl" on the S.W. side of</u> <u>the island - these cannot be counted from</u> <u>the mainland or from a boat. data qual. = II.</u> |
| Brandt's Cormorant | <u>C 680</u> | <u>1360</u> | |
| Double-crested Cormorant | _____ | _____ | |
| Pelagic Cormorant | _____ | _____ | _____ |
| Black Oystercatcher | _____ | _____ | _____ |
| Gull (unid.) | _____ | _____ | _____ |
| Glaucous-winged Gull | _____ | _____ | } <u>Birds were counted that appeared to be on</u> <u>territories, number estimated conservative.</u> <u>Data quality = III. 15 nests est. on N. side,</u> <u>9 nests est. on western side & 4 nests est.</u> <u>on S.E. side.</u> |
| Western Gull | <u>E 28</u> | _____ | |
| Least Tern | _____ | _____ | |
| Forster's Tern | _____ | _____ | _____ |
| Caspian Tern | _____ | _____ | _____ |
| Common Murre | _____ | _____ | _____ |
| Pigeon Guillemot | <u>E 25</u> | _____ | } <u>Good habitat, 24 birds either on the island</u> <u>or just offshore.</u> |
| Marbled Murrelet | _____ | _____ | |
| Xantus' Murrelet | _____ | _____ | _____ |
| Cassin's Auklet | _____ | _____ | _____ |
| Rhinoceros Auklet | _____ | _____ | } <u>One seen flying N. from island on 6/25 in</u> <u>the evening. Reynolds, CDF&G est. 1 pr. here</u> <u>in 1970. Mark Rauzon, USFWS - seaotter prog.</u> <u>has seen no more than 2-3 puffins here. Rock</u> <u>does not appear to have soil, but it may be</u> <u>present and covered with guano.</u> |
| Tufted Puffin | <u>E 1</u> | _____ | |
| _____ | _____ | _____ | |

Recommended Classification: Colony Complex _____ Colony X Sub-colony _____ Roost Area _____

MARINE MAMMALS

| | | | |
|------------------------|-------|--------------|--|
| Steller Sealion | _____ | _____ | } <u>Hauled out primarily on the west, south &</u> <u>eastern sides of the island. Boat distance</u> <u>must be maintained to avoid disturbance &</u> <u>landing on island at this time not possible</u> <u>without causing disturbance.</u> <u>Hauled out on intertidal rock E. of island.</u> |
| California Sealion | _____ | <u>E 500</u> | |
| Northern Elephant Seal | _____ | _____ | |
| Harbor Seal | _____ | <u>E 10</u> | |

Use these abbreviations to describe numbers. Use C & E whenever possible. See P & K. T = Total Count, C = count, E = estimate, P = probably present (state reason under animal), K = present or nesting, B = breeding, N = non-nesting.

Figure 5. Colony Status Record, front.

AREA Number 477 007

Pierdas Blancas Rock
Description of Colony

DATE 6/26 & 8/2/79

Access Excellent landing beach (see map), unless S.W. swell at Pierdas Blancas lighthouse. Mainland adjacent property currently USFWS - seaotter research station, phone (408) 375-2278. Landing on island would be difficult, but not recommended due to disturbance problem with sealions.

Vegetation & Physiographic Characteristics This large island has a large bowl on the S.W. side where most of the Brandt's Cormorants are nesting. A rock stack is at the north end. No vegetation or soil is evident but soil may be covered by guano. See photographs.

Human Activity Probably boats from San Simeon fish off shore and the people at Pierdas Blancas they have seen airplanes buzz the island disturbing the sealions. This area is within the California Seaotter Game Reserve - flying below 1000 ft. is prohibited. Mammalian Predators, Livestock, etc. probably none.

Census Methods & Data Status Island passed by in zodiac on 6/25, 6/26 island was zodiaced on the N., W. & S. sides - E. side could be seen well also. Distance was kept larger than usual so as not to disturb sealions. August 2, 1979 the island was photographed through the open window of a Cessna 182. Aerial photos used for counts of Brandt's Cor.

~~See also XXXXXXXXXX~~ For future surveys it is recommended the island be watched from mainland for a long period when Tufted Puffins should be feeding chicks. Aerial photos work well for Brandt's & boating is necessary for Western Gulls & for Pelagic Cormorants. Island should be landed on if disturbance to sealions & birds is avoided.

Photo Coverage Aerial color slides & B+W's taken from 500-800 ft. w/ a 70-210 zoom & a 300 mm len @ 1/1000 of a sec. Photos through open window of Cessna 182. Permission to fly below 1000 ft. must be obtained from CDF&G prior to flight.

Overall Evaluation of Colony Regionally a large colony and a major hauling area for sealions. At present this may be the southernmost breeding point of the Tufted Puffin on the west coast.

Supplemental Material & Data Attached (list) Photographs attached.

General Colony Sketch




Figure 5 (continued). Colony Status Record, back.



"For fearlessness, pluck and dash the Tufted Puffins have no equal on the island" - Harold Heath (1915).

APPENDIX B: OBSERVATION POINTS FOR SEABIRD COLONIES

Birdwatching is a major form of recreation throughout North America. It contributes to the enjoyment and education of people and furthers their appreciation of the natural world. Hatler, Campbell and Dorst (1978) describe the philosophy of birdwatching as follows:

“It wasn’t the gold I was wanting, as much as just finding the gold.” This line, from one of the most famous poems by Robert Service, alludes to the passion for discovering existing to some extent in everyone. It is likely that the widespread appeal of birdwatching is based, to a considerable degree, on its potential for providing thrills of discovery at all levels of “importance.” At any moment the observer may discover a species he has not seen before, a significant personal event because it represents a broadening of one’s experience. Or, he may discover a bird which few people have seen in that season or at that locality. Then, oh happy day, there is the occasional discovery of a species which has never, or only rarely, been seen previously in a province, country, or even continent. The birdwatcher may also contribute to knowledge of the ecology of a species by observing birds involved in their various annual activities. Finally, even if a series of observations does not include anything unusual, the observer will likely have discovered, or rediscovered, the sense of satisfaction which comes from relating to other creatures with which we share the Earth.

Birders in California have the opportunity to view not only large colonies of seabirds but also several species of marine birds that are difficult to see, either because they are uncommon or because they rarely come close to land. However, the well-meaning student of natural history can easily disrupt seabird colonies in his or her quest to observe or photograph nesting seabirds. Recognizing the rewards of observing seabirds and the need for information about viewing opportunities, as well as the disturbance problems that can occur, we have included this section. We have listed viewing points where large seabird colonies can be observed as well as locations where less common species can be seen without causing disturbances. Readers are encouraged to read the section on human disturbance (page 5) before visiting these sites. The use of binoculars or better yet, a spotting scope are essential.

One of the best ways to view marine birds is through pelagic boat trips, regularly offered at several ports in California. Pelagic trips result in little or no disturbance to birds and the viewer can see several species that are infrequently observed from land, such as the albatross, storm-petrels, and shearwaters. Interested parties should contact local chapters of the Audubon Society for information.


VIEW POINT: Point St. George or Pebble Beach Drive, Crescent City.

COLONY: Castle Rock (325 006).

ACCESS: From Crescent City take any of the several arterial roads leading west from Highway 101 to Pebble Beach Drive. The best locations for viewing are any of the large pullouts near Point St. George (see map). No attempt should be made to land on Castle Rock since a great deal of disturbance would occur.

SEABIRD SPECIES:

Castle Rock is a breeding ground for 12 species of seabirds, but because of its distance from shore, birds can only be seen with a spotting scope. Point St. George is noteworthy because of excellent views offered of Aleutian Canada Geese. The geese are present in greatest numbers in the spring. Up to nearly 1,500 birds can be seen in April. The dawn departure of the geese from Castle Rock to their mainland feeding grounds is a great wildlife spectacle. This is best viewed from anywhere on Point St. George.



VIEW POINT: False Klamath Rock Overlook, Redwood National Park.

COLONY: False Klamath Rock (325 010).

ACCESS: Take the Lagoon Creek pullout from Highway 101, approximately 40 miles south of the Oregon Border and 25 miles north of Orick. A coastal hiking trail leads to an overlook of False Klamath Rock.

SEABIRD SPECIES:


Cormorants - All three species can be seen, particularly during summer.

Brown Pelican - Non-breeding birds are in the area during summer and early fall.

Black Oystercatcher - A few are present in the area all year.

Common Murre - Thousands nest on False Klamath Rock in summer. (May to early August). Birds are sporadically present from November to May.

Pigeon Guillemot - A few birds are in the area from mid-April until September. They are most frequently seen on the water.




VIEW POINT: Prairie Creek Redwoods State Park, Orick.

SPECIES: Marbled Murrelet inland nesting location.

ACCESS: Take the marked turnoff to the Prairie Creek Redwoods State Park headquarters, 30 miles north of Eureka on Highway 101 and about 7 miles north of the town of Orick.

SEABIRD SPECIES:

This is one of the best locations to observe the flight of Marbled Murrelets in the forests. The local population can be seen at dawn from the entrance station circling the tops of the nearby redwoods. In the evening the birds return and their high pitched whistles can be heard in the forest stillness. The best opportunity to observe the murrelets is during the months of May through July. Contact State Park personnel when arriving at the park for more information.



VIEW POINT: Elk Head, Trinidad State Beach.

COLONIES: Green Rock (325 020), Puffin Rock (325 021), and Flatiron Rock (325 023).

ACCESS: Take Trinidad exit off Highway 101, approximately 18 miles north of Eureka. Drive to Trinity Ave., about .2 miles from the exit, and turn right. Proceed .8 mile to a parking lot on the west side of the road. Walk down the trail from the northwest corner of the parking lot to Megwil Point (see map), or near Elk Head to view Flatiron Rock.

SEABIRD SPECIES:

Cormorants - All three species can be seen, particularly during summer.

Brown Pelican - Non-breeding birds are in the area during the summer and early fall.

Black Oystercatcher - A few are present in the area all year.


Western Gull - Birds are present in the area all year.

Common Murre - Thousands nest on Green Rock and Flatiron Rock from May to early August. Birds are sporadically present from November to May.

Pigeon Guillemot - A few birds are present in the area from mid-April until September. They are most often seen on the water.

Rhinoceros Auklet - A few are present on Green Rock from mid-April to mid-August. They are rarely seen except early in the morning.

Tufted Puffin - A few are present on both Green and Puffin Rocks during summer. They are most likely to be seen standing by burrow entrances in the morning.



VIEW POINT: Stump Beach, Salt Point State Park.

COLONY: Cannon Gulch to Stump Beach (404 029).

ACCESS: Salt Point State Park is about 20 miles north of Jenner on Highway 1 and about 80 miles north of San Francisco. A parking area off the highway at the Stump Beach picnic grounds is about 2 miles north of the Salt Point State Park campground entrance. Walk the access trail to the beach, then head up the bluffs on the trail south of the Stump Beach cove.

SEABIRD SPECIES:

Pelagic Cormorants nest on the northern mainland cliffs of Stump Beach. Take extreme care not to disturb nesting birds. Vantage points at the bluff's edge can be found to observe Pelagic Cormorants nesting during June, July and August. A small population of Pigeon Guillemots is also present in the summer. Binoculars and spotting scopes are recommended for better viewing.



VIEW POINT: Cliff House, San Francisco.

COLONY: Seal Rocks (429 009).

ACCESS: The Cliff House overlooks the ocean from a bluff just north of Golden Gate Park on the west side of San Francisco. Access is by bus or private car from downtown. The best viewing is from a platform below the restaurants, where coin-operated spotting scopes are available. The Golden Gate National Recreation Area maintains an interpretive center there.

SEABIRD SPECIES:

Relatively few birds use this site for nesting, but good views of breeding Western Gulls and occasionally of Black Oystercatchers can be made there. During the nonbreeding season, especially in late summer and fall, Seal Rocks are used for roosting by hundreds of Brown Pelicans and Brandt's Cormorants, as well as by Heermann's and Western Gulls. Seal Rocks is also one of the best locations on the California coast to view California Sea Lions and occasionally Steller Sea Lions.



VIEW POINT: Seal and Bird Rock Picnic Area, 17 Mile Drive.

COLONY: Bird Rock (454 006).

ACCESS: Via 17 Mile Drive near Carmel, a scenic private road. There is a charge to enter and a map showing points of interest is provided. Bird Rock can be seen well since it is close to land and coin-operated telescopes are available.

SEABIRD SPECIES:

Brandt's Cormorant - This is the principal nesting species at this colony. Large numbers of Cormorants are present during summer.

Western Gull - A few nest on Bird Rock in summer. These and several other gulls winter in the area.

Brown Pelican - Non-breeding birds can be seen here in summer and fall.


Black Oystercatcher - A few are probably present all year.

MARINE MAMMALS:

California Sea Lion - Large numbers haul out on Bird Rock. This is an excellent place to see sea lions.

Harbor Seal - A few are present year-round. They are most likely to be seen hauled out on small intertidal rocks.

Sea Otter - A few are present in the area year-round.



VIEW POINT: Bird Island Overlook, Point Lobos State Park.

COLONY: Bird Island (454 009).

ACCESS: Enter Point Lobos State Park four miles south of Carmel off Highway 1. Roads and trails to Bird Island Overlook are clearly marked. State park service naturalists offer guided tours, including one to see Bird Island.

SEABIRD SPECIES:

Brandt's Cormorant - This is the principal nesting species at this colony. Large numbers are present during summer, fewer in winter.

Pelagic Cormorant - Small numbers nest at several locations in this state park. Sand Hill Cove, a short distance north of Bird Island, is a good spot to see this species.

Brown Pelican - Non-breeding birds can be seen in the area during summer and fall.

Black Oystercatcher - A few are probably present all year.

Western Gull - Low numbers nest in the area. These and other species of gulls winter in the area.

MARINE MAMMALS:

California Sea Lion - These can be seen at Sea Lion Rocks, a short distance north of Bird Island.

Harbor Seal - A few are present in the area all year.

Sea Otter - A few are present in the area all year.





VIEW POINT: Shell Beach

COLONY: Shell Beach Rocks (477 035).

ACCESS: Highway 101 south of San Luis Obispo to Shell Beach. Go to the south end of town and take any residential street west to the shoreline.

SEABIRD SPECIES:

Shell Beach Rocks are an excellent location for viewing breeding Pigeon Guillemots, Black Oystercatchers, and Western Gulls. In 1980 this was one of only two sites in California where Heermann's Gulls attempted to nest. During summer, fall, and winter months, Shell Beach Rocks are used by many Brown Pelicans, Brandt's Cormorants, Heermann's Gulls, and Western Gulls for roosting. At low tide more than 100 Harbor Seals can usually be easily observed.



COLONIES: East Anacapa Island (502 009) and Santa Barbara Island (524 008).

ACCESS: Access to the Channel Islands is by charter boat from Ventura and Los Angeles, California. The waters on the north side of West Anacapa Island are closed to boats out to nine fathoms during the nesting season. All interested persons are encouraged to contact the National Park Service for more information at:



Channel Islands National Park
1699 Anchors Way
Ventura, CA 93003
(805) 644-8157

SEABIRD SPECIES:

A diverse assemblage of marine birds and mammals can be seen in the Channel Islands. At present both East Anacapa Island and Santa Barbara Island have trails to accommodate visitors. Colonies of Western Gulls can be observed at both islands and breeding Brown Pelicans may be observed from boats offshore of West Anacapa Island (502 007). For overnight camping, permits must be obtained from the National Park Service.



COLONY: Farallon Islands (429 012)

ACCESS: From San Francisco by tour boat chartered by local natural history groups. No landings are allowed. For more information contact:



Refuge Manager
San Francisco Bay National Wildlife Refuge
Box 524
Newark, CA 94560
(415) 792-0222

SEABIRD SPECIES:

Teeming with many thousands of breeding seabirds, the Farallon Islands contain the most important seabird colonies of the California coast. Although visits to the islands are restricted, a boat is an excellent vantage point to observe the bird life of the Farallones.

Appendix C

Below are listed in alphabetical order the names of seabird colonies listed in this catalog. Names given are as on U.S. Geological Survey maps unless they are in quotation marks. Names in quotation marks are of sites which are not named on U.S.G.S. maps. These names are either locally used or were assigned by us or previous investigators.

| Name | Colony | Lat., Long. | Page |
|---------------------------------------|---------|-------------------------|------|
| Agua Hedionda | 524 004 | 33°08'45"N, 117°19'30"W | 322 |
| Alameda Creek | 429 015 | 37°36'59"N, 122°07'20"W | 192 |
| Albion Cove to Navarro River | 379 029 | 39°12'30"N, 123°46'20"W | 136 |
| Alcatraz Island | 429 036 | 37°49'34"N, 122°25'20"W | 208 |
| Aliso Creek | 525 007 | 33°30'35"N, 117°45'12"W | 324 |
| Anacapa Island - East | 502 009 | 34°00'46"N, 119°25'26"W | 288 |
| Anacapa Island - Middle | 502 008 | 24°00.19"N, 119°23'43"W | 288 |
| Anacapa Island - West. | 502 007 | 34°00'54"N, 119°21'57"W | 286 |
| Anaheim Bay and Surfside Beach | 524 009 | 33°44'05"N, 118°05'34"W | 302 |
| "Anderson Canyon Rock" | 454 016 | 36°06'58"N, 121°36'58"W | 224 |
| Anderson Cliffs | 379 013 | 39°52'30"N, 123°54'30"W | 120 |
| Ano Nuevo Island | 429 023 | 37°06'30"N, 122°20'09"W | 194 |
| Arched Rock | 404 006 | 38°25'53"N, 123°07'32"W | 150 |
| Bair Island | 429 016 | 37°31'43"N, 122°13'05"W | 192 |
| Batiquitos Lagoon | 524 005 | 33°05'25"N, 117°17'30"W | 322 |
| Bay Point Area | 501 016 | 34°02'N, 120°19'W | 280 |
| Bench Mark 125 to Timber Cove | 404 031 | 38°32'20"N, 123°17'W | 168 |
| "Bench Mark 227x" | 454 029 | 36°23'21"N, 121°54'13"W | 230 |
| "Bench Mark 247" | 454 036 | 36°02'N, 121°34'45"W | 234 |
| Bird Island | 429 007 | 37°49'27"N, 122°32'09"W | 186 |
| Bird Island | 454 009 | 36°30'25"N, 121°56'33"W | 218 |
| Bird Rock | 404 010 | 38°13'49"N, 122°59'35"W | 154 |
| Bird Rock | 454 006 | 36°35'31"N, 121°57'59"W | 216 |
| Bird Rock | 524 010 | 33°27'04"N, 118°29'04"W | 310 |
| Bird Rock and N.W. San Clemente Is. | 524 012 | 33°02'N, 118°35'W | 314 |
| Bird Rock, mainland point across from | 477 016 | 35°52'37"N, 121°26'59"W | 246 |
| Black Point to Stewarts Point | 404 026 | 38°40'N, 123°25'15"W | 164 |
| Blank Rock | 325 024 | 41°03'15"N, 124°09'26"W | 80 |
| Bodega Head | 404 038 | 38°18'N, 123°03'45"W | 176 |
| Bodega Rock | 404 008 | 38°17'48"N, 123°02'50"W | 150 |
| Bolsa Chica Beach | 524 006 | 33°42'05"N, 118°03'05"W | 304 |
| "Bonee Cliffs" | 379 031 | 39°07'N, 123°42'45"W | 138 |
| Bonita Cove | 429 027 | 37°49'30"N, 122°31'W | 198 |
| Bridgeport Landing | 379 033 | 39°03'45"N, 123°41'50"W | 140 |
| Brothers, The | 429 040 | 37°57'47"N, 122°26'W | 210 |
| Buena Vista Lagoon | 525 008 | 33°10'30"N, 117°21'15"W | 324 |
| "Burns Creek Rocks" | 454 017 | 36°08'29"N, 121°39'28"W | 224 |
| "Button Rock" | 325 054 | 41°03'N, 124°08'W | 100 |
| Cap Rock | 325 054 | 41°03'N, 124°08'W | 100 |
| Cape San Martin | 477 003 | 35°53'17"N, 121°27'55"W | 240 |
| Cape Vizcaino | 379 002 | 39°43'34"N, 123°49'55"W | 108 |
| Cannon Gulch to Stump Beach | 404 029 | 38°35'30"N, 123°20'30"W | 166 |
| Casket Rock | 379 009 | 39°07'49"N, 123°43'39"W | 116 |
| Caspar Anchorage | 379 023 | 39°22'N, 123°49'10"W | 128 |
| Castle Rock | 325 006 | 41°43'37"N, 124°15'W | 66 |
| Castle Rock | 501 005 | 34°03'17"N, 120°26'17"W | 268 |
| Castle Rocks & Mainland | 454 010 | 36°22'35"N, 121°54'25"W | 220 |
| Cavanaugh Cove to Gunderson Rock | 379 030 | 39°08'N, 123°44'W | 138 |
| Cayucas Point, island south of | 477 025 | 35°26'46"N, 120°55'51"W | 250 |
| "Chadbourne Rocks" | 379 019 | 39°37'02"N, 123°47'W | 124 |

Appendix C (Continued)

| Name | Colony | Lat., Long. | Page |
|--|--------------------|---|------------|
| Chris Rocks | 379 003 | 39°42'51"N,123°48'07"W | 110 |
| Collins Landing to Gualala River | 404 023 | 38°46'N,123°32'40"W | 160 |
| Coche Pt. to Cavern Pt. | 502 012 | 34°2'N,119°36'50"W to 3'20"N,119°38'45"W | 292 |
| Cone Rock | 325 001 | 41°58'21"N,124°13'02"W | 62 |
| Cooper Point and Islands | 454 031 | 36°14'55"N,121°50'10"W | 232 |
| "Cormorant Hotel" | 325 056 | 40°02'10"N,124°04'50"W | 102 |
| "Cormorant Rock" | 325 015 | 41°08'32"N,124°09'39"W | 74 |
| Coyote Creek | 429 019 | 37°28'41"N,122°02'51"W | 194 |
| Coyote Hills | 429 017 | 37°32'48"N,122°07'28"W | 192 |
| Davenport to Point Santa Cruz | 454 021 | 36°58'N,122°07'W | 226 |
| Del Mar | 545 006 | 32°33'25"N,117°07'48"W | 336 |
| Del Mar Point | 404 024 | 38°15'N,123°31'W | 160 |
| Destroyer Rock | 501 009 | 34°36'10"N,120°38'40"W | 272 |
| Destroyer Rock, mainland and rocks east of "Devils Basin" | 501 010 379 007 | 34°36'N,120°38'26"W 39°10'14"N,123°44'50"W | 272 114 |
| Devil's Slide Rock and headlands | 429 014 | 37°34'28"N,122°31'39"W | 192 |
| Diablo Canyon Nuclear Power Plant South | 477 030 | 35°12'07",120°50'39"W | 254 |
| Diablo Rock & Adjacent Mainland | 477 029 | 35°12'36"N,120°51'38"W | 254 |
| Dillon Beach Rocks | 404 009 | 38°16'26"N,122°59'11"W | 152 |
| Dolan Rock | 454 018 | 36°05'06"N,121°37'02"W | 224 |
| Double Point Rocks | 429 003 | 37°56'51"N,122°47'08"W | 184 |
| "Double Rock" | 325 054 | 41°03'00"N,124°08'W | 100 |
| "Double Rock Region" | 477 031 | 35°11'39"N,120°50'29"W | 256 |
| Duncan Point to Arched Rock | 404 037 | 38°22'30"N,123°05'W | 174 |
| "Easy Triangle Rocks" | 325 047 | 41°40'22"N,124°08'30"W | 94 |
| Eel Rock Cliffs | 429 031 | 37°24'15"N,122°25'30"W | 204 |
| "Elephant Rocks Complex" | 404 041 | 38°11'N,122°58'W | 178 |
| Elkhorn Slough | 454 003 | 36°49'04"N,121°46'30"W | 214 |
| False Cape Rocks | 325 040 | 40°30'38"N,124°23'40"W | 40 |
| False Klamath Rock | 325 010 | 41°35'40"N,124°06'36"W | 70 |
| Farallon Islands | 429 012 | 37°41'53"N,123°00'05"W | 188 |
| "Fish Rock Cove" | 404 022 | 38°47'45"N,123°35'20"W | 158 |
| Fish Rocks | 404 003 | 38°48'N,123°35'31"W | 146 |
| Flatiron Rock | 325 023 | 41°03'34"N,124°09'39"W | 80 |
| Flint Rock Head | 325 011 | 41°31'31"N,124°05'00"W | 70 |
| Footsteps Rock | 325 050 | 41°37'00"N,124°07'10"W | 94 |
| Fossil Point | 477 034 | 35°10'26"N,120°43'26"W | 256 |
| "Georgia Pacific" | 379 022 | 39°27'N,123°48'45"W | 128 |
| Gerstle Cove to Stillwater Cove | 404 030 | 38°33'N,123°18'45"W | 168 |
| Goat Island | 379 006 | 39°18'28"N,123°48'49"W | 112 |
| Green Rock | 325 020 | 41°04'32"N,124°09'48"W | 78 |
| Greyhound Rock to Davenport | 429 035 | 37°03'N,122°15'W | 206 |
| Grimes Point | 454 033 | 36°12'20"N,121°44'15"W | 232 |
| Guadalupe Slough | 429 020 | 37°28'12"N,122°04'52"W | 194 |
| Gualala Point Island | 404 004 | 38°45'04"N,123°31'42"W | 148 |
| "Guillemot Island Area" | 454 023 | 36°31'25"N,121°56'47"W | 226 |
| Gull Island | 524 001 | 33°57'01"N,119°49'28"W | 300 |
| Gull Rock | 404 035 | 38°25'30"N,123°07'10"W | 172 |
| Gull Rock Area | 429 025 | 37°52'35"N,122°37'W | 196 |
| "Halfmoon Rock" | 325 054 | 41°03'N,124°08'W | 100 |
| Hardy Rock & Union Landing | 379 017 | 39°42'20"N,123°38'30"W | 124 |
| Harris Pt. to Cuyler Harbor | 501 015 | 34°04'N,120°22'W | 278 |
| High Tip | 379 012 | 39°55'30"N,123°57'10"W | 118 |
| "Horseshoe Cove" | 404 028 | 38°36'30"N,123°22'10"W | 166 |

Appendix C (Continued)

| Name | Colony | Lat., Long. | Page |
|--|---------|-------------------------------|------|
| Hunter Rocks | 325 002 | 41° 57' 22" N, 124° 12' 41" W | 62 |
| Huntington Beach | 525 001 | 33° 38' 43" N, 117° 59' 02" W | 320 |
| Hurricane Point Rocks | 454 011 | 36° 21' 40" N, 121° 54' 25" W | 220 |
| "Iverson Landing" | 404 002 | 38° 50' 39" N, 123° 38' 37" W | 144 |
| Kibesillah Rock | 379 004 | 39° 34' 49" N, 123° 46' 51" W | 110 |
| La Cruz Rock | 477 006 | 35° 42' 23" N, 121° 18' 45" W | 242 |
| La Jolla | 545 009 | 32° 51' 00" N, 117° 15' 55" W | 338 |
| Lafler Rock & Mainland | 454 034 | 36° 12' N, 121° 43' 36" W | 232 |
| Lake Talawa Beach | 325 005 | 41° 50' 03" N, 124° 13' 18" W | 64 |
| "Larus Rock" | 477 014 | 35° 57' 44" N, 121° 29' 01" W | 246 |
| "Last Chance Rock" | 325 049 | 41° 38' 05" N, 124° 07' 30" W | 94 |
| Limantour Estero | 404 013 | 38° 01' 52" N, 122° 55' 53" W | 154 |
| Lion Rock | 477 011 | 35° 31' 01" N, 120° 52' 15" W | 244 |
| Lion Rock at Point Sal | 501 008 | 34° 53' 55" N, 120° 39' 50" W | 272 |
| "Little Pewetole Rock" | 325 022 | 41° 04' N, 124° 09' W | 78 |
| Little River Rock | 325 035 | 41° 02' 08" N, 124° 07' 16" W | 84 |
| Lobos Rocks | 454 025 | 36° 27' 18" N, 121° 56' 10" W | 228 |
| Lobos Rock & Lands End | 429 029 | 37° 47' 15" N, 122° 30' 20" W | 200 |
| Lopez Rock | 454 020 | 36° 01' 34" N, 121° 34' 46" W | 226 |
| Los Panasquitos Lagoon | 545 001 | 32° 55' 49" N, 117° 14' 54" W | 328 |
| "Luffenholtz Rock" | 325 054 | 41° 03' N, 124° 08' W | 100 |
| Mallo Pass Creek | 379 034 | 39° 02' 20" N, 123° 41' 50" W | 140 |
| Martin's Beach | 429 033 | 37° 22' N, 122° 24' 30" W | 204 |
| McWay Rocks | 454 015 | 36° 09' 46" N, 121° 40' 44" W | 222 |
| Mendocino | 379 025 | 39° 18' 10" N, 123° 47' 50" W | 132 |
| Mendocino Bay | 379 026 | 39° 17' 30" N, 123° 47' 40" W | 132 |
| Millers Point Rocks | 429 002 | 37° 58' 53" N, 122° 48' 35" W | 184 |
| Mission Bay | 545 002 | 32° 46' 42" N, 117° 13' 46" W | 330 |
| Mistake Point to Big White Rock | 379 014 | 39° 51' 30" N, 123° 53' 30" W | 120 |
| "Moat Cove" | 404 018 | 38° 53' 10" N, 123° 41' W | 156 |
| "Molera Rock" | 454 030 | 36° 16' 45" N, 121° 51' 30" W | 232 |
| Morro Rock and Pillar Rock | 477 026 | 35° 22' 13" N, 120° 52' 08" W | 252 |
| "Mr'rp Rock" | 325 054 | 41° 03' N, 124° 08' W | 100 |
| Mugu Lagoon | 502 006 | 34° 06' 08" N, 119° 06' 04" W | 284 |
| Muir Beach Headlands to Tennessee Cove | 429 026 | 37° 51' 00" N, 122° 33' 45" W | 198 |
| Newport Bay | 525 002 | 33° 38' 46" N, 117° 53' 08" W | 320 |
| "Newport Rocks" | 379 021 | 39° 34' 49" N, 123° 46' 51" W | 126 |
| "North Pismo Beach Rocks" | 477 036 | 35° 08' 57" N, 120° 39' 23" W | 258 |
| North San Diego Bay | 545 003 | 32° 44' N, 117° 12' W | 332 |
| "Northwest Cape Rocks" | 404 032 | 38° 30' 40" N, 123° 15' 17" W | 170 |
| Oakland International Airport | 429 011 | 37° 43' 21" N, 122° 13' 46" W | 188 |
| Old Arcata Wharf | 325 038 | 40° 50' 59" N, 124° 05' 58" W | 86 |
| Ormond Beach | 502 005 | 34° 08' 13" N, 119° 10' 56" W | 284 |
| Oso Flaco Lake | 477 037 | 35° 01' 42" N, 120° 37' 40" W | 258 |
| Palmer's Point to Scotty Point | 325 052 | 41° 07' N, 124° 09' W | 96 |
| "Partington Ridge North" | 454 014 | 36° 10' 06" N, 121° 41' 14" W | 222 |
| "Partington Ridge South" | 454 035 | 36° 00' N, 121° 40' 40" W | 234 |
| "Peaked Hill" | 404 034 | 38° 25' 45" N, 123° 07' 10" W | 172 |
| Pecho Rock | 477 032 | 35° 10' 45" N, 120° 49' 00" W | 256 |
| Pescadero Rock | 454 022 | 36° 33' 43" N, 121° 56' 33" W | 226 |
| Pfeiffer Point | 454 032 | 36° 35' 18" N, 121° 47' 35" W | 232 |
| Piedras Blancas | 477 007 | 35° 39' 52" N, 121° 17' 18" W | 242 |
| Pier 45 | 429 037 | 37° 48' 34" N, 122° 25' W | 208 |
| Pigeon Point | 429 034 | 37° 10' 55" N, 122° 23' 20" W | 206 |
| Pillar Point | 429 030 | 37° 23' N, 122° 29' 55" W | 202 |
| Pilot Rock | 325 026 | 41° 03' 06" N, 124° 09' 09" W | 82 |
| Pinnacle Point Area | 454 007 | 36° 31' 25" N, 121° 57' 14" W | 216 |
| Pinnacle Rock | 404 039 | 38° 18' 20" N, 123° 01' 10" W | 178 |

Appendix C (Continued)

| Name | Colony | Lat., Long. | Page |
|--|---------|--|------|
| Plaskett Rock | 477 002 | 35° 55'14"N, 121° 28'41"W | 238 |
| Plaskett Rock, small rocks and mainland N. and E. of | 477 001 | 35° 55'16"N, 121° 28'22"W | 238 |
| Point Arena | 404 017 | 38° 57'20"N, 123° 44'30"W | 156 |
| Point Arguello | 501 011 | 34° 38'N, 120° 38'49"W | 274 |
| Point Bennett, San Miguel Island | 501 014 | 34° 2'N, 120° 3'30"W | 276 |
| Point Bonita | 429 008 | 37° 48'55"N, 122° 31'40"W | 186 |
| Point Buchon | 477 009 | 35° 15'20"N, 121° 53'58"W | 242 |
| Point Cabrillo to Jack Peters Gulch | 379 024 | 39° 20'N, 123° 49'W | 130 |
| Point Conception | 501 013 | 34° 26'54"N, 120° 28'13"W | 274 |
| Point Diablo Bluffs and Needles | 429 028 | 37° 49'30"N, 122° 29'W | 200 |
| Point No Pass | 379 011 | 39° 58'40"N, 123° 59'40"W | 118 |
| Point Piedras Blancas, two rocks south of | 477 024 | 35° 39'30"N, 121° 16'02"W | 250 |
| Point Resistance | 429 024 | 37° 59'55"N, 122° 49'40"W | 196 |
| Point Reyes | 429 001 | 37° 59'26"N, 123° 59'24"W | 182 |
| Point Reyes Beach | 404 012 | 38° 04'00"N, 122° 58'47"W | 154 |
| Point San Simeon | 477 038 | 35° 38'N, 121° 12'W | 258 |
| Point St. George | 325 057 | 41° 47'N, 124° 15'W | 104 |
| Point St. George Lighthouse | 325 044 | 41° 50'N, 124° 22'W | 92 |
| Point Sur | 454 012 | 36° 18'22"N, 121° 53'39"W | 220 |
| Prince Island | 325 003 | 41° 57'04"N, 124° 12'41"W | 64 |
| Prince Island | 501 004 | 34° 03'29"N, 120° 20'00"W | 266 |
| Prisoner Rock | 325 027 | 41° 03'07"N, 124° 08'34"W | 82 |
| "Puffin Rock" | 325 021 | 41° 04'18"N, 124° 09'32"W | 78 |
| Punta del Ano Nuevo | 429 022 | 37° 07'07"N, 122° 20'09"W | 194 |
| "Pup Rock and Adjacent Mainland" | 477 028 | 35° 13'00"N, 120° 52'11"W | 254 |
| "Radar Station Rocks" | 325 051 | 41° 33'30"N, 124° 06'00"W | 96 |
| "Ragged Point Lodge Colony" | 477 022 | 35° 46'53"N, 121° 19'56"W | 250 |
| Red Rock | 429 039 | 37° 55'45"N, 122° 25'50"W | 210 |
| Redding Rock | 325 013 | 41° 20'29"N, 124° 10'26"W | 72 |
| Redwood Gulch, point north of | 477 017 | 35° 50'20"N, 121° 24'04"W | 246 |
| "Redwood Gulch Rock" | 477 005 | 35° 49'32"N, 121° 23'29"W | 242 |
| Redwood Gulch, Seastack south of | 477 018 | 35° 49'30"N, 121° 23'22"W | 248 |
| "Rock R" | 325 048 | 41° 40'00"N, 124° 08'30"W | 94 |
| "Rockland Landing North" | 454 037 | 36° 00'57"N, 121° 32'30"W | 234 |
| "Rockport Rocks" | 379 001 | 39° 44'10"N, 123° 50'00"W | 108 |
| Rocky Point | 454 028 | 36° 24'06"N, 121° 54'40"W | 230 |
| Rocky Point | 501 012 | 34° 33'45"N, 120° 38'11"W | 274 |
| "Russian Gulch" | 404 033 | 38° 28'N, 123° 09'36"W | 170 |
| "Russian River Rocks" | 404 005 | 38° 27'14"N, 123° 08'34"W | 148 |
| Salmon Creek | 404 007 | 38° 20'27"N, 123° 03'58"W | 150 |
| "Salmon Creek" | 477 020 | 35° 48'31"N, 121° 21'47"W | 248 |
| Salmon Creek, arched peninsula south of | 477 021 | 35° 48'05"N, 121° 21'14"W | 248 |
| San Elijo Lagoon | 525 006 | 33° 00'58"N, 117° 16'52"W | 322 |
| San Gabriel River | 524 005 | 33° 45'12"N, 118° 06'15"W | 304 |
| San Miguel Island | 501 006 | 34° 02'32"N, 120° 22'30"W | 270 |
| San Nicolas Island | 524 011 | 33° 14'30"N, 119° 30'30"W | 312 |
| San Pedro Rock | 429 013 | 37° 35'43"N, 122° 31'20"W | 192 |
| Sand Hill Cove | 454 008 | 36° 31'01"N, 121° 57'01"W | 218 |
| Santa Barbara Island | 524 008 | 33° 28'37"N, 119° 02'03"W | 306 |
| Santa Clara River | 502 003 | 34° 14'08"N, 119° 15'51"W | 284 |
| Santa Cruz Island | 502 010 | | 294 |
| Santa Cruz Island - Kinton Pt. to Diablo Pt. | 502 014 | 34° 0'30"N, 119° 53'W to 34° 3'N, 119° 45'W | 296 |
| Santa Margarita River | 525 003 | 33° 13'57"N, 117° 24'37"W | 320 |
| "Santa Maria River" | 501 001 | 34° 58'09"N, 120° 38'51"W | 262 |
| Santa Rosa Island, Sandy Pt. to Carrington Pt. | 501 007 | | 270 |
| Saunders Landing | 404 020 | 38° 51'13"N, 123° 30'05"W | 158 |


Appendix C (Continued)

| Name | Colony | Lat., Long. | Page |
|-----------------------------------|---------|---|------|
| Schoolhouse Creek to Albion River | 379 028 | 39° 15'N, 123° 46' 30''W | 134 |
| Scorpion Rock | 502 010 | 34° 02' 50''N, 119° 32' 47''W | 290 |
| Scotty Point to Megwill Point | 325 053 | 41° 05'N, 124° 09'W | 98 |
| “Sea Gull Rock” | 325 017 | 41° 05' 21''N, 124° 09' 07''W | 74 |
| “Sea Lion Rock” | 325 018 | 41° 05' 40''N, 124° 09' 49''W | 76 |
| Sea Lion Rock | 325 043 | 40° 19' 35''N, 124° 21' 38''W | 92 |
| Sea Lion Rocks | 404 001 | 38° 55' 07''N, 123° 43' 45''W | 144 |
| Sea Ranch | 404 025 | 38° 42'N, 123° 27' 30''W | 162 |
| Seal Cove to Lost Point | 524 013 | 32° 52'N, 118° 31'W to 32° 54' 10''N, 118° 32' 20''W | 316 |
| Seal Rocks | 429 009 | 37° 46' 42''N, 122° 30' 53''W | 186 |
| Seal Rock Cliffs | 429 032 | 37° 23'N, 122° 25'W | 204 |
| “Section 30 Cove” | 404 019 | 38° 52' 39''N, 123° 40' 10''W | 156 |
| Shag Rock | 524 007 | 33° 29' 15''N, 119° 02' 05''W | 306 |
| “Shell Beach Rocks” | 477 035 | 35° 09' 06''N, 120° 40' 11''W | 258 |
| Shell Wright Beach Rocks | 404 036 | 38° 25'N, 123° 06'W | 172 |
| Sister Rocks | 325 009 | 41° 39' 29''N, 124° 08' 47''W | 68 |
| Sisters, The | 429 041 | 37° 59' 22''N, 122° 26' 25''W | 210 |
| Smith and Whaler Islands | 477 033 | 35° 09' 00''N, 120° 45' 15''W | 256 |
| “Snag Rock” | 325 054 | 41° 03'N, 124° 08'W | 100 |
| “Soberanes Creek Rocks” | 454 026 | 36° 27' 18''N, 121° 55' 35''W | 228 |
| “Soberanes Point South” | 454 027 | 36° 26' 47''N, 121° 55' 35''W | 230 |
| Soldier Frank Point | 379 016 | 39° 45' 18''N, 123° 50' 15''W | 122 |
| “Sonoma-Marín County Line” | 404 040 | 38° 17' 20''N, 123° 00' 20''W | 178 |
| South San Diego Bay | 545 005 | 32° 36'N, 117° 07'W | 334 |
| “Split Rock” | 325 054 | 41° 03'N, 124° 08'W | 100 |
| Sponner’s Cove | 477 027 | 35° 16' 21''N, 120° 53' 57''W | 252 |
| “Sppit Rock” | 502 013 | 34° 02' 45''N, 119° 43' 30''W | 294 |
| Square Black Rock | 454 019 | 36° 04' 21''N, 121° 36' 35''W | 224 |
| Steamboat Rock | 325 042 | 40° 24' 54''N, 124° 24' 09''W | 90 |
| Stewarts Point to Rocky Point | 404 027 | 38° 39'N, 123° 38' 45''W | 164 |
| “Strawberry Cove” | 379 020 | 39° 35' 37''N, 123° 47' 10''W | 126 |
| Sugarloaf Island | 325 041 | 40° 26' 18''N, 124° 24' 41''W | 90 |
| Sutil Island | 524 009 | 33° 28' 50''N, 119° 02' 50''W | 308 |
| Sweetwater River | 545 008 | 32° 38' 30''N, 117° 06' 35''W | 336 |
| “Tepona Rock” | 325 054 | 41° 03'N, 124° 08'W | 100 |
| Terminal Island | 524 003 | 33° 57' 30''N, 118° 27' 30''W | 302 |
| Three Brothers & Hair Seal Rocks | 325 055 | 40° 19' 40''N, 124° 21' 58''W | 102 |
| Tijuana River Mouth | 545 006 | 32° 33' 25''N, 117° 07' 48''W | 336 |
| Tolowa Rocks | 325 007 | 41° 45' 15''N, 124° 14'W | 66 |
| Tomales Point | 404 011 | 38° 12' 13''N, 122° 57' 39''W | 154 |
| “Torre Canyon Rocks” | 454 013 | 36° 11' 25''N, 121° 42' 46''W | 222 |
| Trinidad Bay Rocks | 325 054 | 41° 03'N, 124° 08'W | 100 |
| Trinidad Head | 325 025 | 41° 03' 09''N, 124° 08' 58''W | 82 |
| Triplett Gulch | 404 021 | 38° 49'N, 123° 36' 15''W | 158 |
| “Unmapped Island” | 477 019 | 35° 48' 20''N, 121° 22' 26''W | 248 |
| Unnamed Point | 477 015 | 35° 57' 00''N, 121° 28' 51''W | 246 |
| Unnamed Rock | 477 004 | 35° 53' 05''N, 121° 27' 46''W | 240 |
| Unnamed Rocks | 477 010 | 35° 14' 40''N, 120° 53' 39''W | 244 |
| Unnamed Small Rocks | 325 046 | 41° 42'N, 124° 08'W | 92 |
| Usal Bay | 379 015 | 39° 48' 45''N, 123° 50' 30''W | 122 |
| Van Damme Cove | 379 027 | 39° 16' 10''N, 123° 47' 28''W | 132 |
| Venice Beach | 524 002 | 33° 57' 30''N, 118° 27' 30''W | 302 |
| Wedding Rock | 325 016 | 41° 08' 28''N, 124° 09' 32''W | 74 |
| Westport | 379 018 | 39° 38' 00''N, 123° 47' 10''W | 124 |
| “Whaler Island” | 325 045 | 41° 45'N, 124° 13'W | 92 |
| Wharf Rocks | 379 008 | 39° 07' 49''N, 123° 43' 24''W | 116 |

Appendix C (Continued)

| Name | Colony | Lat., Long. | Page |
|--------------------|---------------|------------------------|-------------|
| White Rock | 325 008 | 41°44'46"N,124°13'44"W | 60 |
| White Rock | 325 012 | 41°30'56"N,124°05'06"W | 70 |
| White Rock | 325 019 | 41°05'13N,124°09'33"W | 76 |
| White Rock | 379 010 | 39°05'42"N,123°43'11"W | 116 |
| Wilson Rock | 325 058 | 41°35'45"N,124°06'37"W | 104 |
| Yankee Point | 454 024 | 36°29'29"N,121°56'41"W | 228 |
| Yerba Buena Island | 429 038 | 37°48'34"N,122°22'15"W | 208 |
| "333 Point" | 379 032 | 39°05'N,123°42'30"W | 140 |
| "3 Rocks" | 477 023 | 35°45'06"N,121°19'07"W | 250 |
| "36 North" | 477 013 | 35°58'36"N,121°29'15"W | 246 |







DEPARTMENT OF THE INTERIOR U.S. FISH AND WILDLIFE SERVICE



As the Nation's principal conservation agency, the Department of the Interior has responsibility for most of our nationally owned public lands and natural resources. This includes fostering the wisest use of our land and water resources, protecting our fish and wildlife, preserving the environmental and cultural values of our national parks and historical places, and providing for the enjoyment of life through outdoor recreation. The Department assesses our energy and mineral resources and works to assure that their development is in the best interests of all our people. The Department also has a major responsibility for American Indian reservation communities and for people who live in island territories under U.S. administration.